











G G Schierle

Architectural Structures

G G Schierle
Architectural Structures
Excerpts

ISBN 0-18-195009-x

Copyright © G Schierle 1990-2006. All rights reserved

Portions of this document reproduce sections from the 2003 International Building Code, International Code Council, Falls Church, Virginia. All rights reserved.

AISC data, copyright © American Institute of Steel Construction, Inc.
Reprinted with permission. All rights reserved

USGS data copyright © United States Geological Survey, courtesy USGS

University of Southern California
Custom Publishing
C/O Chauncey Jemes
Los Angeles, CA 90089-2540
e-mail:jemes@usc.edu
Tel. 213-740-8946
Fax: 213-740-7686

Preface

To foster informed intuition for structures, this book has many illustrations visualizing structural behavior and to complement and clarify mathematical concepts. While the book is primarily targeted for students of architecture, it also serves as reference book for students of civil engineering, and professional architects, engineers, and contractors. The book is organized in six parts. Part I starts with an introduction of key developments in the historic evolution of structures and proceeds to introduce loads on buildings and basic systems to resist them. Part II introduces fundamentals: statics and strength of material, as well as analysis and design of basic elements, such as beams and columns. Part III introduces design methods: ASD and LRFD; design of masonry (ASD) and concrete (strength method); design for wind and seismic forces; as well as conceptual design, explored on case studies. Part IV introduces structure systems for horizontal spans, categorized by bending, axial, form, and tensile resistance. All systems are introduced with conceptual diagrams, describing their structural behavior and alternate options. Case studies describe their use in real projects. Part V introduces vertical structures in similar fashion. Part VI introduces material properties and details for wood, steel, masonry, concrete, and membrane structures. Appendices include math derivation, graphs and tables. Text and graphics are correlated on the same page for easy reading and comprehension. Prerequisites for the book are algebra, trigonometry, and Newtonian physics. The book can be used in courses of statics and strength of material, structure systems and structural materials. Math derivations visualized help understanding and to introduce concepts also to readers with more artistic or visual modes of learning. The book includes many graphs to streamline complex tasks. The graphs, which feature US and SI units to facilitate correlation, include:

- Design graphs for span limits and span/depth ratios
- Column design graphs
- Seismic design graphs
- Wind design graphs

Acknowledgements

I am grateful to many students and others for various contributions to this book, ranging from suggestions to illustrations; most notably drawings by Bronne Dytog and June Yip; but also Xiaojun Cheng, Lucia Ho, Maki Kawaguchi, Ping Kuo, Jennifer Lin, Sassu Mitra, Rick Patratara, Shina Rau, Srinivas Rau, Madhu Thangavelu, and Sharmilla Thanka. Students that provided data and comments include Laura Mae Bryan, Sabina Cheng, Samy Chong, Claudia Chiu, Kristin Donour, Miriam Figueroa, Ping Han, Nick Ketpura, Samuel Kuo, Jason Mazin, Neha Sivaprasad, Timothy Petrash, Musette Profant, Katie Rahill, Reed Suzuki, Bogdan Tomalevski, Carole Wong, Nasim Yalpani. Others that provided comments or material: include: Andrea Cohen Gehring, Jeff Guh, Robert Harris, Theo Heizmann, Helge Wang, Will Shepphird, Robert Timme, Matt Warren, and Walter Winkle. Architects and engineers that provided drawings include: Norman Foster, Von Gerkan Marg, Arata Isozaki, David Lawrence Gray, Paul M. Kaufmann, Pierre Koenig, Panos Koulermos, Edward Niles, Jörg Schlaich, James Tyler, Widom Wein Cohen, and Dimitry Vergun.

To my family

Units

SI * units (metric)			Conversion factor **	US units		
		Remark				Remark
Length						
Millimeter	mm		25.4	Inch	in	
Centimeter	cm	10 mm	30.48	Foot	ft	12 in
Meter	m	1000 mm	0.9144	Yard	yd	3 ft
Kilometer	km	1000 m	1.609	Mile	mi	5280 ft
Area						
Square millimeter	mm ²		645.16	Square in	in ²	
Sq. centimeter	cm ²	100 mm ²	929	Square foot	ft ²	144 in ²
Square meter	m ²	1 Mil	0.835	Sq. yard	yd ²	9 ft ²
Hectar	ha	10000 m ²	2.472	Acre	Acre = 4840 yd ²	
Volume						
Cubic millimeter	mm ³		16387	Cubic inch	in ³	
Cubic centimeter	cm ³	1 k mm ³	28317	Cubic foot	ft ³	
Cubic meter	m ³	1 Mil cm ³	0.7646	Cubic yard	yd ³	
Liter	l	0.001 m ³	0.264	Gallon	US gal = 3.785 liter	
Mass						
Gram	g		28.35	Ounce	oz	
Kilogram	kg	1000 g	0.4536	Pound	Lb, #	16 oz
Tonn	t	1000 kg	0.4536	Kip	k	1000 #
Force / load						
Newton	N		4.448	Pound	Lb, #	
Kilo Newton	kN	1000 N	4.448	Kip	k	1000 #
Newton/ meter	N/m		14.59	Pound/ ft	plf	
Kilo Newton/ m	kN/m		14.59	Kip/ ft	klf	1000 plf
Stress						
Pascal= N/m ²	Pa		6895	Pound/ in ²	psi	
Kilo Pascal	kPa	1000 Pa	6895	Kip / in ²	ksi	1000
Fabric stress						
Kilo Newton / m	kN/m		175	Pound/ in	Lb/in	Fabric
Load / soil pressure						
Kilo Pascal	kPa	1000 Pa	47.88	Pound/ ft ²	psf	
Moment						
Newton-meter	N-m		1.356	Pound-foot	Lb-ft, #	
Kilo Newton-m	kN-m	1000 N-	1.356	Kip-foot	k-ft, k'	1000#'
Temperature						
Celcius	°C		.55(F-32)	Fahrenheit	°F	
Water freezing		0°C	=	32°F		
Water boiling		100°C	=	212°F		

Prefixes

Prefix	Factor
Micro-	0.000001
Milli-, m	0.00001
Centi-	0.01
Deci-	0.1
Semi-, hemi-, demi-	0.5
Uni-	1
Bi-, di-	2
Tri-, ter-	3
Tetra-, tetra-, quadr-	4
Pent-, penta-, quintu-	5
Sex-, sexi-, hexi-, hexa-,	6
Hep-, septi-,	7
Oct-, oct-, octa-, octo-	8
Non-, nona-	9
Dec-, deca-, deci, deka-	10
Hect-, hector-	100
Kilo-, k	1,000
Mega-, M	1,000,000
Giga-, G	1,000,000,000
Tera-	1,000,000,000,000

* SI = System International (French - designation for metric system)

** Multiplying US units with conversion factor = SI units
Dividing SI units by conversion factor = US units

Contents

PART I: BACKGROUND

1 Historic Evolution

- 1-2 Walls
- 1-6 Post-and-beam
- 1-10 Arch, Vault, Dome
- 1-21 Suspended
- 1-24 Truss
- 1-26 Skyscraper

2 Loads

- 2-2 Introduction
- 2-2 Dead load
- 2-4 Live load
- 2-5 Seismic load
- 2-6 Wind load
- 2-8 Tributary load and load path

3 Basic Concepts

- 3-2 Synergy, Strength, Stiffness, Stability
- 3-3 Rupture length
- 3-4 Horizontal structures
 - Slab, plate, deck (one & two-way)
 - Beam, arch and cable
 - Truss
- 3-9 Vertical/lateral structures
 - Wall
 - Cantilever
 - Moment frame
 - Braced frame

PART II: MECHANICS

4 Statics

- 4-2 Force and moment
- 4-3 Static equilibrium
- 4-4 Supports
- 4-5 Reactions
- 4-10 Static determinacy
- 4-13 Vector analysis
- 4-15 Truss analysis
- 4-17 Funicular
- 4-21 Vector reactions

5 Strength Stiffness Stability

- 5-2 Force types
- 5-3 Force vs. stress
- 5-4 Allowable stress
- 5-5 Axial stress
- 5-6 Shear stress
- 5-8 Torsion
- 5-9 Principal stress
- 5-10 Strain
- 5-10 Hook's law
- 5-11 Elastic Modulus
- 5-14 Thermal strain
- 5-14 Thermal stress
- 5-17 Stability

6 Bending

- 6-4 Bending and shear
- 6-8 Equilibrium method
- 6-10 Area method
- 6-13 Indeterminate beams
- 6-14 Flexure formula
- 6-15 Section modulus
- 6-16 Moment of inertia
- 6-18 Shear stress
- 6-22 Deflection

7 Buckling

- 7-3 Euler formula
- 7-3 Slenderness ratio
- 7-4 Combined stress
- 7-5 Kern
- 7-6 Arch and vault
- 7-7 Wood buckling
- 7-12 Steel buckling

PART III: DESIGN METHODS

8 ASD, LRFD, Masonry and Concrete Design

- 8-2 ASD (Allowable Stress Design)
- 8-3 LRFD (Load Resistance Factor Design)
- 8-4 Masonry design (ASD)
- 8-10 Concrete strength design (LRFD)

9 Lateral Force Design

- 9-2 Design for wind
- 9-8 Seismic design
- 9-13 SD-graphs
- 9-15 Analysis steps
- 9-18 Vertical distribution
- 9-19 Horizontal diaphragms
- 9-22 Eccentricity
- 9-23 Hazard configurations
- 9-24 Stability issues
- 9-27 Seismic safety items

10 Conceptual Design

- 10-1 System selection
- 10-3 Global moment and shear
- 10-4 Radial pressure
- 10-5 Examples
- 10-7 Case studies
- 10-15 Portal method
- 10-17 Moment frame
- 10-19 Braced frame
- 10-21 Test models
- 10-23 Sample projects
- 10-29 Computer aided design

PART IV: HORIZONTAL SYSTEMS**11 Bending Resistant**

- 11-1 Bending concepts
- 11-3 Beam optimization
- 11-5 Joist, beam, girder
- 11-11 *Vierendeel*
- 11-17 Folded plate
- 11-22 Cylindrical shell

12 Axial Resistant

- 12-2 Truss
 - Truss configurations
 - Prismatic truss
 - Folded truss
- 12-13 Space truss
- 12-22 Tree structures

13 Form-Resistant

- 13-2 Funicular concepts
- 13-4 Arch
- 13-10 Vault
- 13-17 Dome
- 13-23 Grid shell
- 13-29 HP shell
- 13-37 Freeform shell

14 Tensile Resistant

- 14-1 Tension members
- 14-2 Prestress
- 14-3 Stayed structures
- 14-8 Propped structures
- 14-10 Suspended structures
- 14-17 Cable truss
- 14-21 Anticlastic structures
- 14-42 Pneumatic structures

PART V: VERTICAL SYSTEMS**15 General Background**

- 15-2 Tall structures
- 15-3 Gravity load
- 15-4 Lateral load
- 15-7 Structure systems
- 15-11 Floor framing
- 15-12 Beam-column interaction

16 Shear Resistant

- 16-2 Classic walls
- 16-3 Seismic failures
- 16-4 Shear walls
- 16-6 Shear wall stability
- 16-7 Wood shear walls
- 16-10 Shear wall reinforcing

17 Bending Resistant

- 17-2 Cantilever
- 17-6 Moment frame
- 17-13 Framed tube
- 17-16 Bundled tube

18	Axial Resistant
18-2	Braced frame
18-8	Belt truss and outrigger
18-12	Braced tube
18-16	Eccentric braced frame

19	Suspended high-rise
19-2	Suspension rational
19-3	Design options
19-3	Limits
19-4	Case studies

PART VI: MATERIAL

20	Wood
20-1	Material
20-5	Heavy timber
20-13	Grid structures
	Balloon framing
	Platform framing
20-29	Projects

21	Steel
21-1	Material
21-7	Heavy steel
21-29	Light gauge steel
21-33	Projects

22	Masonry
22-1	Material
22-7	Brick masonry
22-18	Concrete masonry
22-22	Stone masonry
22-23	Projects

23	Concrete
23-1	Material
23-4	Reinforced concrete
23-17	Prestressed concrete
23-20	Precast concrete
23-24	Tilt-up concrete
23-26	Projects

24	Fabric and cables
24-1	Material
24-2	Fabric
24-4	Cables
24-10	Projects

Appendix A: Beam Formulas

A-2	Beam formulas
A-3	Bending coefficients

Appendix B: Geometric Properties

B-2	Centroid
B-4	Moment of Inertia
B-6	Parallel Axis Theorem
B-7	Radius of Gyration
B-8	Geometric properties

Appendix C: Lateral Design Data

C-2	Wind design data
C-7	Seismic design data

Appendix D: Material and Buckling Data

D-2	Wood
D-8	Steel

Appendix E: Design Tables

E-2	Span Ranges for Structure Elements
E-3	Span Ranges for Structure Systems

3

Basic Concepts

This chapter on basic concept introduces:

- Structural design for:
 - Strength
 - Stiffness
 - Stability
 - Synergy
- Rupture length (material properties, i.e., structural efficiency)
- Basic structure systems
 - Horizontal structures
 - Vertical / lateral structures for:
 - Gravity load
 - Lateral load

Strength, Stiffness, Stability, Synergy

Structures must be designed to satisfy three Ss and should satisfy all four Ss of structural design – as demonstrated on the following examples, illustrated at left.

- 1 **S**trength to prevent breaking
- 2 **S**tiffness to prevent excessive deformation
- 3 **S**tability to prevent collapse
- 4 **S**ynergy to reinforce architectural design, described on two examples:
 Pragmatic example: Beam composed of wooden boards
 Philosophical example: Auditorium design

Comparing beams of wooden boards, $b = 12''$ wide and $d = 1''$ deep, each. Stiffness is defined by the **Moment of Inertia**, $I = b d^3/12$

1 board, $I = 12 \times 1^3/12$	$I = 1$
10 boards $I = 10 (12 \times 1^3/12)$	$I = 10$
10 boards glued, $I = 12 \times 10^3/12$	$I = 1000$


Strength is defined by the **Section modulus**, $S = I/(d/2)$


1 board, $S = 1/0.5$	$S = 2$
10 boards, $S = 10/0.5$	$S = 20$
10 boards, glued, $S = 1000/5$	$S = 200$

Note:

The same amount of material is 100 times stiffer and 10 times stronger when glued together to transfer shear and thereby engage top and bottom fibers in compression and tension (a system, greater than the sum of its parts). On a philosophical level, structures can strengthen architectural design as shown on the example of an auditorium:

- Architecturally, columns define the circulation
- Structurally, column location reduces bending in roof beams **over 500% !**





Rupture length

Rupture length is the maximum length a bar of constant cross section area can be suspended without rupture under its weight in tension (compression for concrete & masonry).

Rapture length defines material efficiency as strength / weight ratio:

$$R = F / \lambda$$











R = rupture length

F = breaking strength

λ = specific gravity (self weight)

Rupture length, is of particular importance for long-span structures. The depth of horizontal span members increases with span. Consequently the weight also increases with span. Therefore the capacity of material to span depends on both its strength and weight. This is why lightweight material, such as glass fiber fabrics are good for long-span structures. For some material, a thin line extends the rupture length to account for different material grades.

The graph data is partly based on a study of the Light weight Structures Institute, University Stuttgart, Germany




Horizontal structures

Horizontal systems come in two types: one way and two way. Two way systems are only efficient for spaces with about equal span in both directions; as described below. The diagrams here show one way systems at left and two way systems at right


- 1 Plywood deck on wood joists
- 2 Concrete slab on metal deck and steel joists
- 3 One way concrete slab
- 4 One way beams
- 5 One way rib slab
- 6 Two way concrete plate
- 7 Two way concrete slab on drop panels
- 8 Two way concrete slab on edge beams
- 9 Two way beams
- 10 Two way waffle slab
- 11 Deflection Δ for span length L_1
- 12 Deflection $\Delta=16$ due to double span $L_2 = 2 L_1$

Note:


Deflection increases with the fourth power of span. Hence for double span deflection increase 16-fold.. Therefore two way systems over rectangular plan are ineffective because elements that span the short way control deflection and consequently have to resist most load and elements that span the long way are very ineffective.





11





12





1





2




3



4




5



Trusses


Trusses support load much like beams, but for longer spans. As the depth and thus dead weight of beams increases with span they become increasingly inefficient, requiring most capacity to support their own weight rather than imposed live load. Trusses replace bulk by triangulation to reduce dead weight.

- 1 Unstable square panel deforms under load.
Only triangles are intrinsically stable polygons
- 2 Truss of triangular panels with inward sloping diagonal bars that elongate in tension under load (preferred configuration)
- 3 Outward sloping diagonal bars compress (disadvantage)
- 4 Top chords shorten in compression
Bottom chords elongate in tension under gravity load
- 5 Gable truss with top compression and bottom tension



Warren trusses



Pompidou Center, Paris by Piano and Rogers



Prismatic trusses

IBM Sport Center by Michael Hopkins

(Prismatic trusses of triangular cross section provide rotational resistance)







Space trusses

square and triangular plan

Note:




Two way space trusses are most effective if the spans in the principle directions are about equal, as described for two-way slabs above. The base modules of trusses should be compatible with plan configuration (square, triangular, etc.)



Funicular structures

The funicular concept can be best described and visualized with cables or chains, suspended from two points, that adjust their form for any load in tension. But funicular structures may also be compressed like arches. Yet, although funicular tension structures adjust their form for pure tension under any load, funicular compression structures may be subject to bending in addition to compression since their form is rigid and not adaptable. The funicular line for tension and compression are inversely identical; the form of a cable becomes the form of an arch upside-down. Thus funicular forms may be found on tensile elements.

- 1 Funicular tension triangle under single load
- 2 Funicular compression triangle under single load
- 3 Funicular tension trapezoid under twin loads
- 4 Funicular compression trapezoid under twin loads
- 5 Funicular tension polygon under point loads
- 6 Funicular compression polygon under point load
- 7 Funicular tension parabola under uniform load
- 8 Funicular compression parabola under uniform load











Vault

IBM traveling exhibit by Renzo Piano

A series of trussed arches in linear extrusion form a vault space. The trussed arches consist of wood bars with metal connectors for quick assembly and disassembly as required for the traveling exhibit. Plastic panels form the enclosing skin. The trussed arches provide depth and rigidity to accommodate various load conditions.

Suspension roof

Exhibit hall Hanover by Thomas Herzog




Vertical structures

Vertical elements

Vertical elements transfer load from roof to foundation, carrying gravity and/or lateral load. Although elements may resist only gravity or only lateral load, most are designed to resist both. Shear walls designed for both gravity and lateral load may use gravity dead load to resist overturning which is most important for short walls. Four basic elements are used individually or in combination to resist gravity and lateral loads

- 1 Wall under gravity load
- 2 Wall under lateral load (shear wall)
- 3 Cantilever under gravity load
- 4 Cantilever under lateral load
- 5 Moment frame under gravity load
- 6 Moment frame under lateral load
- 7 Braced frame under gravity load
- 9 Braced frame under lateral load




Vertical systems

Vertical systems transfer the load of horizontal systems from roof to foundation, carrying gravity and/or lateral load. Although they may resist gravity or lateral load only, most resist both, gravity load in compression, lateral load in shear. Walls are usually designed to define spaces and provide support, an appropriate solution for apartment and hotel buildings. The four systems are:

- 1 Shear walls (apartments / hotels)
 - 2 Cantilever (Johnson Wax tower by F L Wright)
 - 3 Moment frame
 - 4 Braced frame
- A Concrete moment resistant joint
Column re-bars penetrate beam and beam re-bars penetrate column)
- B Steel moment resistant joint
(stiffener plates between column flanges resist beam flange stress)







Vertical / lateral element selection criteria		
Element	Advantages	Challenges
Shear wall Architectural criteria	Good for apartments/hotels	Inflexible for future changes
Structural criteria	Very stiff, good for wind resistance	Stiffness increases seismic forces
Cantilever Architectural criteria	Flexible planning Around cantilever	Must remain in future changes
Structural criteria	Ductile, much like a tree trunk	Too flexible for tall structures
Moment frame Architectural criteria	Most flexible, good for office buildings	Expensive, drift may cause problems
Structural criteria	Ductile, absorbs seismic force	Tall structures need additional stiffening
Braced frame Architectural criteria	More flexible than Shear walls	Less flexible than moment frame
Structural criteria	Very stiff, good for Wind resistance	Stiffness increases seismic forces



Shear walls

As the name implies, shear walls resist lateral load in shear. Shear walls may be of wood, concrete or masonry. In the US the most common material for low-rise apartments is light-weight wood framing with plywood or particle board sheathing. Framing studs, spaced 16 or 24 inches, support gravity load and sheathing resists lateral shear. In seismic areas concrete and masonry shear walls must be reinforced with steel bars to resist lateral shear.


- 1 Wood shear wall with plywood sheathing
- 2 Light gauge steel shear wall with plywood sheathing
- 3 Concrete shear wall with steel reinforcing
- 4 CMU shear wall with steel reinforcing
- 5 Un-reinforced brick masonry (not allowed in seismic areas)
- 8 Two-wythe brick shear wall with steel reinforcing



Cantilevers

Cantilevers resist lateral load primarily in bending. They may consist of single towers or multiple towers. Single towers act much like trees and require large footings like tree roots to resist overturning. Bending in cantilevers increases from top down, justifying tapered form in response.

- 1 Single tower cantilever
- 2 Single tower cantilever under lateral load
- 3 Twin tower cantilever
- 4 Twin tower cantilever under lateral load
- 5 Suspended tower with single cantilever
- 6 Suspended tower under lateral load













Moment frames

Moment frames resist gravity and lateral load in bending and compression. They are derived from post-and beam portals with moment resisting beam to column connections (for convenience referred to as moment frames and moment joints). The effect of moment joints is that load applied to the beam will rotate its ends and in turn rotate the attached columns. Equally, load applied to columns will rotate their ends and in turn rotate the beam. This mutual interaction makes moment frames effective to resist lateral load with ductility. Ductility is the capacity to deform without breaking, a good property to resist earthquakes, resulting in smaller seismic forces than in shear walls and braced frames. However, in areas with prevailing wind load, the greater stiffness of shear walls and braced frames is an advantage. The effect of moment joints to resist loads is visualized through amplified deformation as follows:

- 1 Portal with pin joints collapses under lateral load
 - 2 Portal with moment joints at base under lateral load
 - 3 Portal with moment beam/column joints under gravity load
 - 4 Portal with moment beam/column joints under lateral load
 - 5 Portal with all moment joints under gravity load
 - 6 Portal with all moment joints under lateral load
 - 7 High-rise moment frame under gravity load
 - 8 Moment frame building under lateral load
- I Inflection points (zero bending between negative and positive bending)

Note:
deformations reverse under reversed load



Braced frames

Braced frames resist gravity load in bending and axial compression, and lateral load in axial compression and tension by triangulation, much like trusses. The triangulation results in greater stiffness, an advantage to resist wind load, but increases seismic forces, a disadvantage to resist earthquakes. Triangulation may take several configurations, single diagonals, A-bracing, V-bracing, X-bracing, etc., considering both architectural and structural criteria. For example, location of doors may be effected by bracing and impossible with X-bracing. Structurally, a single diagonal brace is the longest, which increases buckling tendency under compression. Also the number of costly joints varies: two for single diagonals, three for A- and V-braces, and five joints for X-braces. The effect of bracing to resist load is visualized through amplified deformation as follows:

- 1 Single diagonal portal under gravity and lateral loads
- 2 A-braced portal under gravity and lateral load
- 3 V-braced portal under gravity and lateral load
- 4 X-braced portal under gravity and lateral load
- 5 Braced frame building without and with lateral load

Note:

deformations and forces reverse under reversed load

Part II

4

Mechanics

Mechanics, as defined for the study of structures, is the behavior of physical systems under the action of forces; this includes both statics and dynamics.


Dynamics is the branch of mechanics that deals with the motion of a system of material particles under the influence of forces. Dynamic equilibrium, also known as kinetic equilibrium, is the condition of a mechanical system when the kinetic reaction of all forces acting on it are in dynamic equilibrium.

Statics is the branch of mechanics that deals with forces and force systems that act on bodies in equilibrium as described in the following.


Statics

Statics is the branch of mechanics that deals with forces and force systems that act on bodies in equilibrium. Since buildings are typically designed to be at rest (in equilibrium), the subject of this book is primarily focused on statics. Even though loads like earthquakes are dynamic they are usually treated as equivalent static forces.


1



2



3



Force and Moment

Force is an action on a body that tends to:

- change the shape of an object or
- move an object or
- change the motion of an object

US units: # (pound), k (kip)

SI units: N (Newton), kN (kilo Newton)

Moment is a force acting about a point at a distance called *lever arm*

$M = P L$ (Force $\times$ lever arm)

The lever arm is measured normal (perpendicular) to the force.

Moments tend to:



- rotate an object or
- bend an object (bending moment)

US units: #' (pound-feet), k' (kip-feet), #" (pound-inch), k" (kip-inch)

SI units: N-m (Newton-meter), kN-m (kilo-Newton-meter)

- 1 Gravity force (compresses the pyramid)
- 2 Pulling force (moves the boulder)
- 3 Moment = force times lever arm ($M = P L$)

- A Point about which the force rotates
 L Lever arm
 M Moment
 P Force



Static Equilibrium




For any body to be in static equilibrium, all forces and moments acting on it must be in equilibrium, i.e. their sum must equal zero. This powerful concept is used for static analysis and is defined by the following three equations of statics:

$$\begin{aligned}\Sigma H &= 0 && \text{(all horizontal forces must equal zero)} \\ \Sigma V &= 0 && \text{(all vertical forces must equal zero)} \\ \Sigma M &= 0 && \text{(all moments must equal zero)}\end{aligned}$$

The equilibrium equations are illustrated as follows:

- 1 Horizontal equilibrium: pulling left and right with equal forces, mathematically defined as
 $\Sigma H = 0 = +100 - 100 = 0$
- 2 Vertical equilibrium: pushing up with a force equal to a weight, mathematically defined as:
 $\Sigma V = 0 = -2 \times 100 + 200 = 0$
- 3 Moment equilibrium: balancing both sides of a balance board, mathematically defined as:
 $\Sigma M = 0 = -50\#(8') + 200\#(2') = -400 + 400 = 0$

Much of this book is based on the three equilibrium equations.









Supports

For convenience, support types are described for beams, but apply to other horizontal elements, like trusses, as well. The type of support affects analysis and design, as well as performance. Given the three equations of statics defined above, $\Sigma H=0$, $\Sigma V=0$, and $\Sigma M=0$, beams with three unknown reactions are considered *determinate* (as described below) and can be analyzed by the three static equations. Beams with more than three unknown reactions are considered *indeterminate* and cannot be analyzed by the three static equations alone. A beam with two pin supports (1) has four unknown reactions, one horizontal and one vertical reaction at each support. Under load, in addition to bending, this beam would deform like a suspended cable in tension, making the analysis more complex and not possible with static equations.

By contrast, a beam with one pin and one roller support (2) has only three unknown reactions, one horizontal and two vertical. In bridge structures such supports are quite common. To simplify analysis, in building structures this type of support may be assumed, since supporting walls or columns usually are flexible enough to simulate the same behavior as one pin and one roller support. The diagrams at left show for each support on top the physical conditions and below the symbolic abstraction.

- 1 Beam with fixed supports at both ends subject to bending and tension
- 2 Simple beam with one pin and one roller support subject to bending only
- 3 Beam with flexible supports, behaves like a simple beam

Simple beams, supported by one pin and one roller, are very common and easy to analyze. Designations of roller- and pin supports are used to describe the structural behavior assumed for analysis, but do not always reflect the actual physical support. For example, a pin support is not an actual pin but a support that resists horizontal and vertical movement but allows rotation. Roller supports may consist of *Teflon* or similar material of low friction that allows horizontal movement like a roller.




Support symbols

The diagrams show common types of support at left and related symbols at right. In addition to the pin and roller support described above, they also include fixed-end support (as used in steel and concrete moment frames, for example).

Support types				
		Degrees of freedom		
	Support type	Horizontal movement	Vertical movement	Rotation
1	Roller	Free	Fixed	Free
2	Pin	Fixed	Fixed	Free
3	Rigid	Fixed	Fixed	Fixed

1



Reactions

Support reactions for asymmetrical loads and/or supports are computed using the equations of statics, $\Sigma H=0$, $\Sigma V=0$, and $\Sigma M=0$. The following examples illustrate the use of the three equations to find reactions.

1 Weight lifter on balcony

Assume:

$$P = 400\#, L = 6'$$

$$\Sigma V = 0 \uparrow +$$

$$R - P = 0$$

$$R = P$$

$$R = 400 \#$$


$$\Sigma M = 0, \curvearrowright +$$

$$P L - M = 0$$

$$M = P L = 400 \times 6$$

$$M = 2,400 \#'$$

2



2. Flag pole

Assume:

$$H = 80\# \text{ (wind load on flag)}$$

$$L = 20'$$

$$\Sigma H = 0 \rightarrow +$$

$$W - H = 0$$

$$H = W$$

$$H = 80 \#$$

$$\Sigma M = 0 \curvearrowright +$$

$$W L + M = 0$$


$$M = -W L = -80 \times 20$$

$$M = -1,600 \#'$$

Note:

The negative moment implies, the positive moment arrow must be reversed

3



3 Tow truck

Assume:

$$P = 2k, C = 7', L = 10'$$

$$\Sigma M_a = 0 \curvearrowright +$$

$$R_b L - P C = 0$$

$$R_b = P C / L = 2 \times 7 / 10$$

$$R_b = 1.4k$$

$$\Sigma M_b = 0 \curvearrowright +$$

$$R_a L - P (C+L) = 0$$

$$R_a = P (C+L) / L = 2 (7+10) / 10$$

$$R_a = +3.4k$$

$$\text{Check } \Sigma V = 0$$


$$\Sigma V = 0 = +3.4 - 1.4 - 2$$

$$\Sigma V = 0$$


Note:

The lever arm is always perpendicular to load

R_b pointing downward is provided by the truck weight



1



2

Beam reactions

To find reactions for asymmetrical beams:

- Draw an abstract beam diagram to illustrate computations
- Use $\sum M = 0$ at one support to find reaction at other support
- Verify results for vertical equilibrium

- 1 Floor framing
- 2 Abstract beam diagram

Assume:

DL = 10 psf

LL = 20 psf

$\Sigma = 30$ psf

Uniform beam load:

$w = 30 \text{ psf} \times 2'$

$w = 60 \text{ plf}$

For convenience, substitute total beam load W for uniform load w at its centroid

Total beam load

$W = w L = 60 (12+4)$

$W = 960 \text{ \#}$

Support reactions:

$\sum M_b = 0 \curvearrowright +$

$12 R_a - 4 W = 0$

$R_a = 4 \times 960 / 12$

$R_a = 320 \text{ \#}$

$\sum M_a = 0 \curvearrowright +$

$8 W - 12 R_b = 0$

$12 R_b = 8 \times 960$

$R_b = 8 \times 960 / 12$

$R_b = 640 \text{ \#}$

Check $\sum V = 0 \uparrow +$

$R_a + R_b - W = 320 + 640 - 960 = 0$

$\sum V = 0$

Alternate method (use uniform load directly)

Support reactions:

$\sum M_b = 0 \curvearrowright +$

$12 R_a - 4 \times 60 \text{ plf} \times 16' = 0$

$R_a = 4 \times 60 \times 16 / 12$

$R_a = 320 \text{ \#}$

$\sum M_a = 0 \curvearrowright +$

$8 \times 60 \times 16 - 12 R_b = 0$

$12 R_b = 8 \times 60 \times 16$


$R_b = 8 \times 60 \times 16 / 12$

$R_b = 640 \text{ \#}$

Check $\sum V = 0 \uparrow +$

$R_a + R_b - W = 320 + 640 - 960 = 0$

$\sum V = 0$




1 Simple beam with point loads

Assume: $P = 1.2\text{k}$

$$R = 5 P / 2 = 5 \times 1.2 / 2$$

$$R = 3\text{k}$$



2 Beam with overhang and point loads

Assume: $P = 2\text{k}$

$$\Sigma M_b = 0 \curvearrowright +$$

$$12 R_a - 2 \times 16 - 2 \times 12 - 2 \times 8 - 2 \times 4 = 0$$

$$R_a = (32 + 24 + 16 + 8) / 12$$

$$R_a = 6.67\text{k}$$

$$\Sigma M_a = 0 \curvearrowright +$$

$$-12 R_b - 2 \times 4 + 2 \times 4 + 2 \times 8 + 2 \times 12 = 0$$


$$R_b = (2 \times 8 + 2 \times 12) / 12$$

$$R_b = 3.33\text{k}$$

$$\text{Check } \Sigma V = 0 \uparrow +$$

$$6.67 + 3.33 - 5 \times 2$$

$$\Sigma V = 0$$



3 Beam with uniform load and point load (wall)

Assume: $w = 100\text{ plf}$, $P = 800\#$

$$\Sigma M_c = 0 \curvearrowright +$$

$$16 R_a - 100 \times 16 \times 8 - 800 \times 12 = 0$$

$$R_a = (100 \times 16 \times 8 + 800 \times 12) / 16$$

$$R_a = 1,400\#$$

$$\Sigma M_a = 0 \curvearrowright +$$

$$-16 R_c + 100 \times 16 \times 8 + 800 \times 4 + 800 \times 16 = 0$$




$$R_c = (100 \times 16 \times 8 + 800 \times 4 + 800 \times 16) / 16$$

$$R_c = 1800\#$$

$$\text{Check } \Sigma V = 0 \uparrow +$$

$$1400 + 1800 - 100 \times 16 - 800 - 800$$

$$\Sigma V = 0$$



Vector Analysis







First used by Leonardo da Vinci, graphic vector analysis is a powerful method to analyze and visualize the flow of forces through a structure. However, the use of this method is restricted to statically determinate systems. In addition to forces, vectors may represent displacement, velocity, etc. Though only two-dimensional forces are described here, vectors may represent forces in three-dimensional space as well. Vectors are defined by *magnitude*, *line of action*, and *direction*, represented by a straight line with an arrow and defined as follows:

Magnitude is the vector length in a force scale, like $1'' = 10 \text{ k}$ or $1 \text{ cm} = 50 \text{ kN}$

Line of Action is the vector slope and location in space

Direction is defined by an arrow pointing in the direction of action

- Two force vectors P_1 and P_2 acting on a body pull in a certain direction. The *resultant* R is a force with the same results as P_1 and P_2 combined, pulling in the same general direction. The resultant is found by drawing a force parallelogram [A] or a force triangle [B]. Lines in the vector triangle must be parallel to corresponding lines in the vector plan [A]. The line of action of the resultant is at the intersection of P_1 / P_2 in the vector plan [A]. Since most structures must be at rest it is more useful to find the *equilibrant* E that puts a set of forces in equilibrium [C]. The equilibrant is equal in magnitude but opposite in direction to the resultant. The equilibrant closes a force triangle with all vectors connected head-to-tail. The line of action of the equilibrant is also at the intersection of P_1 / P_2 in the vector plan [A].
- The equilibrant of three forces [D] is found, combining interim resultant R_{1-2} of forces P_1 and P_2 with P_3 [E]. This process may be repeated for any number of forces. The interim resultants help to clarify the process but are not required [F]. The line of action of the equilibrant is located at the intersection of all forces in the vector plan [D]. Finding the equilibrant for any number of forces may be stated as follows:
The equilibrant closes a force polygon with all forces connected head-to-tail, and puts them in equilibrium in the force plan.
- The equilibrant of forces without a common cross-point [G] is found in stages: First the interim resultant R_{1-2} of P_1 and P_2 is found [H] and located at the intersection of P_1 / P_2 in the vector plan [G]. P_3 is then combined with R_{1-2} to find the equilibrant for all three forces, located at the intersection of R_{1-2} with P_3 in the vector plan. The process is repeated for any number of forces.



Vector components





Vector components have the same effect on a body as the initial vector. Thus components relate to a vector as two vectors relate to a resultant or equilibrant.

- 1 The component forces C_1 and C_2 in two cables supporting a load P are found by drawing a force triangle [B] with corresponding lines parallel to the those in the vector plan [A].
- 2 Forces in more than two cables supporting a load P are indeterminate [C] and cannot be found by graphic vector method since there are infinite number of solutions [D]. A problem with more than two unknown force components requires consideration of relative cable stiffness (cross-section area, length, and stiffness). Hence we can state:

Only two components can be found by graphic vector method

- 3 This example demonstrates graphic vector analysis: Forces are drawn on a vector plan with line of action and direction [E]. The magnitude may be written on each vector or the vector may be drawn at a force scale. A force polygon [F] is drawn next at a force scale, such as $1'' = 1k$. For good accuracy, the force scale should be as large as space permits. The line of action of the equilibrant (or resultant) is then transposed into the vector plan at the intersection of all force vectors [E].

$$R_l = R_r = (2 \times 1 + 3 \times 2) / 2 = 4K$$



BH = -6.7K
 HG = +6.0K
 CI = -5.6K
 IH = -1.8K
 IK = +1.8K
 KG = +4.0K



5

Truss Analysis


Graphic truss analysis (*Bow's Notation*) is a method to find bar forces using graphic vectors as in the following steps:

- Draw a truss scaled as large as possible (1) and compute the reactions as for beams (by moment method for asymmetrical trusses).
- Letter the spaces between loads, reactions, and truss bars. Name bars by adjacent letters: bar BH between B and H, etc.
- Draw a force polygon for external loads and reactions in a force scale, such as 1"=10 pounds (2). Use a large scale for accuracy. A closed polygon with head-to-tail arrows implies equilibrium. Offset the reactions to the right for clarity.
- Draw polygons for each joint to find forces in connected bars. Closed polygons with head-to-tail arrows are in equilibrium. Start with left joint ABHG. Draw a vector parallel to bar BH through B in the polygon. H is along BH. Draw a vector parallel to bar HG through G to find H at intersection BH-HG.
- Measure the bar forces as vector length in the polygon.
- Find bar tension and compression. Start with direction of load AB and follow polygon ABHGA with head-to-tail arrows. Transpose arrows to respective bars in the truss next to the joint. Arrows pushing toward the joint are in compression; arrows pulling away are in tension. Since the arrows reverse for adjacent joints, draw them only on the truss but not on the polygon.
- Draw equilibrium arrows on opposite bar ends; then proceed to the next joint with two unknown bar forces or less (3). Draw polygons for all joints (4), starting with known loads or bars (for symmetrical trusses half analysis is needed).

- Truss diagram
- Force polygon for loads, reactions, and the first joint polygon
- Truss with completed tension and compression arrows
- Completed force polygon for left half of truss
- Tabulated bar forces (- implies compression)



HA = -20K
 BI = -26K
 IH = +30K
 HG = 0K
 IK = -10K
 CK = -26K
 KL = -10K
 LG = +35K
 LM = 0K



Truss Example


Some trusses have bars with zero force under certain loads. The example here has zero force in bars HG, LM, and PG under the given load. Under asymmetrical loads these bars would not be zero and, therefore, cannot be eliminated. Bars with zero force have vectors of zero length in the equilibrium polygon and, therefore, have both letters at the same location.

Tension and compression in truss bars can be visually verified by deformed shape (4), exaggerated for clarity. Bars in tension will elongate; bars in compression will shorten. In the truss illustrated the top chord is in compression; the bottom chord is in tension; inward sloping diagonal bars in tension; outward sloping diagonal bars in compression.

Since diagonal bars are the longest and, therefore, more likely subject to buckling, they are best oriented as tension bars.

- 1 Truss diagram
- 2 Force polygon
- 3 Tabulated bar forces (+ implies tension, - compression)
- 4 Deformed truss to visualize tension and compression bars

- A Bar elongation causes tension
 B Bar shortening causes compression



Funicular

Graphic vector are powerful means to design funicular structures, like arches and suspension roofs; providing both form and forces under uniform and random loads.

Arch

Assume:

Arch span $L = 150$, arch spacing $e = 20'$

$DL = 14$ psf

$LL = 16$ psf

$\Sigma = 30$ psf

Uniform load

$w = 30 \text{ psf} \times 20' / 1000$

$w = 0.6 \text{ klf}$

Vertical reactions

$R = w L / 2 = 0.6 \times 150 / 2$

$R = 45 \text{ k}$

Draw vector polygon, starting with vertical reaction R

Horizontal reaction

$H = 56 \text{ k}$

Max. arch force (diagonal vector parallel to arch tangent)

$F = 72 \text{ k}$

1 Arch structure

2 Parabolic arch by graphic method

Process:

Draw AB and AC (tangents of arch at supports)

Divide tangents AB and AC into equal segments

Lines connecting AB to AC define parabolic arch envelope

3 Arch profile

Process:

Define desired arch rise D (usually $D = L/5$)

Define point A at $2D$ above supports

AB and AC are tangents of parabolic arch at supports

Compute vertical reactions $R = w L / 2$

4 Equilibrium vector polygon at supports (force scale: $1'' = 50 \text{ k}$)

Process:


Draw vertical vector (reaction R)

Complete vector polygon (diagonal vector parallel to tangent)

Measure vectors (H = horizontal reaction, F = max. arch force)

Note:

The arch force varies from minimum at crown (equal to horizontal reaction), gradually increasing with arch slope, to maximum at the supports.



Suspension roof

Assume:

Span $L = 300$, cable spacing $e = 10'$, sag $f = 30'$, height difference $h = 50'$

DL = 14 psf

LL = 16 psf

$\Sigma = 30$ psf

Uniform load

$w = 30 \text{ psf} \times 10' / 1000$

$w = 0.3 \text{ klf}$

Total load

$W = w L = 0.3 \times 300$

$R = 90 \text{ k}$

Draw vector polygon, starting with total load W

Horizontal reaction

$H = 113 \text{ k}$

Vertical reactions

Left reactions

$R_l = 26 \text{ k}$

Right reaction

$R_r = 64 \text{ k}$

Cable tension

At left support

$T_l = 115 \text{ k}$

At right support (maximum)

$T_r = 129 \text{ k}$

1 Cable roof structure

2 Parabolic cable by graphic method

Process:

Draw AB and AC (tangents of cable at supports)

Divide tangents AB and AC into equal segments

Lines connecting AB to AC define parabolic cable envelop

3 Cable profile

Process:

Define desired cable sag f (usually $f = L/10$)

Define point A at $2f$ below midpoint of line BC

AB and AC are tangents of parabolic cable at supports

Compute total load $W = w L$

4 Equilibrium vector polygon at supports (force scale: $1'' = 50 \text{ k}$)

Process:

Draw vertical vector (total load W)

Draw equilibrium polygon $W-T_l-Tr$

Draw equilibrium polygons at left support T_l-H-R_l

Draw equilibrium polygons at right support $Tr-R_r-H$

Measure vectors H, R_l, R_r at force scale

Note:


This powerful method finds five unknowns: H, R_l, R_r, T_l, Tr

The maximum cable force is at the highest support

5

This chapter introduces the theory and examples of strength, stiffness, and stability described in the following sections: Force types; force vs. stress; allowable stress; axial stress; shear stress; principle stress and Mohr's circle; torsion; strain; Hooke's law; Poisson's ratio; creep; elastic modulus; thermal strain; thermal stress; and stability.

Strength Stiffness Stability



	A	B	C	D	E
5					
6					


Force types

Forces on structures include tension, compression, shear, bending, and torsion. Their effects and notations are tabulated below and all but bending and related shear are described on the following pages. Bending and related shear are more complex and further described in the next chapter.

Type of forces			
Force type	Action	Symbol	Notation
Tension	Elongates	Internal reaction arrows	+
Compression	Shortens	Internal reaction arrows	-
Shear	Sliding force	Arrow couple	Clockwise couple +
Bending	Elongates one side shortens other side	Concave and convex arcs	Concave arc + Convex arc -
Torsion	Twists	Bar with arrows	Right-hand-rule +

- 1 Axial force (tension and compression)
- 2 Shear
- 3 Bending
- 4 Torsion
- 5 Force actions
- 6 Symbols and notations

- A Tension
- B Compression
- C Shear
- D Bending
- E Torsion



Force vs. stress

Force and stress refer to the same phenomena, but with different meanings. Force is an external action, measured in absolute units: # (pound), k (kip); or SI units: N (Newton), kN (kilo Newton). Stress is an internal reaction in relative units (force/area), measured in psi (pound per square inch), ksi (kip per square inch); or SI units: Pa (Pascal), kPa (kilo Pascal). Axial stress is computed as:

$$f = P / A$$

where

f = stress

P = force

A = cross section area

Note: stress can be compared to allowable stress of a given material.

- **Force** is the load or action on a member
- Stress can be compared to allowable stress for any material, expressed as:
 $F \geq f$ (Allowable stress must be equal or greater than actual stress)
 where
 F = allowable stress
 f = actual stress

The type of stress is usually defined by subscript:

F_a, f_a (axial stress, capital F = allowable stress)
 F_b, f_b (bending stress, capital F = allowable stress)
 F_v, f_v (shear stress, capital F = allowable stress)

The following examples of axial stress demonstrate force and stress relations:

1 Wood column (compression)

Assume: Force P = 2000#, allowable stress F = 1000 psi

A = 2 x 2 = 4 in² (cross section area)

Stress $f = P / A = 2000\# / 4$

$f = 500$ psi
 $1000 > 500$, ok

2 Steel rod (tension)

Assume: P = 6 k, 1/2" rod, $F_a = 30$ ksi

Cross section area $A = \pi r^2 = (0.5/2)^2 \pi$

Stress $f = P / A = 5 \text{ k} / 0.2$

$A = 0.2$ in²

$f = 25$ ksi

$25 < 30$, ok


3 Spiked heel on wood stair (compression)

Assume: P = 200# (impact load), A = 0.04 in², $F_a = 400$ psi


Stress $f = P / A = 200 / 0.04$

$f = 5000$ psi
 $5000 \gg 400$. NOT ok


Note: The heel would sink into the wood, yield it and mark an indentation




1



2



3



4

Axial stress

Axial stress acts in the axis of members, such as columns. Axial tension is common in rods and cables; while axial compression is common in walls and columns. The following examples illustrate axial design and analysis. Analysis determines if an element is ok; design defines the required size. The equation, $f_a = P/A$, is used for analysis. The equation $A = P/F_a$, is used for design. Allowable stress, F_a , includes a factor of safety.

1 Crane cable design

Assume: $P = 12 \text{ k}$, $F_a = 70 \text{ ksi}$

Find required cable size

Metallic cross section A_m (cables are about 60% metallic)

$$A_m = P / F_a = 12 \text{ k} / 70 \text{ ksi}$$

$$A_m = 0.17 \text{ in}^2$$

Gross cable area

$$A_g = A_m / 0.6 = 0.17 / 0.6$$

$$A_g = 0.28 \text{ in}^2$$

Cable size

$$\phi = 2 (A/\pi)^{1/2} = 2 (0.28 / \pi)^{1/2} = 0.6''$$

$$\text{use } \phi = 5/8''$$

2 Suspension hanger analysis (Hong Kong-Shanghai bank)

Assume: load per floor $P = 227 \text{ k}$, $F_a = 30 \text{ ksi}$, level 1 $A = 12 \text{ in}^2$, level 6 $A = 75 \text{ in}^2$

Hanger stress

$$\text{Level 1: } f_a = P / A = 227 / 12$$

$$f_a = 19 \text{ ksi} < 30$$

$$\text{Level 6: } f_a = 6 P / A = 6 \times 227 / 75$$

$$f_a = 18 \text{ ksi} < 30$$

3 Post/footing analysis

Assume: $P = 12,000 \text{ \#}$, 3'x3'x2' footing at 150 pcf, 4x4 post (3.5"x3.5" actual)

Allowable post stress $F_a = 1000 \text{ psi}$, allowable soil pressure $F_s = 2000 \text{ psf}$

Post stress

$$P/A = 12,000 \text{ \#} / (3.5'' \times 3.5'')$$

$$f_a = 980 \text{ psi} < 1000$$

Soil pressure

$$f_s = P/A = (12,000 \text{ \#} + 3' \times 3' \times 2' \times 150 \text{ pcf}) / (3' \times 3')$$

$$f_s = 1633 \text{ psf} < 2000$$

4 Slab/wall/footing, analyze a 1' wide strip

Assume: allowable wall stress $F_a = 360 \text{ psi}$; allowable soil pressure $F_s = 1500 \text{ psf}$

Concrete slab, $t = 8''$ thick, $L = 20'$ span

CMU wall, $h = 10'$, $DL = 80 \text{ psf}$, $t = 8''$ nominal ($7 \frac{5}{8}'' = 7.625''$ actual)

Slab load

$$100 \text{ psf } DL + 40 \text{ psf } LL$$

$$DL + LL = 140 \text{ psf}$$

Load at wall base

$$P = 140 \text{ psf } (20'/2) + 80 \text{ psf } (10')$$

$$P = 2,200 \text{ \#}$$

Wall stress

$$f_a = P / A = 2200 \text{ \#} / (12'' \times 7.625'')$$

$$f_a = 24 \text{ psi} < 360$$

Load on soil


$$P = 2200 + 150 \text{ pcf} \times 2' \times 1'$$

$$P = 2,500 \text{ \#}$$


Soil pressure

$$f_s = 2,500 \text{ \#} / (1' \times 2')$$


$$f_s = 1250 \text{ psf} < 1500$$




1




2




3



4



5



6

Shear stress

Shear stress occurs in many situations, including the following examples, but also in conjunction with bending, described in the next chapter on bending. Shear stress develops as a resistance to sliding of adjacent parts or fibers, as shown on the following examples. Depending on the number of shear planes (the joining surface [A] of connected elements) shear is defined as single shear or double shear.

A Shear plane

B Shear crack

1 Single shear

Assume: $P = 3 \text{ k} = 3000 \text{ \#}$, $2" \times 4"$ wood bars with $\frac{1}{2}"$ bolt of $F_v = 20 \text{ ksi}$

Shear area (bolt cross section)

$$A = \pi r^2 = \pi (0.5/2)^2$$

$$A = 0.2 \text{ in}^2$$

$$\text{Shear stress } f_v = P / A = 3 / 0.2$$

$$f_v = 15 \text{ ksi} < 20$$

2 Check end block (A)

Assume: Block length 6", wood $F_v = 95 \text{ psi}$, all other as above

End block shear area $A = 2 \times 2" \times 6"$

$$\text{Shear stress } f_v = P / A = 3000 \text{ \#} / 24$$

$$A = 24 \text{ in}^2$$

$$f_v = 125 \text{ psi} > 95$$

NOT ok

use $e = 8$

$$\text{Required block length } e = 125 \times 6" / 95 = 7.9:$$

3 Double shear

Assume: $P = 22 \text{ k}$, $2 \frac{5}{8}"$ bolts of $F_v = 20 \text{ ksi}$

Shear area $A = 4 \pi r^2 = 4 \pi (0.625/2)^2$

$$\text{Shear stress } f_v = P / A = 22 / 1.2$$

$$A = 1.2 \text{ in}^2$$

$$f_v = 18 \text{ ksi} < 20$$

4 Double shear, glued

Assume: $P = 6000 \text{ \#}$, Wood bars, $F_v = 95 \text{ psi}$

Shear area $A = 2 \times 4" \times 8"$

$$\text{Shear stress } F_v = P / A = 6000 / 64$$

$$A = 64 \text{ in}^2$$

$$f_v = 94 \text{ psi} < 95$$

5 Twin beam double shear

Assume: $P = R = 12 \text{ k}$, $2 \frac{1}{2}"$ bolts, $F_v = 20 \text{ ksi}$

Shear area $A = 4 \pi r^2 = 4 \pi (0.5/2)^2$

$$\text{Shear stress } f_v = P / A = 12 / 0.79$$

$$A = 0.79 \text{ in}^2$$

$$f_v = 15 \text{ ksi} < 20$$

6 Shear wall


Assume: $P = 20 \text{ k}$, $8"$ CMU wall, $t = 7.625"$, $L = 8'$, $F_v = 30 \text{ psi}$

Shear area $A = 7.625" \times 12" \times 8'$

$$\text{Shear stress } f_v = P / A = 20,000 \text{ \#} / 732$$

$$A = 732 \text{ in}^2$$

$$f_v = 27 \text{ psi} < 30$$




Torsion

Torsion is very common in machines but less common in building structures. The examples here include a small detail and an entire garage.

- 1 Door handle
Assume: $P = 10 \text{ \#}$, $e = 3''$

Torsion moment M
 $M = P e = 10 \times 3$

$M = 30 \text{ \#'}$



- 2 Tuck-under parking
Assume: Shear $e = 10'$, base shear $V = 12 \text{ k}$





Torsion moment M
 $M = V e = 12 \text{ k} \times 10'$

$M = 120 \text{ k'}$

Note:

The torsion moment is the product of base shear v and lever arm e , the distance from center of mass to center of resistance (rear shear wall).

In the past, torsion of tuck-under parking was assumed to be resisted by cross shear walls. However, since the Northridge Earthquake of 1994 where several buildings with tuck-under parking collapsed, such buildings are designed with moment resistant beam/column joints at the open rear side.



Principle stress

Shear stress in one direction, at 45 degrees acts as tensile and compressive stress, defined as *principle stress*. Shear stress is zero in the direction of principle stress, where the normal stress is maximum. At any direction between maximum principle stress and maximum shear stress, there is a combination of shear stress and normal stress. The magnitude of shear and principle stress is sometimes required for design of details. Professor Otto Mohr of Dresden University develop 1895 a graphic method to define the relationships between shear stress and principle stress, named **Mohr's Circle**. Mohr's circle is derived in books on mechanics (Popov, 1968).

Isostatic lines


Isostatic lines define the directions of principal stress to visualize the stress trajectories in beams and other elements. Isostatic lines can be defined by experimentally by photo-elastic model simulation or graphically by Mohr's circle.

- 1 Simple beam with a square marked for investigation
- 2 Free-body of square marked on beam with shear stress arrows
- 3 Free-body square with shear arrows divided into pairs of equal effect
- 4 Free-body square with principal stress arrows (resultant shear stress vectors)
- 5 Free-body square rotated 45 degrees in direction of principal stress
- 6 Beam with isostatic lines (thick compression lines and thin tension lines)


Note:

Under gravity load beam shear increases from zero at mid-span to maximum at supports. Beam compression and tension, caused by bending stress, increase from zero at both supports to maximum at mid-span. The isostatic lines reflect this stress pattern; vertical orientation dominated by shear at both supports and horizontal orientation dominated by normal stress at mid-span. Isostatic lines appear as approximate tension "cables" and compression "arches".


1



2



3



Strain


Strain is a deformation caused by stress, or change in temperature, described later. Strain may elongate or shorten a solid, depending on the type of stress.

Hooke's law


Material expand and contract under tension and compression, respectively. The stress/strain relationship, called *Hooke's law* after the English scientist Robert Hooke, who discovered it in the 17th century, has since been confirmed by many empirical tests. The Hooke's law assumes isotropic material (equal properties in any direction). The stress/strain relation is visualized here by a spring, as substitute for rods as used in testing machines, to amplify the deformation.

- 1 Elongation due to tension
- 2 Shortening due to compression
- 3 Stress / strain graph
- L Unstressed length
- ΔL Strain (elongation or shortening under load)
- P Applied load
- ϵ Unit strain Epsilon ($\epsilon = \Delta L / L$)
- E Elastic modulus $E = f / \epsilon f$
- A Cross section area of assumed rod


$$\text{Stress } f = P / A$$




1




3




5




7




2



4



6



8

Stress/strain relations

Although stress/strain tests may be done for any materials, for convenience the following test description assumes a steel rod. After measuring the unstressed length, load is applied and the strain recorded. The load is then incrementally increased and all related elongations recorded on a Cartesian graph, strain on the horizontal axis, stress on the vertical axis. The recorded measure points are connected by a line. A straight line implies linear stress/strain relations, a curved line implies non-linear relations. Most structural materials are linear up to the proportional limit, and non-linear beyond that point. If the rod returns to its original length after the load is removed, the material is considered *elastic*; if it remains deformed it is considered *plastic*. The remaining deformation is the *permanent set*. Rubber is an elastic material; clay a plastic material. Some materials, such as steel, are *elastic-plastic*, i.e., up to the *elastic limit* steel is elastic; beyond the elastic limit it is plastic. The transition from elastic to plastic strain is also called *yield point*. Materials which deform much and absorb energy before breaking are considered *ductile*; materials which break abruptly are considered *brittle*. Mild steel is considered a ductile material; concrete is usually brittle.

- 1 Test loads 1 to 5 kip
- 2 Stress-strain graph (horizontal axis = strain, vertical axis = stress)
- 3 Linear material (linear stress/strain relation)
- 4 Non-linear material (non-linear stress /strain relation)
- 5 Elastic material (returns to original size if unloaded, like rubber)
- 6 Plastic material (remains permanently deformed like clay)
- 7 Brittle material (breaks abruptly)
- 8 Ductile material (deforms and absorbs energy before breaking)

Elastic modulus

- E $E = f / \epsilon$ = Elastic Modulus (defines material stiffness)
 f Stress
 ϵ Unit strain ($\epsilon = \Delta L / L$)
 S Permanent set (remaining strain after stress is removed)


Derivation of working equation to compute strain:

$$\frac{\Delta L}{L} = \epsilon = \frac{f}{E} = \frac{P}{AE} \quad \text{solving for } \Delta L$$

$$\Delta L = PL / AE$$

The equation is used to compute strain due to load. It shows that strain:

- Increases with increasing P and L
- Increases inversely with A and E



Poisson's ratio

Poisson's ratio is named after French scientist *Poisson* who defined it 1807 as ratio of lateral strain / axial strain. All materials shrink laterally when elongated and expand when compressed. Poisson's ratio is defined as:

$$\nu = \text{lateral strain} / \text{axial strain}$$

Based on empirical tests, Poisson's ratio for most materials is in the range of 0.25 to 0.35; only rubber reaches 0.5, the maximum for isotropic material.

Creep

Creep is a time dependent strain, most critical in concrete where it is caused by moisture squeezed from pores under stress. Creep tends to diminish with time. Concrete creep may exceed elastic strain several times, as demonstrated by Case Study 9 of Northridge Earthquake failures (Schierle, 2002). Yet much research is needed to provide design data and guidelines regarding creep.

Elastic modulus



The elastic modulus E , also called modulus of elasticity or Young's modulus Y , after English scientist Young, who defined it 1807. The term elastic modulus is actually a misnomer since it defines stiffness, the opposite of elasticity.

Note:


Since $E = f / \epsilon$ and ϵ is a ratio without units, the elastic modulus has the same units as stress

- 1 Poisson's ratio effect
- 2 Creep deformation (C = creep, T = time)
- 3 Elastic / plastic stress / strain curve (E = elastic range, P = plastic range)
- 4 Abstract steel graph (A = *proportional limit*, B = *elastic limit*, C = *yield point*, CD = *yield plateau*, E = *ultimate strength*, F = *breaking point*)
- 5 Mild steel stress / strain curve
- 6 High strength steel stress / strain curve
- 7 Concrete stress / strain curve (compressive strengths: A=9 ksi, B=4 ksi, C=3 ksi)
- 8 Stress / strain of linearly elastic wood

Allowable stress vs. elastic modulus (typically about 1:1000 ratio)		
Material	Allowable stress (psi)	Elastic modulus (psi)
Wood	1,400	1,400,000
Steel	30,000	30,000,000
Masonry	1,500	1,500,000
Concrete	3,000	3,000,000




1



2

3



4

Strain examples

Elevator cables

Assume

4 cables $\phi \frac{1}{2}$ " each, 60% metallic area Breaking strength $F_y = 210$ ksi

Allowable stress $(210 \text{ ksi} / 3)$

Elastic Modulus

$L = 800'$ each

$P = 8\text{k}$

Metallic area

$$A_m = 4 \pi r^2 = 4 \times .6 \pi (0.5/2)^2$$

Stress

$$f = P / A = 8 / 0.47$$

$$F_a = 70 \text{ ksi}$$

$$E = 16,000 \text{ ksi}$$

$$A_m = 0.47 \text{ in}^2$$

$$f = 17 \text{ ksi}$$

$$17 < 70, \text{ ok}$$

Elongation under load

$$\Delta L = PL / AE$$

$$\Delta L = 8\text{k} \times 800' \times 12" / (0.47 \times 16000)$$

$$\Delta L = 10"$$

2 Suspended building

3 Differential strain

Assume

10 stories @ $14' = 10 \times 14' \times 12"$

$$L = 1680"$$

Average column stress

$$f = 18 \text{ ksi}$$

Average strand stress

$$f = 60 \text{ ksi}$$

Elastic modulus (steel)

$$E = 29,000 \text{ ksi}$$

Elastic modulus (strand)

$$E = 22,000 \text{ ksi}$$

$$\Delta L = PL/AE, \text{ since } f = P/A \rightarrow \Delta L = f L/E$$

Column strain

$$\Delta L = 18 \text{ ksi} \times 1680" / 29000$$

$$\Delta L = 1"$$

Strand strain

$$\Delta L = 60 \text{ ksi} \times 1680" / 22000$$

$$\Delta L = 4.6"$$


Differential settlement

$$\Delta L = 5.6"$$

4 Shorten hangers under DL to reduce differential strain, or prestress strands to reduce ΔL by half

Note: Differential strain is additive since both strains are downwards

To limit differential strain, suspended buildings have ≤ 10 stories / stack



Thermal strain

Unrestrained objects expand and contract if subjected to temperature increase and decrease, respectively. Thermal strain is defined by a coefficient α for each material. Thermal strain varies linearly with temperature variation.

- 1 Bar of initial length L
- 2 Thermal strain ΔL due to temperature increase, computed as:

$$\Delta L = \alpha \Delta t L$$

where

α = thermal coefficient (in/in/°F) [/°C (SI units)]

Δt = temperature increase (+) / decrease (-)

L = initial length

Thermal stress

Thermal stress is caused when thermal strain is prevented by restrains.

- 3 Bar of initial length L
- 4 Elongation ΔL due to heat
- 5 Heated bar reduced to initial length by load P
- 6 Restrained bar under stress

Thermal stress derivation:

Since $\Delta L = PL / AE$ and $f = P/A$

$\Delta L = f L / E \rightarrow f = E \Delta L / L$


$\Delta L = \alpha \Delta t L \rightarrow f = E \alpha \Delta t L / L$

$$f = \alpha \Delta t E$$




where

f = thermal stress

E = elastic modulus



Coefficient of thermal expansion α and elastic modulus E				
Material	US α ($10^{-6}/^{\circ}\text{F}$)	US $E\alpha$ (10^6psi)	SI α ($10^{-6}/^{\circ}\text{C}$)	SI $E\alpha$ (10^6gPa)
Aluminum	13	10	24	69
Steel	6.5	29	11.7	200
Concrete	6	3 – 4	11	20 – 28
Masonry	4	1 – 3	7	7 – 21
Wood	1.7 – 2.5	1.2 – 2.2	3.5 – 4.5	8 – 15
Glass	44	9.6	80	66
Plastics	68 – 80	0.3 – 0.4	122 – 144	2 – 2.8
Aluminum	13	10	24	70



Thermal examples

1 Curtain wall

Assume:

Aluminum curtain wall, find required expansion joint

$\Delta t = 100^\circ \text{F}$ (summer vs. winter temperature)

2 story mullion, $L = 30' \times 12" = 360"$

$\alpha = 13 \times 10^{-6} \text{ in/in/}^\circ \text{F}$

$E = 10 \times 10^6 \text{ psi}$

Thermal strain

$$\Delta L = \alpha \Delta t L = 13 \times 10^{-6} \times 100^\circ \times 360"$$

$$\Delta L = 0.47"$$

Use $\frac{1}{2}"$ expansion joints

$$0.5 > 0.47$$

Assume ignorant designer forgets expansion joint

Thermal stress:

$$f = \alpha \Delta t E = 13 \times 10^{-6} \times 100 \times 10 \times 10^6 \text{ psi}$$

$$f = 13,000 \text{ psi}$$

Note: 10^6 and 10^{-6} cancel out and can be ignored

13,000 psi is too much stress for aluminum

2 High-rise building, differential expansion

Assume:

Steel columns exposed to outside temperature

$\Delta t = 50^\circ \text{F}$ (south vs. north temperature)

$L = 840'$ (60 stories at 14')

$\alpha = 6.5 \times 10^{-6} \text{ in/in/}^\circ \text{F}$

Differential expansion

$$\Delta L = \alpha \Delta t L = 6.5 \times 10^{-6} \times 50^\circ \times 840' \times 12"$$

$$\Delta L = 3.3"$$

Note: the differential expansion would cause bending stress

3 Masonry expansion joints

(masonry expansion joints should be at maximum $L = 100'$)

Assume

Temperature variation $\Delta t = 70^\circ \text{F}$

Joint spacing $L = 100' \times 12"$

Thermal coefficient

E-modulus

$$L = 1200"$$

$$\alpha = 4 \times 10^{-6} / ^\circ \text{F}$$

$$E = 1.5 \times 10^6 \text{ psi}$$

Required joint width

$$\Delta L = \alpha \Delta t L = (4 \times 10^{-6}) 70^\circ (1200")$$

$$\Delta L = 0.34"$$

Use $\frac{3}{8}"$ expansion joint





$$0.375 > 0.34$$

Check thermal stress without expansion joint

$$f = \alpha \Delta t E$$

$$f = 4 \times 10^{-6} \times 70^\circ \times 1.5 \times 10^6$$

$$f = 280 \text{ psi}$$






Stability

Stability is more complex and in some manifestations more difficult to measure than strength and stiffness but can be broadly defined as capacity to resist:

- Displacement
- Overturning
- Collapse
- Buckling

Diagrams 1-3 give a theoretical definition; all the other diagrams illustrate stability of conceptual structures.

- 1 Unstable
- 2 Neutral
- 3 Stable
- 4 Weak stability: high center of gravity, narrow base
- 5 Strong stability: low center of gravity, broad base
- 6 Unstable post and beam portal
- 7 Stable moment frame
- 8 Unstable T-frame with pin joint at base
- 9 Stable twin T-frames



Buckling stability

Buckling stability is more complex to measure than strength and stiffness and largely based on empirical test data.. This introduction of buckling stability is intended to give only a qualitative intuitive understanding.

Column buckling is defined as function of slenderness and beam buckling as function of compactness. A formula for column buckling was first defined in the 18th century by Swiss mathematician Leonhard Euler. Today column buckling is largely based on empirical tests which confirmed Euler's theory for slender columns; though short and stubby columns may crush due to lack of compressive strength.

Beam buckling is based on empirical test defined by compactness, a quality similar to column slenderness.

- 1 Slender column buckles in direction of least dimension
- 2 Square column resist buckling equally in both directions
- 3 Blocking resists buckling about least dimension
- 4 Long and slender wood joist subject to buckling
- 5 blocking resists buckling of wood joist
- 6 Web buckling of steel beam
- 7 Stiffener plates resist web buckling

- A Blocking of wood stud
 B Blocking of wood joist
 C Stiffener plate welded to web
 P Load

6

Bending

Bending elements are very common in structures, most notably as beams. Therefore, the theory of bending is also referred to as beam theory, not only because beams are the most common bending elements but their form is most convenient to derive and describe the theory. For convenience, similar elements, such as joists and girders, are also considered beams. Although they are different in the order or hierarchy of structures, their bending behavior is similar to that of beams, so is that of other bending elements, such as slabs, etc., shown on the next page. Thus, although the following description applies to the other bending elements, the beam analogy is used for convenience.

Beams are subject to load that acts usually perpendicular to the long axis but is carried in bending along the long axis to vertical supports. Under gravity load beams are subject to bending moments that shorten the top in compression and elongate the bottom in tension. Most beams are also subject to shear, a sliding force, that acts both horizontally and vertically. Because beams and other bending elements are very common, the beam theory is important in structural design and analysis.

As for other structural elements, beam investigation may involve analysis or design; analysis, if a given beam is defined by architectural or other factors; design, if beam dimensions must be determined to support applied loads within allowable stress and deflection. Both, analysis and design, require to find the tributary load, reactions, shear, and bending moment. In addition, analysis requires to find deflections, shear- and bending stress, and verify if they meet allowable limits; by contrast design requires sizing the beam, usually starting with an estimated size.

The following notations are commonly used for bending and shear stress:

f_b = actual bending stress

F_b = allowable bending stress

f_v = actual shear stress

F_v = allowable shear stress

Allowable stresses are given in building codes for various materials.

Allowable stresses assumed in this chapter are:

Wood

F_b = 1450 psi (9998 kPa)


F_v = 95 psi (655 kPa)

Steel

F_b = 22 ksi (152 MPa)

F_v = 14 ksi (97 MPa)

The more complex design and analysis of concrete and masonry will be introduced later.




Bending and Shear

Although derivation and numeric examples are required to analyze and design beams, intuitive understanding is an important prerequisite to gain deeper insight into the behavior of beams. The following is an intuitive introduction to beam bending and shear. A simple beam with uniform load is used for convenience.

Bending moment

Gravity load on a simple beam shortens the top and elongates the bottom, causing compressive and tensile stresses at top and bottom, respectively; with zero stress at the neutral axis (N. A.). In beams of symmetrical cross-section, the neutral axis is at the center. The compressive and tensile stress blocks generate an internal force couple that resists the external bending moment caused by load.



- 1 Simple beam with pin and roller supports
- 2 Deformed beam under uniform gravity load
- 3 Free-body diagram with bending stress block that generates an internal force couple to resist the external bending moment caused by load



Shear force

With few exceptions, described later, shear coexists with bending. When shear is present it acts both horizontally and vertically at equal magnitude. In wood beams horizontal shear is more critical because wood's shear capacity is much smaller parallel than perpendicular to the grain.

- 1 Beam under uniform load with shear cracks as they occur in some concrete beams near the supports where shear is maximum
- 2 Tendency of beam parts to slide vertically generates vertical shear stress that is zero at mid-span and increases to maximum at the supports where the vertical shear deformation is greatest
- 3 Tendency of beam layers to slide horizontally generates horizontal shear that is zero at mid-span and increases toward the supports. This is visualized, assuming a beam composed of several boards
- 4 Shear diagram reflects shear distribution over beam length
- 5 Unloaded beam marked with squares to visualize shear
- 6 Loaded beam with squares deformed into rhomboids due to shear
- 7 Horizontal and vertical shear couples on a square beam part are equal to balance rotational tendencies ($\Sigma M = 0$). Therefore, horizontal and vertical shear stresses are equal at any point on the beam.
- 8 Shear vectors generate compression and tension diagonal to the shear. This tends to generate diagonal tension cracks in concrete beams



Bending and shear stress

Bending and shear stresses in beams relate to bending moment and shear force similar to the way axial stress relates to axial force ($f = P/A$). Bending and shear stresses are derived here for a rectangular beam of homogeneous material (beam of constant property). A general derivation follows later with the *Flexure Formula*.

- 1 Simple wood beam with hatched area and square marked for inquiry
- 2 Shear diagram with hatched area marked for inquiry
- 3 Bending moment diagram with hatched area marked for inquiry
- 4 Partial beam of length x , with stress blocks for bending f_b and shear f_v , where x is assumed a differential (very small) length

Reactions, found by equilibrium $\Sigma M = 0$ (clockwise +)

$$\text{at c: } +12 R_a - 3(8) = 0; R_a = 3(8)/12$$

$$R_a = 2 \text{ k}$$

$$\text{at a: } -12 R_c + 3(4) = 0; R_c = 3(4)/12$$

$$R_c = 1 \text{ k}$$

Shear V, found by vertical equilibrium, $\Sigma V = 0$ (upward +).

$$\text{right of a and left of b: } V = 0 + 2$$

$$V = 2 \text{ k}$$

$$\text{right of b and left of c: } V = 2 - 3$$

$$V = -1 \text{ k}$$

Bending moment M, found by equilibrium $\Sigma M = 0$ (clockwise +)

$$\text{at a: } M = +2(0)$$

$$M = 0 \text{ k'}$$

$$\text{at b: } M = +2(4)$$

$$M = 8 \text{ k'}$$

$$\text{at c: } M = +2(12) - 3(8)$$

$$M = 0 \text{ k'}$$

Bending stress f_b is derived, referring to 4. Bending is resisted by the force couple C-T, with lever arm $2/3 d$ = distance between centroids of triangular stress blocks. $C = T = f_b bd/4$, $M = C(2d/3) = (f_b bd/4)(2d/3) = f_b bd^2/6$, or $f_b = M/(bd^2/6)$; where $bd^2/6 = S$ = **Section Modulus** for rectangular beam; thus

$$f_b = M/S$$

$$\text{For our beam: } S = bd^2/6 = 4(12)^2/6 =$$

$$S = 96 \text{ in}^3$$

$$f_b = M/S = 8(1000)/96 *$$

$$f_b = 1000 \text{ psi}$$

* multiplying by 1000 converts kips to pounds, by 12 converts feet to inches.


Shear stress f_v is derived, referring to 4. Bending stress blocks pushing and pulling in opposite directions create horizontal shear stress. The maximum shear stress is $f_v = C/bx$, where b = width and x = length of resisting shear plane. Shear at left support is $V = R$. Let M = bending moment at x , and f_b = bending stress at x , then $M = RX = VX$, and $f_b = M/S = Vx/S$. Substituting Vx/S for f_b in $C = f_b bd/4$, the compressive top force, yields $C = (Vx/S)(bd/4)$. Thus $f_v = C/(bx)$ yields $f_v = (Vx/S)(bd/4)/(bx)$. Substituting $bd^2/6$ for S yields

$$f_v = \frac{Vx}{bd^2/6} \frac{bd/4}{bx} = \frac{Vbd/4}{b^2d^2/6} = \frac{6V}{4bd}, \text{ or}$$

$$f_v = 1.5 V / bd$$

$$\text{For the sample beam: } f_v = 1.5(2)/1000/(4 \times 12)$$

$$f_v = 63 \text{ psi}$$



Equilibrium Method

Cantilever beam with point load

Assume a beam of length $L = 10$ ft, supporting a load $P = 2$ k. The beam bending moment and shear force may be computed, like the external reactions, by equations of equilibrium $\Sigma H = 0$, $\Sigma V = 0$, and $\Sigma M = 0$. Bending moment and shear force cause bending- and shear stress, similar to axial load yielding axial stress $f = P/A$. Formulas for bending- and shear stress are given on the next page and derived later in this chapter.

- 1 Cantilever beam with concentrated load
- V Shear diagram (shear force at any point along beam)
- M Bending moment diagram (bending moment at any point along beam)
- Δ Deflection diagram (exaggerated for clarity)

Reactions, found by equilibrium, $\Sigma V = 0$ (up +) and $\Sigma M = 0$ (clockwise +)

at b $\Sigma V = 0 =$	$R - 2 = 0$	$R = 2$ k
at b $\Sigma M = 0 =$	$M - 2(10) = 0$	$M = 20$ k'

Shear V, found by vertical equilibrium, $\Sigma V = 0$ (up +)

right of a = left of b	$V = 0 - 2$	$V = -2$ k
----------------------------	-------------	------------


Left of a and right of b , shear is zero because there is no beam to resist it (reaction at b reduces shear to zero). Shear may be checked, considering it starts and stops with zero. Concentrated loads or reactions change shear from left to right of them. Without load between a and b (beam DL assumed negligible) shear is constant.

Bending moment M, found by moment equilibrium, $\Sigma M = 0$ (clockwise +)

at a $M = -2(0)$	$= 0$ k'
at mid-span $M = -2(5)$	$= -10$ k'
at b $M = -2(10)$	$= -20$ k'

The mid-span moment being half the moment at b implies linear distribution. The support reaction moment is equal and opposite to the beam moment.

Deflection Δ is described later. Diagrams visualize positive and negative bending by concave and convex curvature, respectively. They are drawn, visualizing a highly flexible beam, and may be used to verify bending.



Simple beam with uniform load

- 1 Beam of $L = 20$ ft span, with uniformly distributed load $w = 100$ plf
- 2 Free-body diagram of partial beam x units long
- 3 Shear diagram
- 4 Bending moment diagram

To find the distribution of shear and bending along the beam, we investigate the beam at intervals of 5', from left to right. This is not normally required.

Reactions R are half the load on each support due to symmetry

$$R = wL/2 = 100(20)/2$$

$$R = +1000 \text{ lbs}$$

Shear force V_x at any distance x from left is found using $\sum V = 0$

$$\sum V = 0; \quad R - wx - V_x = 0;$$

solving for V_x

$$V_x = R - wx$$

$$\text{at } x = 0' \quad V = 0 + R_a = 0 + 1000$$

$$V = +1000 \text{ lbs}$$

$$\text{at } x = 5' \quad V = +1000 - 100(5)$$

$$V = +500 \text{ lbs}$$

$$\text{at } x = 10' \quad V = +1000 - 100(10)$$

$$V = 0 \text{ lbs}$$

$$\text{at } x = 15' \quad V = +1000 - 100(15)$$

$$V = -500 \text{ lbs}$$

$$\text{at } x = 20' \quad V = +1000 - 100(20)$$

$$V = -1000 \text{ lbs}$$

Bending moment M_x at any distance x from left is found by $\sum M = 0$.

$$\sum M = 0; \quad Rx - wx(x/2) - M_x = 0;$$

solving for M_x

$$M_x = Rx - wx^2/2$$

$$\text{at } x = 0 \quad M = 1000(0) - 100(0)^2/2$$

$$M = 0 \text{ lb-ft}$$

$$\text{at } x = 5' \quad M = 1000(5) - 100(5)^2/2$$

$$M = 3750 \text{ lb-ft}$$

$$\text{at } x = 10' \quad M = 1000(10) - 100(10)^2/2$$

$$M = 5000 \text{ lb-ft}$$

$$\text{at } x = 15' \quad M = 1000(15) - 100(15)^2/2$$

$$M = 3750 \text{ lb-ft}$$

$$\text{at } x = 20' \quad M = 1000(20) - 100(20)^2/2$$

$$M = 0 \text{ lb-ft}$$

Bending is zero at both supports since pins and rollers have no moment resistance. Since the bending formula $M_x = Rx - wx^2/2$ is quadratic, bending increase is quadratic (parabolic curve) toward maximum at center, and decreases to zero at the right support. For simple beams with uniform load the maximum shear force is at the supports and the maximum bending moment at mid-span ($x = L/2$) are:

$$V_{\max} = R = wL/2$$

$$M_{\max} = (wL/2)L/2 - (wL/2)L/4 = 2wL^2/8 - wL^2/8, \text{ or}$$


$$M_{\max} = wL^2/8$$

This formula is only for simple beams with uniform load. Verifying example:

$$M_{\max} = wL^2/8 = 100(20)^2/8$$

$$M_{\max} = +5000 \text{ lbs-ft}$$

(same as above)



Area Method

The area method for beam design simplifies computation of shear forces and bending moments and is derived, referring to the following diagrams:

- 1 Load diagram on beam
- 2 Beam diagram
- 3 Shear diagram
- 4 Bending diagram

The area method may be stated:

- The shear at any point n is equal to the shear at point m plus the area of the load diagram between m and n .
- The bending moment at any point n is equal to the moment at point m plus the area of the shear diagram between m and n .

The shear force is derived using vertical equilibrium:

$$\sum V = 0; \quad V_m - w x - V_n = 0; \quad \text{solving for } V_n$$

$$V_n = V_m - wx$$

where $w x$ is the load area between m and n (downward load $w = \text{negative}$).

The bending moment is derived using moment equilibrium:

$$\sum M = 0; \quad M_m + V_m x - w x x/2 - M_n = 0; \quad \text{solving for } M_n$$

$$M_n = M_m + V_m x - wx^2/2$$



where $V_m x - wx^2/2$ is the shear area between m and n , namely, the rectangle $V_m x$ less the triangle $w x^2/2$. This relationship may also be stated as $M_n = M_m + Vx$, where V is the average shear between m and n .

By the area method moments are usually equal to the area of one or more rectangles and/or triangles. It is best to first compute and draw the shear diagram and then compute the moments as the area of the shear diagram.

From the diagrams and derivation we may conclude:

- Positive shear implies increasing bending moment.
- Zero shear (change from $+$ to $-$) implies peak bending moment (useful to locate maximum bending moment).
- Negative shear implies decreasing bending moment.

Even though the foregoing is for uniform load, it applies to concentrated load and non-uniform load as well. The derivation for such loads is similar.



Examples

The following wood beams demonstrate the area method for design and analysis. For design, a beam is sized for given loads; for analysis, stresses are checked against allowable limits, or how much load a beam can carry.

Beam design

V Shear diagram.

M Bending diagram.

Δ Deflection diagram.

I Inflection point (change from + to - bending).

Reactions

$$R = 400 \text{ plf} (24)/2$$

$$R = 4800 \text{ lbs}$$

Shear

$$V_a = 0$$

$$V_a = 0 \text{ lbs}$$

$$V_{bl} = 0 - 400(5)$$

$$V_{bl} = -2000 \text{ lbs}$$

$$V_{br} = -2000 + 4800$$

$$V_{br} = +2800 \text{ lbs}$$

$$V_{cl} = +2800 - 400(14)$$

$$V_{cl} = -2800 \text{ lbs}$$

$$V_{cr} = -2800 + 4800$$

$$V_{cr} = +2000 \text{ lbs}$$

$$V_d = +2000 - 400(5)$$

$$V_d = 0 \text{ lbs, ok}$$

Moment

$$M_a = 0$$

$$M_b = 0 - 2000 (5)/2$$

$$M_b = -5000 \text{ lb-ft}$$

$$M_{b-c} = -5000 + 2800 (7)/2$$

$$M_{b-c} = +4800 \text{ lb-ft}$$

$$M_c = +4800 - 2800 (7)/2$$

$$M_c = -5000 \text{ lb-ft}$$

$$M_d = -5000 + 2000 (5)/2$$

$$M_d = 0, \text{ ok}$$

Try 4x10 beam

$$S = (3.5) 9.25^2/6$$

$$S = 50 \text{ in}^3$$

Bending stress

$$f_b = M_{\max}/S = 5000 (12)/50$$

$$f_b = 1200 \text{ psi}$$

$$1200 < 1450, \text{ ok}$$

Shear stress

$$f_v = 1.5V/bd = 1.5(2800)/[3.5(9.25)]$$

$$f_v = 130 \text{ psi}$$

$$130 > 95, \text{ not ok}$$


Try 6x10 beam

$$f_v = 1.5V/bd = 1.5 (2800)/[5.5 (9.25)]$$

$$f_v = 83 \text{ psi}$$

$$83 < 95, \text{ ok}$$

Note: increased beam width is most effective to reduce shear stress; but increased depth is most effective to reduce bending stress.



Beam analysis

Reactions

$$\Sigma M_c = 0 = +16 R_b - 1000(20) - 300(4)(18) - 200(16)(8)$$

$$16 R_b = 1000(20) + 300(4)(18) + 200(16)(8)$$

$$R_b = (20000 + 21600 + 25600)/16$$

$$R_b = +4200 \text{ lbs}$$

$$\Sigma M_b = 0 = -16 R_c - 1000(4) - 300(4)(2) + 200(16)(8)$$

$$16 R_c = -1000(4) - 300(4)(2) + 200(16)(8)$$

$$R_c = (-4000 - 2400 + 25600)/16 =$$

$$R_c = +1200 \text{ lbs}$$

Shear

$$V_{ar} = 0 - 1000$$

$$V_{ar} = -1000 \text{ lbs}$$

$$V_{bl} = -1000 - 300(4)$$

$$V_{bl} = -2200 \text{ lbs}$$

$$V_{br} = -2200 + 4200$$

$$V_{br} = +2000 \text{ lbs}$$

$$V_{cl} = +2000 - 200(16) = -R_c$$

$$V_{cl} = -1200 \text{ lbs}$$

$$V_{cr} = -1200 + 1200$$

$$V_{cr} = 0 \text{ lbs}$$

Find x, where shear = 0 and bending = maximum:

$$V_{br} - w_2 x = 0; x = V_{br}/w_2 = 2000/200$$

$$x = 10 \text{ ft}$$

Moment

$$M_a = 0$$

$$M_b = 0 + 4(-1000 - 2200)/2$$

$$M_b = -6400 \text{ lb-ft}$$

$$M_x = -6400 + 10(2000)/2$$

$$M_x = +3600 \text{ lb-ft}$$

$$M_c = +3600 + (16-10)(-1200)/2$$

$$M_c = 0$$

Section modulus

$$S = bd^2/6 = (3.5)(11.25)^2/6$$

$$S = 74 \text{ in}^3$$

Bending stress

$$f_b = M/S = 6400(12)/74$$

$$f_b = 1038 \text{ psi}$$

$$1038 < 1450, \text{ ok}$$

Shear stress


$$f_v = 1.5V/(bd) = 1.5(2200)/[3.5(11.25)]$$

$$f_v = 84 \text{ psi}$$

$$84 < 95 = \text{ok}$$

Note: stress is figured, using absolute maximum bending and shear, regardless if positive or negative. Lumber sizes are nominal, yet actual sizes are used for computation. Actual sizes are 1/2 in. less for lumber up to 6 in. nominal and 3/4 in. less for larger sizes: 4x8 nominal is 3 1/2 x 7 1/4 in. actual.

Note: in the above two beams shear stress is more critical (closer to the allowable stress) than bending stress, because negative cantilever moments partly reduces positive moments.



Indeterminate beams

Indeterminate beams include beams with fixed-end (moment resistant) supports and beams of more than two supports, referred to as continuous beams. The design of statically indeterminate beams cannot be done by static equations alone. However, bending coefficients, derived by mechanics, may be used for analysis of typical beams. The bending moment is computed, multiplying the bending coefficients by the total load W and span L between supports. For continuous beams, the method is limited to beams of equal spans for all bays. The coefficients here assume all bays are loaded. Coefficients for alternating live load on some bays and combined dead load plus live load on others, which may result in greater bending moments, are in Appendix A. Appendix A also has coefficients for other load conditions, such as various point loads. The equation for bending moments by bending coefficients is:

$$M = C L W$$



M = bending moment

C = bending coefficient


L = span between supports

$W = w L$ (total load per bay)

w = uniform load in plf (pounds / linear foot)



- 1 Simple beam
- 2 Fixed-end beam
(combined positive plus negative moments equal the simple-beam moment)
- 3 Two-span beam
- 4 Three-span beam



Flexure Formula

The flexure formula gives the internal bending stress caused by an external moment on a beam or other bending member of homogeneous material. It is derived here for a rectangular beam but is valid for any shape.

- 1 Unloaded beam with hatched square
- 2 Beam subject to bending with hatched square deformed
- 3 Stress diagram of deformed beam subject to bending

Referring to the diagram, a beam subject to positive bending assumes a concave curvature (circular under pure bending). As illustrated by the hatched square, the top shortens and the bottom elongates, causing compressive stress on the top and tensile stress on the bottom. Assuming stress varies linearly with strain, stress distribution over the beam depth is proportional to strain deformation. Thus stress varies linearly over the depth of the beam and is zero at the neutral axis (NA). The bending stress f_y at any distance y from the neutral axis is found, considering similar triangles, namely f_y relates to y as f relates to c ; f is the maximum bending stress at top or bottom and c the distance from the Neutral Axis, namely $f_y / y = f / c$. Solving for f_y yields

$$f_y = y f / c$$

To satisfy equilibrium, the beam requires an internal resisting moment that is equal and opposite to the external bending moment. The internal resisting moment is the sum of all partial forces F rotating around the neutral axis with a lever arm of length y to balance the external moment. Each partial force F is the product of stress f_y and the partial area a on which it acts, $F = a f_y$. Substituting $f_y = y f / c$, defined above, yields $F = a y f / c$. Since the internal resisting moment M is the sum of all forces F times their lever arm y to the neutral axis, $M = F y = (f/c) \sum y y a = (f/c) \sum y^2 a$, or $M = I f / c$, where the term $\sum y^2 a$ is defined as *moment of inertia* ($I = \sum y^2 a$) for convenience. In formal calculus the summation of area a is replaced by integration of the differential area da , an infinitely small area:

$$I = \int y^2 da$$

$I = \text{moment of inertia.}$

The internal resisting moment equation $M = I f / c$ solved for stress f yields

$$f = M c / I$$


the *flexure formula*,

which gives the bending stress f at any distance c from the neutral axis. A simpler form is used to compute the *maximum* fiber stress as derived before. Assuming c as maximum fiber distance from the neutral axis yields:


$$f = M / S$$

$S = I / c = \text{section modulus}$


Both the moment of inertia I and section modulus S define the strength of a cross-section regarding its geometric form.



1



2



3

Section modulus

Rectangular beams of homogeneous material, such as wood, are common in practice. The section modulus for such beams is derived here.

- 1 Stress block in rectangular beam under positive bending.
- 2 Large stress block and lever-arm of a joist in typical upright position.
- 3 Small, inefficient, stress block and lever-arm of a joist laid flat.

Referring to 1, the section modulus for a rectangular beam of homogeneous material may be derived as follows. The force couple C and T rotate about the neutral axis to provide the internal resisting moment. C and T act at the center of mass of their respective triangular stress block at $d/3$ from the neutral axis. The magnitude of C and T is the volume of the upper and lower stress block, respectively.

$$C = T = (f/2) (bd/2) = f b d/4.$$

The internal resisting moment is the sum of C and T times their respective lever arm, $d/3$, to the neutral axis. Hence

$$M = C d/3 + T d/3. \text{ Substituting } C = T = f b d/4 \text{ yields}$$

$$M = 2 (f b d/4) d/3 = f b d^2/6, \text{ or } M = f S,$$

where $S = b d^2/6$, defined as the section modulus for rectangular beams of homogeneous material.

$$S = b d^2/6$$

Solving $M = f S$ for f yields the maximum bending stress as defined before:

$$f = M/S$$


This formula is valid for homogeneous beams of any shape; but the formula $S = b d^2/6$ is valid for rectangular beams only. For other shapes S can be computed as $S = I/c$ as defined before for the flexure formula. The moment of inertia I for various common shapes is given in Appendix A.

Comparing a joist of 2"x12" in upright and flat position as illustrated in 2 and 3 yields an interesting observation:


$$S = 2 \times 12^2/6 = 48 \text{ in}^3 \quad \text{for the upright joist}$$

$$S = 12 \times 2^2/6 = 8 \text{ in}^3 \quad \text{for the flat joist.}$$


The upright joist is six times stronger than the flat joist of equal cross-section. This demonstrates the importance of correct orientation of bending members, such as beams or moment frames.




1



2



3



4


Moment of inertia

The formula for the moment of inertia $I = \int y^2 da$ reveals that the resistance of any differential area da increases with its distance y from the neutral axis squared, forming a parabolic distribution. For a beam of rectangular cross-section, the resistance of top and bottom fibers with distance $y = d/2$ from the neutral axis is $(d/2)^2$. Thus, the moment of inertia, as geometric resistance, is the volume of all fibers under a parabolic surface, which is $1/3$ the volume of a cube of equal dimensions, or $I = bd(d/2)^2/3$, or

$$I = bd^3 / 12 \quad (\text{for rectangular beams only})$$

the moment of inertia of a rectangular beam of homogeneous material. A formal calculus derivation of this formula is given in Appendix A. The section modulus gives only the maximum bending stress, but the moment of inertia gives the stress at any distance c from the neutral axis as $f = Mc/I$. This is useful, for example, for bending elements of asymmetrical cross-section, such as T- and L-shapes.

- 1 Bending stress distribution over beam cross-section
- 2 Moment of inertia visualized as volume under parabolic surface
- 3 T-bar with asymmetrical stress: max. stress at c_2 from the neutral axis
- 4 Angle bar with asymmetrical stress distribution about x, y, and z-axes: maximum resistance about x-axis and minimum resistance about z-axis



Shear stress

The distribution of shear stress over the cross-section of beams is derived, referring to a beam part of length x marked on diagrams. Even though horizontal and vertical shear are equal at any part of a beam, horizontal shear stress is derived here because it is much more critical in wood due to horizontal fiber direction.

- 1 Beam, shear and bending diagrams with marked part of length x
- 2 Beam part with bending stress pushing and pulling to cause shear
- 3 Beam part with bending stress above an arbitrary shear plane

Let M be the differential bending moment between m and n . M is equal to the shear area between m and n (area method), thus $M = V x$. Substituting $V x$ for M in the flexure formula $f = M c / I$ yields bending stress $f = V x c / I$ in terms of shear. The differential bending stress between m and n pushes top and bottom fibers in opposite directions, causing shear stress. At any shear plane y_1 from the neutral axis of the beam the sum of shear stress above this plane yields a force F that equals average stress f_y times the cross section area A above the shear plane, $F = A f_y$. The average stress f_y is found from similar triangles; f_y relates to y as f relates to c , i.e., $f_y / y = f / c$; thus $f_y = f y / c$. Since $f = V x c / I$, substituting $V x c / I$ for f yields $f_y = (V x c / I) y / c = V x y / I$. Since $F = A f_y$, it follows that $F = A V x y / I$. The horizontal shear stress v equals the force F divided by the area of the shear plane;

$$V = F / (x b) = A V x y / (I x b) = V A y / (I b)$$

The term $A y$ is defined as Q , the first static moment of the area above the shear plane times the lever arm from its centroid to the neutral axis of the entire cross-section. Substituting Q for $A y$ yields the working formula

$$v = V Q / (I b) \quad (\text{shear stress})$$

v = horizontal shear stress.

Q = static moment (area above shear plane times distance from centroid of that area to the neutral axis of the entire cross-section)




I = moment of Inertia of entire cross section

b = width of shear plane

The formula for shear stress can also be stated as shear flow q , measured in force per unit length (pound per linear inch, kip per linear inch, or similar metric units); hence

$$q = V Q / I \quad (\text{shear flow})$$

q = force per unit length



Shear stress in wood and steel beams

Based on the foregoing general derivation of shear stress, the formulas for shear stress in rectangular wood beams and flanged steel beams is derived here. The maximum stress in those beams is customarily defined as f_v instead of v in the general shear formula.

- 1 Shear at neutral axis of rectangular beam (maximum stress),
 $Q = Ay = (bd/2) d/4$, or
 $Q = bd^2/8$ (Note: d^2 implies parabolic distribution)
 $I = bd^3/12$, hence
 $v = VQ / Ib = V (bd^2/8) / [(bd^3/12)b] = f_v$, or

$$f_v = 1.5 V / (bd)$$

Note: this is the same formula derived for maximum shear stress before

- 2 Shear stress at the bottom of rectangular beam. Note that $y = 0$ since the centroid of the area above the shear plane (bottom) coincides with the neutral axis of the entire section. Thus $Q = Ay = (bd/2) 0 = 0$, hence
 $v = VQ / (Ib) = 0 = f_v$, thus
 $f_v = 0$

Note: this confirms an intuitive interpretation that suggests zero stress since no fibers below the beam could resist shear

- 3 Shear stress at top of rectangular beam. Note $A = 0b = 0$ since the depth of the shear area above the top of the beam is zero. Thus
 $Q = Ay = 0 d/2 = 0$, hence $v = VQ / (Ib) = 0 = f_v$, thus
 $f_v = 0$

Note: this, too, confirms an intuitive interpretation that suggests zero stress since no fibers above the beam top could resist shear.



- 4 Shear stress distribution over a rectangular section is parabolic as implied by the formula $Q = bd^2/8$ derived above.
- 5 Shear stress in a steel beam is minimal in the flanges and parabolic over the web. The formula $v = VQ / (Ib)$ results in a small stress in the flanges since the width b of flanges is much greater than the web thickness. However, for convenience, shear stress in steel beams is computed as "average" by the simplified formula:

$$f_v = V / A_v$$

f_v = shear stress in steel beam

V = shear force at section investigated

A_v = shear area, defined as web thickness times beam depth



Shear stress in wood I-beam

Since this is not a rectangular beam, shear stress must be computed by the general shear formula. The maximum shear stress at the neutral axis as well as shear stress at the intersection between flange and web (shear plane A_s) will be computed. The latter gives the shear stress in the glued connection. To compare shear- and bending stress the latter is also computed.

- 1 Beam of $L = 10$ ft length, with uniform load $w = 280$ plf ($W = 2800$ lbs)
- 2 Cross-section of wood I-beam

$$\text{Shear force } V = W/2 = 2800/2$$

$$V = 1400 \text{ lbs}$$

$$\text{Bending moment } M = WL/8 = 2800(10)/8$$

$$M = 3500 \text{ lb'}$$

For the formula $v = VQ/(Ib)$ we must find the moment of inertia of the entire cross-section. We could use the *parallel axis theorem* of Appendix A. However, due to symmetry, a simplified formula is possible, finding the moment of inertia for the overall dimensions as rectangular beam minus that for two rectangles on both sides of the web.

$$I = (BD^3 - bd^3)/12 = [6(10)^3 - 2(2)^3]/12$$

$$I = 428 \text{ in}^4$$

$$\text{Bending stress } f_b = Mc/I = 3500(12)/428$$

$$f_b = 491 \text{ psi}$$

$$491 < 1450, \text{ ok}$$

Note $c = 10/2 = 5$ (half the beam depth due to symmetry)

Static moment Q of flange about the neutral axis:

$$Q = Ay = 6(2)4$$

$$Q = 48 \text{ in}^3$$

Shear stress at flange/web intersection:

$$v = VQ/(Ib) = 1400(48)/[428(2)]$$

$$v = 79 \text{ psi}$$

Static moment Q of flange plus upper half of web about the neutral axis

$$Q = \Sigma Ay = 6(2)4 + 2(3)1.5$$

$$Q = 57 \text{ in}^3$$

Maximum shear stress at neutral axis:

$$v = VQ/(Ib) = 1400(57)/[428(2)]$$

$$v = 93 \text{ psi} < 95, \text{ ok}$$

Note: Maximum shear stress reaches almost the allowable stress limit, but bending stress is well below allowable bending stress because the beam is very short. We can try at what span the beam approaches allowable stress, assuming $L = 30$ ft, using the same total load $W = 2800$ lbs to keep shear stress constant:

$$M = WL/8 = 2800(30)/8$$





$$M = 10500 \text{ lb-ft}$$

$$f_b = Mc/I = 10500(12)/428$$

$$f_b = 1472 \text{ psi}$$

$$1472 > 1450, \text{ not ok}$$

At 30 ft span bending stress is just over the allowable stress of 1450 psi. This shows that in short beams shear governs, but in long beams bending or deflection governs.



Shear stress in steel beam

This beam, supporting a column point load of 96 k over a door, is a composite beam consisting of a wide-flange base beam with 8x½ in plates welded to top and bottom flanges. The beam is analyzed with and without plates. As shown before, for steel beams shear stress is assumed to be resisted by the web only, computed as $f_v = V/A_v$. The base beam is a W10x49 [10 in (254 mm) nominal depth, 49 lbs/ft (6.77 kg/m) DL] with a moment of inertia $I_{xx} = 272 \text{ in}^4$ (11322 cm⁴) (see Appendix). Shear in the welds connecting the plates to the beam is found using the shear flow formula $q = VQ/I$.

- 1 Beam of $L = 6 \text{ ft}$ (1.83 m) span with $P = 96 \text{ k}$ point load
- 2 Composite wide-flange beam W10x49 with 8x½ inch stiffener plates

$$\text{Shear force } V = P/2 = 96/2$$

$$V = 48 \text{ k}$$

$$\text{Bending moment } M = 48(3)$$

$$M = 144 \text{ k'}$$

Wide-flange beam

Shear area of web $A_v = \text{web thickness} \times \text{beam depth}$

$$A_v = 0.34(10)$$

$$A_v = 3.4 \text{ in}^2$$

$$\text{Shear stress } f_v = V/A_v = 48/3.4$$

$$f_v = 14 \text{ ksi}$$

$$14 < 14.5, \text{ ok}$$

$$\text{Bending stress } f_b = Mc/I = 144(12)5.5/272$$

$$f_b = 35 \text{ ksi}$$

$$35 > 22, \text{ not ok}$$

Since the beam would fail in bending, a composite beam is used.

Composite beam

Moment of inertia $I = \Sigma(I_{oo} + Ay^2)$ (see *parallel axis theorem* in Appendix A)

$$I = 272 + 2(8)0.5^3/12 + 2(8)0.5(5.25)^2$$

$$I = 493 \text{ in}^4$$

$$\text{Bending stress } f_b = Mc/I = 144(12)5/493$$

$$f_b = 19 \text{ ksi}$$

$$19 < 22, \text{ ok}$$

Since the shear force remains unchanged, the web shear stress is still ok.

Shear flow q in welded plate connection

$$Q = Ay = 8(.5)5.25 = 21 \text{ in}^3$$

$$q_{\text{tot}} = VQ/I = 48(21)/493$$

$$q_{\text{tot}} = 2 \text{ k/in}$$

Since there are two welds, each resists half the total shear flow

$$q = q_{\text{tot}}/2$$





$$q = 1 \text{ k/in}$$

Assume ¼ in weld of 3.2 k/in * strength

$$1 < 3.2, \text{ ok}$$

* see AISC weld strength table













Note: in this steel beam, bending stress is more critical than shear stress; this is typical for steel beams, except very short ones.



Deflection formulas

Based on the moment-area method, the following formulas for slope and deflection are derived for beams of common load and support conditions. Additional formulas are provided in Appendix A. Although downward deflection would theoretically be negative, it is customary to ignore the sign convention and define up- or downward deflection by inspection. The angle θ is the slope of the tangent to the elastic curve at the free end for cantilever beams and at supports for simple beams; Δ is the maximum deflection for all cases. As derived before, θ is the area of the bending moment diagram divided by EI , the elastic modulus and moment of inertia, respectively; Δ equals θ times the lever-arm from the centroid of the bending moment diagram between zero and maximum deflection to the point where θ is maximum.

- 1 Cantilever beam with point load; $\theta = (PL)(L/2)/(EI)$, $\Delta = \theta \frac{2}{3} L$
 $\theta = \frac{1}{2} PL^2/(EI)$
 $\Delta = \frac{1}{3} PL^3/(EI)$
- 2 Cantilever beam with uniform load; $\theta = (WL/2)(L/3)/(EI)$, $\Delta = \theta \frac{3}{4} L$
 $\theta = \frac{1}{6} WL^2/(EI)$
 $\Delta = \frac{1}{8} WL^3/(EI)$
- 3 Simple beam with point load; $\theta = (PL/4)(L/4)/(EI)$, $\Delta = \theta \frac{1}{3} L$
 $\theta = \frac{1}{16} PL^2/(EI)$
 $\Delta = \frac{1}{48} PL^3/(EI)$
- 4 Simple beam with uniform load; $\theta = (WL/8)(2/3 L/2)/(EI)$, $\Delta = \theta \frac{5}{16} L$
 $\theta = \frac{1}{24} WL^2/(EI)$
 $\Delta = \frac{5}{384} WL^3/(EI)$



Typical beam diagrams

Deflection, shear, and bending diagrams are shown here for typical beams. The beam with deflection and load diagrams are drawn on top with shear and bending diagrams shown below. With experience, these diagrams may be drawn by visual inspection prior to computing. This is useful to verify computations and develop an intuitive sense and visualization regarding shear and bending on beams. The deflection diagram is drawn, visualizing the deflection of a thin board, flexible ruler, or similar device. It is drawn grossly exaggerated to be visible. The shear diagram is drawn at a convenient force scale left to right, starting with zero shear to the left of the beam. Downward uniform load yields downward sloping shear. Downward point loads are drawn as downward offset, and upward reactions yield upward offset. Bending diagrams are drawn, considering the area method; namely, bending at any point is equal to the area of the shear diagram up to that point. Both, shear and bending must be zero to the right of the right beam end. To satisfy this, requires a certain amount of forward thinking and, in complex cases, even working backward from right to left as well as left to right.

- 1 Cantilever beam with point load
- 2 Cantilever beam with uniform load
- 3 Cantilever beam with mixed load
- 4 Simple beam with point loads
- 5 Simple beam with uniform load
- 6 Simple beam with mixed load
- 7 Beam with one overhang and point load
- 8 Beam with one overhang and uniform load
- 9 Beam with one overhang and mixed load
- 10 Beam with two overhangs and point loads
- 11 Beam with two overhangs and uniform load
- 12 Beam with two overhangs and mixed load

9

Lateral Force Design

Lateral loads, acting primarily horizontally, include:

- Wind load
- Seismic load
- Earth pressure on retaining walls (not included in this book)

Wind and earthquakes are the most devastating forces of nature:


Hurricane Andrew 1992, with gusts of 170 mph, devastated 300 square miles, left 300,000 homeless, caused about \$ 25 billion damage, and damaged 100,000 homes

The 1976 Tangshan Earthquake (magnitude 7.8), obliterating the city in northeast China and killing over 240,000 people, was the most devastating earthquake of the 20th century.

Swiss Re reported 2003 world wide losses:

- 60,000 people killed
- Over two thirds earthquake victims
- \$70 billion economic losses

IBC table 1604.5. Importance Classification excerpt					
Category	Seismic Use Group	Nature of Occupancy	Seismic importance factor	Snow importance factor	Wind importance factor
I	I	Low hazard structures: Agriculture, temporary, minor storage	1	0.8	0.87
II	I	Structures not in categories I, III, IV	1	1	1
III	II	Structures such as: Occupancy >300 people per area Elementary schools >250 students Colleges >500 students Occupancy >5000	1.25	1.1	1.15
IV	III	Essential facilities, such as: Hospitals, polices and fire stations	1.5	1.2	1.15



IBC Fig. 1609. Basic wind speed (3-second gust)

Map values are nominal design 3-second gust wind speeds in mph (m/s) at 33 ft (10 m) above ground for Exposure C. Mountains, gorges, ocean promontories, and special wind regions shall be examined for special wind conditions.



Steady winds are static



Gusty winds are dynamic


Design for Wind

Wind forces are very complex, effected by building form, height, flexibility and openness, as well as topography, environment, wind velocity and direction. Tornadoes are the most destructive. United States tornadoes occur between Rocky mountains and Appalachian mountains with speeds over 200 mph. However, the probability of any building to be hit is remote. Hurricanes along the Atlantic coast range from 90 to 150 mph. Typhoons, similar to hurricanes, occur in the Pacific, Indian Ocean, Arabian Sea, and Australia.


Wind speed increases with height. Wind load is defined by speed, both constant velocity and dynamic gusts. As air moves along the earth it is slowed near the ground due to friction, which also makes wind more erratic. Wind speed is less in cities but gusts are greater. When wind encounters a building it flows around and over it, causing pressure on the windward side, negative suction on the leeward side and side walls, and pressure or suction on the roof. Flat roofs and leeward slopes are subject to suction, as well as shallow windward slopes, but steep windward roofs have pressure. Wind flow is effected by form; square plans have greater pressure than round ones. Forms like aircraft wings streamline air flow with least resistance. Buildings drift in wind and vibrate in gusts. Wind pressure on edges, ridges and eaves is greater than the mean surface pressure. This is important for cladding and curtain walls.

Wind design methods assume pressure increases with height. However, wind tunnel tests show maximum wind pressure at about 2/3 the building height, reducing toward the top due to air flow over the roof. Regular buildings are designed for wind in two orthogonal directions. Unusual forms may require to investigate other directions, such as 45 degrees. Unusual forms may also require wind tunnel tests. For example wind tunnel tests for the unique Toronto City Hall showed wind load greater than required by code. Structures sensitive to dynamic behavior may also require wind tunnel tests. Wind resistance is effected by type of construction. Buildings of heavy material resist wind better than light buildings. Skeleton buildings with light curtain walls are more vulnerable to wind load than old bearing wall buildings. Flexible structures may sway and vibrate under wind gusts.


Lateral drift is an important issue in tall buildings to assure human comfort and prevent damage or failure of curtain walls, partitions, and other architectural items. IBC tables 1604.3 and 1617.3.1 limit allowable deflection and drift. However, less than code drift may be desirable to prevent damage or failure of curtain walls, partitions and other items and assure occupant comfort. Story drift of $h/400$ implies about 0.4 inch drift; greater drift could dislodge glass panels. Total drift of $h/400$ in a 60-story building implies about 2 foot drift each way on top; more drift might cause discomfort for occupants. Given the complexity of computing drift, it is best analyzed by computer.




1




2




3



4



5



6

Wind load

- 1 Wind load on gabled building
- 2 Wind load on dome or vault
- 3 Protected buildings inside a city
- 4 Exposed tall building inside a city
- 5 Wind flow around and above exposed building
- 6 Wind speed amplified by building configuration

Wind channeled between buildings causes a *Venturi* effect of increased wind speed. Air movement through buildings causes internal pressure that effects curtain walls and cladding design. Internal pressure has a balloon-like effect, acting outward if the wind enters primarily on the windward side. Openings on leeward or side walls cause inward pressure. In tall buildings with fixed curtain wall the difference between outside wind pressure and interior pressure causes air movement from high pressure to low pressure. This causes air infiltration on the windward side and outflow on the leeward side. In high-rise buildings, warm air moving from lower to upper levels causes pressures at top levels on the leeward face and negative suction on lower levels. Wind pressure is based on the equation developed by Daniel Bernoulli (1700-1782). For steady air flow of velocity V , the velocity pressure, q , on a rigid body is

$$q = \rho V^2 / 2$$

ρ = air density (air weight divided by the acceleration of gravity $g = 32.2 \text{ ft/sec}^2$)

Air of 15°C at sea level weighs 0.0765 lb/ft^3 , which yields:

$$q = 0.00256V^2 \quad (q \text{ in psf})$$

The American National Standards Institute (ANSI) *Minimum design loads for buildings and other structures* (ANSI A58.1 - 1982), converted dynamic pressure to velocity pressure q_z (psf) at height z as

$$q_z = 0.00256 K_z (I V)^2$$

$$K_z = 2.58(z/z_g)^{2/a} \quad (\text{for buildings of 15 ft or higher})$$

a = Power coefficient (see exposures A – D below)


Z = Height above ground

Z_g = Height at which ground friction no longer effects the wind speed (see exposures A - D below)

I = Importance factor (see IBC table 1604.5)

ANSI A58.1 defined exposures A, B, C, D (IBC uses B, C, D only):

Exposure A	Large city centers	$a = 3.0, Z_g = 1500 \text{ ft}$
Exposure B	Urban and suburban areas, wooded areas	$a = 4.5, Z_g = 1200 \text{ ft}$
Exposure C	Flat, open country with minimal obstructions	$a = 7.0, Z_g = 900 \text{ ft}$
Exposure D	Flat, unobstructed coastal areas	$a = 10.0, Z_g = 700 \text{ ft}$



Wind effect

A building in the path of wind causes wind pressure which in turn causes force, shear, and overturn moment at each level that must be resisted, following a load path to the foundations (wind wall pressure transfers to horizontal diaphragms, then to shear walls, finally to foundation). Wind pressure times tributary area per level causes lateral force per level. Shear per level, the sum of wind forces above, defines required resistance. Overturn moment per level is the sum of forces above times their height above the respective level.

- 1 Wind force, shear, and overturn moment per level
 F_x = wind force = wind pressure times tributary area per level exposed to wind
 V_x = shear per level = sum of F_x above
 M_x = overturn moment = sum of all forces above times their distance above level x .

- 2 Overturn effect

- 3 Windward pressure increase with height

- 4 Wind force
 F_x = (windward pressure + leeward suction) times tributary area per level
 (leeward wind suction is assumed constant for full height)
 $F_x = P A$
 P = wind pressure and suction in psf (Pa)
 A = tributary area exposed to wind
 (tributary area = building width times half the story height above and below)




- 5 Shear
 Wind shear per level = sum of all wind forces above
 Wind shear is the integration of wind forces above




$$V_x = \sum_{i=x}^n F_i$$

- 6 Overturn moment
 Overturn moment per level = sum of all forces above times their distance
 Overturn moment per level = integration of shear diagram above respective level

$$M_x = \sum_{i=x}^n F_i (h_i - h_x)$$

F_i = Force at level i
 h_i = height of level i
 h_x = height of level x
 n = top level





Wind pressure

ASCE 7 provides three methods to define wind pressure:

Method 1 – Simplified Design (limited to mean roof height $h \leq 60$ ft [18 m])

Method 2 – Analytical Procedure (briefly described below)

Method 3 – Wind-tunnel Procedure

The Analytical Procedure includes figures and tables for wind speed, exposure, building form, roof slope, enclosure, dynamic behavior and topography.

$p = qG C_p - q_i(GC_{pi})$ (ASCE 7 6.5.12.2.1, minimum $p = 10$ psf [480 Pa])

q velocity pressure (defined below)

G gust factor (ASCE 7, 6.5.8)

$G = 0.85$ (for rigid structures > 1 Hz, usually < 10 stories)

$G = 1.5$ to 2.0 (for fabric structures, depending on form, etc)

C_p Pressure coefficient (ASCE 7 figures and tables)

$C_p = 0.8$ (windward walls, varies with height z)

$C_p = -0.7$ (side walls - constant - based on height h)

$C_p = -0.2$ to -0.5 (leeward walls - constant - based on height h)

$C_p = -1.3$ to $+0.4$ (windward and flat roofs)

$C_p = -0.3$ to -0.7 (leeward roof)

GC_{pi} Internal pressure factor (ASCE 7 Fig. 6-5, based on highest opening)

$GC_{pi} = 0$ (open structures)

$GC_{pi} = \pm 0.18$ (enclosed buildings)

$q = 0.00256 I K_z K_{zt} K_d V^2$ (Velocity pressure in psf)

$q = 0.613 I K_z K_{zt} K_d V^2$ (SI units: velocity pressure in Pa)

V = wind speed in mph [m/s] (IBC Fig. 1609 wind speed map or local data)

I = Importance factor (IBC table 1604.5)

$I = 1$ (all structures not listed below)

$I = 1.15$ (essential facilities: hospitals, police and fire stations)

$I = 1.15$ (facilities presenting hazards to human life)

$I = 0.87$ (agricultural and some temporary facilities)

K_{zt} Topography factor (ASCE 7 Fig. 6.4)

$K_{zt} = 1$ (for regular flat sites, assumed in graphs)

K_d Directionality factor (ASCE 7 Table 6-4)

$k_d = 0.85$ (for building structures)

K_z Exposure factor (ASCE 7 Table 6-3)

K_z graph (left): (Exposure B cladding minimum $K_z = 0.7$)

B = Exposure B, inner city, protected by other buildings or trees

C = Exposure C, open area, unprotected buildings

D = Exposure D, near ocean or large lakes


Note: The following graphs assume:

Regular flat sites ($K_{zt} = 1$)

Interior, leeward, and side wall pressure, constant, based on height h

Positive values for pressure, negative values for suction

Exposure C wind pressure for 10' to 100' height and 85 to 150 mph wind speed




Windward pressure (psf)

85	5.7	6.0	6.5	6.9	7.3	7.6	7.8	8.1	8.3	8.4
90	6.4	6.7	7.3	7.8	8.2	8.5	8.8	9.1	9.3	9.4
100	7.9	8.3	9.1	9.6	10.1	10.5	10.8	11.2	11.5	11.7
110	9.5	10.1	11.0	11.6	12.2	12.6	13.1	13.5	13.9	14.1
120	11.3	12.0	13.1	13.8	14.5	15.0	15.6	16.1	16.5	16.8
130	13.3	14.1	15.3	16.3	17.0	17.7	18.3	18.9	19.4	19.7
140	15.4	16.3	17.8	18.9	19.8	20.5	21.2	21.9	22.5	22.8
150	17.7	18.7	20.4	21.6	22.7	23.5	24.3	25.2	25.8	26.2

Leeward pressure (psf)

85	2.4	2.5	2.8	2.9	3.1	3.2	3.3	3.4	3.5	3.6
90	2.7	2.9	3.1	3.3	3.5	3.6	3.7	3.8	3.9	4.0
100	3.3	3.5	3.8	4.1	4.3	4.4	4.6	4.7	4.9	4.9
110	4.0	4.3	4.6	4.9	5.2	5.4	5.5	5.7	5.9	6.0
120	4.8	5.1	5.5	5.9	6.1	6.4	6.6	6.8	7.0	7.1
130	5.6	6.0	6.5	6.9	7.2	7.5	7.7	8.0	8.2	8.3
140	6.5	6.9	7.5	8.0	8.4	8.7	9.0	9.3	9.5	9.7
150	7.5	7.9	8.6	9.2	9.6	10.0	10.3	10.7	10.9	11.1

Interior pressure (psf)



Example: Wood shear walls

Assume: 66'x120'x27' high, 3 shear walls, $L=3 \times 30'=90'$, wind speed 90 mph, exposure C, Importance factor $I = 1$, gust factor $G = 0.85$ (ASCE 7, 6.5.8 for rigid structures > 1 Hz)

For each level in width direction find: wind pressure P , force F , shear V , shear wall type
Interior pressure (from graph for $h = 30'$) $p = 3.1$ psf

Leeward suction (from graph for $h = 30'$) $P = 7.3$ psf

Level 3 ($h = 29'$ – use 30' pressure)

Wind pressure (windward + leeward + interior)

$$p = 11.7 + 7.3 + 3.1 \quad p = 22.1 \text{ psf}$$

$$\text{Force } F = 22.1 \times 120 \times 10' / 2 \quad F = 13,260 \text{ \#}$$

$$\text{Shear } V = F \quad V = 13,260 \text{ \#}$$

$$\text{Required wall strength} = 13,260 / 90' = 147 \text{ plf; use } 5/16", 6d \text{ at } 6" \quad 200 > 147$$

Level 2 ($h = 19'$ – use 20' pressure)

$$p = 10.8 + 7.3 + 3.1 \quad p = 21.2 \text{ psf}$$

$$\text{Force } F = 21.2 \times 120 \times 10' \quad F = 25,440 \text{ \#}$$

$$\text{Shear } V = 13,260 + 25,440 \quad V = 38,700 \text{ \#}$$

$$\text{Required wall strength} = 38,700 / 90' = 430 \text{ plf; use } 15/32", 8d \text{ at } 4" \quad 430 = 430$$

Level 1 ($h = 9'$ – use 10' pressure)

$$p = 10.2 + 7.3 + 3.1 \quad p = 20.6 \text{ psf}$$

$$\text{Force } F = 23.7 \times 120 \times 10' \quad F = 24,720 \text{ \#}$$

$$\text{Shear } V = 38,700 + 24,720 \quad V = 63,420 \text{ \#}$$

$$\text{Required strength} = 63,420 / 90' = 705 \text{ plf; use } 15/32", 8d \text{ at } 2" \quad 730 > 705$$

Note:

The results are very similar to 9.1 with less computation

See Appendix C for exposure B and D graphs


IBC table 2306.4.1 excerpts

Allowable shear for wood panels with Douglas-Fir-Large or Southern Pine

Panel grade	Panel thickness	Nail penetration	Nail size	Nail spacing at panel edge (inches)			
				6	4	3	2
				Allowable shear (lbs / foot)			
Structural I sheathing	5/16 in	1 1/4 in	6d	200	300	390	510
	3/8 in	1 3/8 in	8d	230	360	460	610
	7/16 in	1 3/8 in	8d	255	395	505	670
	15/32 in	1 3/8 in	8d	280	430	550	730
		1 1/2 in	10d	340	510	665	870

* Requires 3 x framing and staggered nailing

Exposure D wind pressure for 10' to 100' height and 85 to 150 mph wind speed




Windward pressure (psf)

85	6.9	7.2	7.8	8.2	8.5	8.8	9.0	9.2	9.4	9.6
90	7.7	8.1	8.7	9.1	9.5	9.8	10.0	10.3	10.5	10.7
100	9.5	10.0	10.7	11.3	11.7	12.1	12.4	12.8	12.9	13.2
110	11.5	12.1	13.0	13.7	14.2	14.7	15.0	15.4	15.7	16.0
120	13.7	14.4	15.4	16.2	16.9	17.4	17.8	18.4	18.6	19.0
130	16.1	16.9	18.1	19.1	19.8	20.5	20.9	21.6	21.9	22.3
140	18.7	19.6	21.0	22.1	23.0	23.7	24.3	25.0	25.4	25.9
150	21.4	22.5	24.1	25.4	26.4	27.3	27.9	28.7	29.1	29.8

Leeward pressure (psf)

85	2.9	3.1	3.3	3.5	3.6	3.7	3.8	3.9	4.0	4.0
90	3.3	3.4	3.7	3.9	4.0	4.2	4.3	4.4	4.4	4.5
100	4.0	4.2	4.5	4.8	5.0	5.1	5.2	5.4	5.5	5.6
110	4.9	5.1	5.5	5.8	6.0	6.2	6.4	6.5	6.6	6.8
120	5.8	6.1	6.5	6.9	7.2	7.4	7.6	7.8	7.9	8.1
130	6.8	7.1	7.7	8.1	8.4	8.7	8.9	9.1	9.3	9.5
140	7.9	8.3	8.9	9.4	9.7	10.1	10.3	10.6	10.7	11.0
150	9.1	9.5	10.2	10.8	11.2	11.5	11.8	12.2	12.3	12.6

Interior pressure (psf)



Example: CMU shear walls

Assume: Regular flat site

Office building: 6-story, 90'x90'x60', 30'x30' core

30' CMU walls, 8" nominal (7.625")

Shear wall length $L = 2 \times (30' - 6' \text{ doors}) = 48'$

Shear walls resist all lateral load

Roof fabric canopy, 50'x50'x10', gust factor $G = 1.8$

Wind speed $V = 100 \text{ mph}$

Exposure D

Importance factor $I = 1$

Interior pressure (assume conservative opening height $h = 60'$)

$p = 5.1 \text{ psf}$

Leeward pressure (for $h = 60'$)

$p = 17.2 \text{ psf}$

$P = 12.1 \text{ psf} + 5.1 \text{ psf}$

Average windward pressure ($h = 10 \text{ to } 60'$)

$p = 17.5 \text{ psf}$

$P = (15.2 + 16.0 + 17.2 + 18.1 + 18.8 + 19.4) / 6$

Average combined wind pressure

$P = 39.8 \text{ psf}$

$P = 17.5 + 17.2 + 5.1$

Roof canopy pressure $P_{\text{canopy}} = (12.1)(1.8)$

$P_{\text{canopy}} = 21.8 \text{ psf}$

Base shear

$V = A P = 90' \times (60' - 5') \times 39.8 + (50' \times 10' / 2) \times 21.8$

$V = 202,460 \text{ \#}$


Core shear stress

$v = V / A = 202,460 / (48' \times 12' \times 7.625'')$

$v = 46 \text{ psi}$

Note:

Wind on lower half of first floor, resisted by footing, has no effect on shear walls



Seismic Design

Earthquakes are caused primarily by release of shear stress in seismic faults, such as the *San Andreas* fault, that separates the Pacific plate from the North American plate, two of the plates that make up the earth's crust according to the plate tectonics theory. Plates move with respect to each other at rates of about 2-5 cm per year, building up stress in the process. When stress exceeds the soil's shear capacity, the plates slip and cause earthquakes. The point of slippage is called the *hypocenter* or *focus*, the point on the surface above is called the *epicenter*. Ground waves propagate in radial pattern from the focus. The radial waves cause shaking somewhat more vertical above the focus and more horizontal far away; yet irregular rock formations may deflect the ground waves in random patterns. The Northridge earthquake of January 17, 1994 caused unusually strong vertical acceleration because it occurred under the city.



Occasionally earthquakes may occur within plates rather than at the edges. This was the case with a series of strong earthquakes in New Madrid, along the Mississippi River in Missouri in 1811-1812. Earthquakes are also caused by volcanic eruptions, underground explosions, or similar man-made events

Buildings are shaken by ground waves, but their inertia tends to resist the movement which causes lateral forces. The building mass (dead weight) and acceleration effects these forces. In response, structure height and stiffness, as well as soil type effect the response of buildings to the acceleration. For example, seismic forces for concrete shear walls (which are very stiff) are considered twice that of more flexible moment frames. As an analogy, the resilience of grass blades will prevent them from breaking in an earthquake; but when frozen in winter they would break because of increased stiffness.

The cyclical nature of earthquakes causes dynamic forces that are best determined by dynamic analysis. However, given the complexity of dynamic analysis, many buildings of regular shape and height limits, as defined by codes, may be analyzed by a *static force* method, adapted from Newton's law $F = ma$ (Force = mass x acceleration).

- 1 Seismic wave propagation and fault rupture
- 2 Lateral slip fault
- 3 Thrust fault
- 4 Building overturn
- 5 Building shear
- 6 Bending of building (first mode)
- 7 Bending of building (higher mode)

E Epicenter
H Hypocenter



Richter scale method, courtesy US Geological Survey

Seismic terms

The following seismic terms are important to understanding seismic design:

Period is the time interval of one cycle a wave or a building sways back and forth. A building period resonant with the earthquake period can cause collapse.

Amplitude is the displacement of a wave perpendicular to the direction it moves

Richter scale

The Richter scale was developed in 1935 by Charles Richter of the California Institute of Technology to compare the magnitude of earthquakes. The Richter scale is determined from the logarithm of the amplitude of waves recorded by seismographs; adjusted for the distance to the earthquake epicenter. The Richter Scale gives magnitude in whole numbers and decimal fractions. For example, magnitude 5 is a moderate earthquake, but magnitude 7 is a strong one. Because of the logarithmic scale, each whole number increase represents a **tenfold increase in amplitude and force and 31 times more energy**.

Velocity is the shaking speed of an earthquake (meter/ second)

Acceleration is velocity increase (or decrease), like car acceleration (meter / second²) **Spectral acceleration** is what is experienced by a building, modeled by a particle on a mass-less vertical rod of the same period as the building

PGA (peak ground acceleration) is experienced by a particle on the ground (without damping)

Body waves

Body waves are seismic waves that move through the interior of the earth, as opposed to surface waves that travel near the earth's surface. P and S waves are body waves. Each type of wave shakes the ground in different ways.

P waves are high-speed seismic body waves, traveling at about 26000 mph (42000 km), that shake the ground in the same and opposite direction as the waves move.




S waves (shear waves) are seismic body waves that shake back and forth perpendicular to the direction the wave is moving.

Surface waves

Surface waves are seismic waves that are trapped near the surface of the earth

Rayleigh waves are seismic surface waves causing the ground to shake in an elliptical motion, with no transverse, or perpendicular, motion.

Love waves are surface waves with a horizontal motion transverse (perpendicular) to the direction the wave is traveling.



SD Graphs (Seismic Design Graphs)

by G G Schierle

adapted from IBC *Equivalent Lateral Force Analysis*
Load Resistance Factor Design (LRFD)

to

Allowable Stress Design (ASD)

assuming $ASD = LRFD / 1.4$

C_s Graph for light framing with wood panels (R=6, I=)

Used to compute base shear V

$$V = I C_s W$$

I = Importance factor (see IBC table 1604.5)

C_s = Seismic coefficient

W = Building mass (dead load + some live loads)

S_{DS} Graph: 0.2 seconds Design Spectral Acceleration

Used for low-rise structures

$$C_s = I S_{DS} / R$$


R = Reduction factor for structure systems (see IBC table 1617.6.2)

S_{D1} Graph for 1 second Design Spectral Acceleration


Used for high-rise structures ($T > T_s$) ($T_s = S_{DS}/S_{D1}$)

$$C_s = I S_{D1} / (TR)$$


T = building period (approximately 0.1 seconds per story height)



Spectral acceleration



Acceleration spectra for four soil types (by Seed)



IBC Design Response Spectrum

Basic concepts

Earthquake ground shaking generates forces on structures. Though these forces act in all direction, the horizontal (lateral) forces are usually most critical. Seismic forces are $f = m a$ (Force = mass x acceleration)

where

Mass = building dead weight

Acceleration

Note:

PGA (Peak ground Acceleration) is experienced by a particle on the ground
Spectral Acceleration approximates the acceleration of a building, as modeled by a particle on a mass-less vertical rod of the same period of vibration as the building.

Acceleration Spectra (left)

Based on the 1971 San Fernando and other Earthquakes Seed (1976) developed Acceleration Spectra to correlate time period (X-axis) with acceleration for four soil types. Other studies by Hall, Hayashi, Kuribayashi, and Mohraz demonstrated similar results.

Equivalent Lateral Force Analysis is based on Acceleration Spectra, abstracted as *Design Response Spectrum*

Design Response Spectrum (left)

The IBC Design Response Spectrum correlate time period T and Spectral Acceleration, defining three zones. Two critical zones are:



$T < T_s$ governs low-rise structures of short periods

$T > T_s$ governs tall structures of long periods


where

T = time period of structure ($T \sim 0.1$ sec. per story - or per ASCE 7 table 1615.1.1)

$T_s = S_{DS}/S_{D1}$ (See the following graphs for S_{DS} and S_{D1})



Cs factors for light framing with wood panels (R=6, I=1)



Cs for site class A-E for 0.2 sec mapped spectral accelerations Ss (top line)

Analysis steps

Define site class by geologist, or assume default site class D (IBC table 1615.1.1)

Define Mapped Spectral Accelerations S_s and S_1

For overview see USGS maps at left: 0.2 sec low-rise (top) 1 sec high-rise (bottom)

Enter Site coordinates at USGS web site:

<http://eqdesign.cr.usgs.gov/html/lookup-2002-interp-D6.html>

Enter Latitude: 37.7795	Enter Longitude: -122.4195
Enter Latitude:	Enter Longitude:

Enter latitude in the left box in *decimal degrees* (range: 24.6 to 50.0)

Enter negative longitude in the right box (range: -125.0 to -65.0)

Web output:

LOCATION 37.7795 Lat. -122.4195 Long.

Interpolated Probabilistic Ground Motion(Spectral Acceleration SA) in %g, at the site are:

10%PE in 50 yr. 2%PE in 50 yr.

0.2 sec SA 115.35 182.76 % → $S_s = 1.83$ (for low-rise)

1.0 sec SA 53.08 92.41 % → $S_1 = 0.92$ (for high-rise)

Low-rise: $T < T_s$ (structures < 5 stories)

High-rise: $T > T_s$ (structures > 10 stories)

$T_s = S_{DS}/S_{D1}$ (For S_{DS} and S_{D1} see graphs on following pages)

Define base shear V (lateral force at base of structure)

$V = C_s W$

W = Dead load (+ 25% storage live load + 20% flat roof snow load > 30 psf)

C_s = seismic coefficient - see sample graph at left (S_s at top line)

For other structures:

$C_s = I S_{DS} / R$ (for $T < T_s$)

Need not exceed

$C_s = I S_{D1} / (TR)$ (for $T > T_s$)

I = Importance factor (IBC table 1604.5)

R = R-factor (IBC table 1617.6.2)

S_{DS} and S_{D1} (See graphs on the following pages)

C_s varies with spectral acceleration S_s & S_1 and type of structure

(defined on the following pages)

For example, in seismic areas:

$C_s \sim 3\%$ for tall steel frame structures

$C_s \sim 15\%$ for low-rise wood structures

$C_s \sim 30\%$ for some low-rise masonry structures

$W = w A$ (w = dead load, DL in psf, A = total gross floor area of building)

w varies with type of construction – for example:

$w \sim 15$ to 25 psf for wood structures

$w \sim 70$ to 100 psf for steel structures

$w \sim 150$ to 200 psf for concrete structures

IBC table 1615.1.1 Site class definitions excerpts		
Site class	Soil profile name	Average shear velocity in top 100 ft (30 m)
A	Hard rock	$V_s > 5000$ ft/s (1500 m/s)
B	Rock	$V_s = 2500$ to 5000 ft/s (760 to 1500 m/s)
C	Very dense soil & soft rock	$V_s = 1200$ to 2500 ft/s (370 to 760 m/s)
D	Stiff soil	$V_s = 600$ to 1200 ft/s (180 to 370 m/s)
E	Soft soil	$V_s < 600$ ft/s (180 m/s)
F	Soil vulnerable to failure, very organic clay, high plasticity clay, etc.	

IBC table 1617.6.2 excerpt	R-factor	Height limits (ft), categories A-F					
Bearing wall systems		A	B	C	D	E	F
Light framed walls with wood panels	6	NL	NL	65	65	65	
Light framed walls with other panels	2	NL	NL	35	NP	NP	
Ordinary reinforced concrete walls	4	NL	NL	NP	NP	NP	
Special reinforced concrete walls	5	NL	NL	160	160	100	
Ordinary reinforced masonry walls	2	NL	160	NP	NP	NP	
Special reinforced masonry walls	5	NL	NL	160	160	100	
Building frame systems							
Ordinary steel concentric braced frames	5	NL	NL	35	35	NP	
Special steel concentric braced frames	6	NL	NL	160	160	100	
Ordinary steel moment frames	3.5	NL	NL	NP	NP	NP	
Special steel moment frames	8	NL	NL	NL	NL	NL	

Example: One-story residence, San Francisco

Assume: Light framing with plywood panels

36'x40'x10' high, DL = 25 psf, site class undefined, use default D, $I = 1$

Enter site coordinates at USGS web site

<http://eqdesign.cr.usgs.gov/html/lookup-2002-interp-D6.html>

Web site output

0.2 sec Spectral Acceleration

$S_s = 1.85$

Design Spectral Accelerations (see graph)

At $S_s = 2.0$ $C_s = 0.16$

Interpolate C_s at $S_s = 1.85$ ($C_s/1.85 = 0.16 / 2.0$)

$C_s = 1.85 \times 0.16 / 2.0$

$C_s = 0.15$

Building dead weight

$W = 25$ psf x 36'x40'

$W = 36,000\#$

Base Shear

$V = C_s W = 0.15 \times 36,000$

$V = 5,400\#$

Example: Same residence in San Francisco on site class A

C_s factor (see graph)

Interpolate C_s at $S_s = 1.85$ ($C_s/1.85 = 0.13 / 2.0$)

$C_s = 0.13 \times 1.85 / 2.0$

$C_s = 0.12$

Base shear $V = C_s W = 0.12 \times 36,000$

$V = 4,320\#$

Example: Same residence in Tucson

Site class D, $S_s = 0.329$

C_s factor (see graph)

Interpolate for $S_s = 0.329$ ($C_s/0.329 = 0.06/0.5$)

$C_s = 0.329 \times 0.06 / 0.5$

$C_s = 0.04$

Base shear $V = C_s W = 0.04 \times 36,000$

$V = 1,440\#$

Example: Same residence in Tucson on site class A

C_s factor (see graph)

Interpolate for $S_s = 0.329$ (at $S_s = 0.5$ $C_s = 0.03$)

$C_s = 0.329 \times 0.03 / 0.5$

$C_s = 0.02$

Base shear $V = C_s W = 0.02 \times 36,000$

$V = 720\#$

Compare seismic factors

Los Angeles site class D

$C_s = 0.15$

Los Angeles site class A


$C_s = 0.12$


Tucson site class D

$C_s = 0.04$


Tucson site class A

$C_s = 0.02$





S_{DS} for site class A-E for 0.2 sec. mapped spectral accelerations S_s (top line)



S_{D1} for site class A-E for 1 sec. mapped spectral accelerations S₁ (top line)

General C_s factors

The previous examples are limited to light framing with wood panels

For other structures the C_s factor must be computed:

For low-rise structures of T < T_s

For high-rise structure of T > T_s

See graphs at left for S_{DS} and S_{D1} (Design Spectral Accelerations)

Example: 7-story special steel moment frame

Assume: Office building, 90'x180'x84' high, DL=70 psf

Site class D, I = 1, R = 8, S_s = 1.81, S₁ = 1.00

Time period (see ASCE 7 table 1615.1.1)

T = C_T h^{0.8} = 0.028 x 84^{0.8}

Design Spectral Accelerations (see graphs at left)

At S_s = 1.81 Interpolate S_{DS} = 1.81 x 0.95 / 2

At S₁ = 1.00

Design response spectrum limit

T_s = S_{DS}/S_{D1} = 0.86/0.71

T < T_s

C_s = I S_{DS} / R = 1 x 0.86 / 8

Structure dead load

W = 7 x 70 psf x 90' x 180' / 1000

Base shear

V = C_s W = 0.11 x 7,938

$$C_s = S_{DS} / R$$

$$C_s = I S_{D1} / (TR)$$

$$T = 0.97 \text{ sec}$$

$$S_{DS} = 0.86$$

$$S_{D1} = 0.71$$

$$T_s = 1.21$$

$$0.97 < 1.21$$

$$C_s = 0.11$$

$$W = 7,938 \text{ k}$$

$$V = 873 \text{ k}$$

Example: 20-story special (ductile) steel moment frame

Assume: Office building, 90'x180'x250' high, DL=70 psf

Same site and seismic factors as above but I = 1.25 (Occupancy > 300), R = 8

Time period

T = C_T h^{0.8} = 0.028 x 84^{0.8}

Design Spectral Accelerations (see graphs at left)

At S_s = 1.81 Interpolate S_{DS} = 1.81 x 0.95 / 2

At S₁ = 1.00

Design response spectrum limit

T_s = S_{DS}/S_{D1} = 0.86/0.71

T > T_s

C_s = I S_{D1} / (TR) = 1.25 x 0.71 / (2.32 x 8)

Structure dead load

W = 20 x 70 psf x 90' x 180' / 1000

Base shear

V = C_s W = 0.048 x 22,680

$$T = 2.32 \text{ sec}$$

$$S_{DS} = 0.86$$

$$S_{D1} = 0.71$$

$$T_s = 1.21$$

$$2.32 > 1.21$$

$$C_s = 0.048$$

$$W = 22,680 \text{ k}$$

$$V = 1,089 \text{ k}$$

Example: 20-story ordinary (non-ductile) steel moment frame






C_s = I S_{D1} / (TR) = 1.25 x 0.71 / (2.32 x 3.5), R = 3.5

Base shear

V = C_s W = 0.109 x 22,680

$$C_s = 0.109$$

$$V = 2,472 \text{ k}$$



Vertical distribution

Seismic forces increase with building height since $f = ma$ (force = mass $\times$ acceleration), i.e., increased drift increases acceleration. Thus story forces F_x are story mass times height above ground. For buildings with periods of 0.5 seconds or less the force increase is considered linear. For tall buildings the story-force varies non-linear. Since all story forces are resisted at the ground, each story must resist its own force plus all forces from above. Thus shear per level increases from top to bottom. The overturn moment per level is the sum of all forces above times their distance to the level considered.

1 Linear force increase for $T \leq 0.5$ seconds

2 Non-linear force increase for $T > 0.5$

3 Distribution per level of force

F_x = force per level x

V_x = Shear per level x = sum all forces above

$V_2 = 3 \text{ k}$

$V_1 = 3 \text{ k} + 2 \text{ k}$

$V_0 = 5 \text{ k} + 1 \text{ k}$

M_x = overturn moment per level = sum of all forces above times level arm

Assuming 10' story height:

$M_2 = 3 \text{ k} \times 10'$

$M_1 = 3 \text{ k} \times 20' + 2 \text{ k} \times 10'$

$M_0 = 3 \text{ k} \times 30' + 2 \text{ k} \times 20' + 1 \text{ k} \times 10'$

4 Overturn moment visualized

5 Force per level

$F_x = C_{vx} V$

$C_{vx} = w_x h_x / \sum_{i=1}^n w_i h_i^k$ (vertical distribution factor)

W = total dead weight of level x

h = height of level x above ground

n = total number of stories

k = exponent related to structure period

$k = 1$ for $T \leq 0.5$ seconds

$k = 2$ for $T > 2.5$ seconds

k = interpolated between $T = 0.5$ and 2.5

6 k Interpolation graph

7 Shear per level

$$V_x = \sum_{i=x}^n F_i$$

8 Overturn moment per level

$$M_x = \sum_{i=x}^n F_i (h_n - h_i)$$

$V_2 = 3 \text{ k}$


$V_1 = 5 \text{ k}$

$V_0 = 6 \text{ k}$


$M_2 = 30 \text{ k'}$

$M_1 = 80 \text{ k'}$


$M_0 = 140 \text{ k'}$



1



2



Horizontal diaphragms

Horizontal floor and roof diaphragms transfer lateral load to walls and other supporting elements. The amount each wall assumes depends if diaphragms are **flexible** or **rigid**.

1 Flexible diaphragm

Floors and roofs with plywood sheathing are usually flexible; they transfer load, similar to simple beams, in proportion to the tributary area of each wall

Wall reactions R are computed based on tributary area of each wall

Required shear flow q (wall capacity)

$q = R / L$ (L = length of shear wall)

$R = w$ (tributary width)

$q = R / L$ (L = shear wall length)

$R1 = (150)16/2 = 1200$ lbs

$q = 1200 / 8'$

$q = 150$ plf

$R2 = (150)(16+14)/2 = 2250$ lbs

$q = 2250 / 12'$

$q = 188$ plf

$R3 = (150)14/2 = 1050$ lbs

$q = 1050 / 8'$

$q = 131$ plf

2 Rigid diaphragm

Concrete slabs and some steel decks are rigid; they transfer load in proportion to the relative stiffness of each wall. Since rigid diaphragms experience only minor deflections under load they impose equal drift on walls of equal length and stiffness.

For unequal walls reactions are proportional to a resistance factor r.

$r = EI / h^3 / \sum (EI / h^3)$

h = wall height

$I = bL^3 / 12$

(moment of inertia of wall)

b = wall thickness

L = wall length

For walls of equal height, thickness and material, the resistance factors are:

$r = L^3 / \sum L^3$

$L1^3 = 16^3 = 4096$

$L2^3 = 12^3 = 1728$

$\sum L^3 = 4096 + 1728 + 512$

$\sum L^3 = 2752$

$r1 = 4096 / 2752$

$r1 = 0.186$

$r2 = 1728 / 2752$

$r2 = 0.628$

$r3 = 512 / 2752$

$r3 = 0.186$

Check $\sum r$

$\sum r = 1.000$

Total force F

$F = 1000 \text{ plf} \times (16' + 14') / 1000$

$F = 30 \text{ k}$

Wall reactions

$R1 = r1 F = 0.186 \times 30 \text{ k}$

$R1 = 5.58 \text{ k}$

$R2 = r2 F = 0.628 \times 30 \text{ k}$

$R2 = 18.84 \text{ k}$

$R3 = r3 F = 0.186 \times 30 \text{ k}$


$R3 = 5.58 \text{ k}$

Check $\sum R$


$\sum R = 30.00 \text{ k}$

IBC table 2306.4.1 excerpts Allowable shear for wood panels with Douglas-Fir-Large or Southern Pine							
Panel grade	Panel thickness	Nail penetration	Nail size	Nail spacing at panel edge (inches)			
				6	4	3	2 *
				Allowable shear (lbs / foot)			
Structural I sheathing	5/16 in	1 1/4 in	6d	200	300	390	510
	3/8 in	1 3/8 in	8d	230	360	460	610
	7/16 in	1 3/8 in	8d	255	395	505	670
	15/32 in	1 3/8 in	8d	280	430	550	730
		1 1/2 in	10d	340	510	665	870


* Requires 3 x framing and staggered nailing



1



3



Example: Flexible diaphragm

Assume: plywood diaphragm, plywood shear walls on light wood framing

Dead load

DL = 23 psf

Seismic factor (adjusted for ASD)

$C_s = 0.15$

Dead load per level

$W = 23 \text{ psf} \times 68' \times 150' / 1000$

$W = 235 \text{ k}$

Total DL (3 levels)

$\sum W = 3 \times 245 \text{ k}$

$\sum W = 705 \text{ k}$

Base shear

$V = W C_s = 705 \times 0.15$

$V = 106 \text{ k}$

Force distribution

Level	W_x	h_x	$W_x h_x$	$w_x h_x / \sum w_i h_i$	$F_x = V(w_x h_x / \sum w_i h_i)$	$V_x = \sum F_x$
2	247 k	27'	6669 k'	0.50	53 k	53 k
1	247 k	18'	4446 k'	0.33	35 k	88 k
0	247 k	9'	2223 k'	0.17	18 k	106 k
			$\sum w_i h_i = 13,338 \text{ k}'$			$V = 106 \text{ k}$

Area per level $A = 68 (150)$

$A = 10200 \text{ ft}^2$

Shear per square foot v

$v = V / A$

$v \text{ (psi)}$

$V_0 = 106 \text{ k} = 106000 \text{ lbs}$

$v_0 = 106000 / 10200$

$v_0 = 10.4 \text{ psf}$

$V_1 = 88 \text{ k} = 88000 \text{ lbs}$

$v_1 = 88000 / 10200$

$v_1 = 8.6 \text{ psf}$

$V_2 = 53 \text{ k} = 53000 \text{ lbs}$

$v_2 = 53000 / 10200$

$v_2 = 5.2 \text{ psf}$

Level 0 shear walls

Wall A = 10.4 psf (15')30'/12' = 390 plf

390 plf

use 5/16, 6d @ 3" = 390 plf

390 plf

Wall B = 10.4 psf (19')30'/24' = 247 plf

247 plf

use 7/16, 8d @ 6" = 255 plf

255 plf

Wall C = 10.4 psf (34')15'/30' = 177 plf

177 plf

use 5/16, 6d @ 6" = 200 plf

200 plf

Wall D = 10.4 psf (34')30'/30' = 354 plf

354 plf

use 3/8, 8d @ 4" = 360 plf

360 plf

Level 1 shear walls

Wall A = 8.6 psf (15')30'/12' = 323 plf

323 plf

use 15/32, 10d @ 6" = 340 plf

340 plf

Wall B = 8.6 psf (19')30'/24' = 204 plf

204 plf

use 3/8, 8d @ 6" = 230 plf

230 plf

Wall C = 8.6 psf (34')15'/30' = 146 plf

146 plf

use 5/16, 6d @ 6" = 200 plf

200 plf

Wall D = 8.6 psf (34')30'/30' = 292 plf

292 plf

use 5/16, 6d @ 4" = 300 plf

300 plf

Level 2 shear walls

Wall A = 5.2 psf (15')30'/12' = 195 plf

195 plf

use 5/16, 6d @ 6" = 200 plf

200 plf

Wall B = 5.2 psf (19')30'/24' = 124 plf

124 plf

use 5/16, 6d @ 6" = 200 plf

200 plf

Wall C = 5.2 psf (34')15'/30' = 89 plf

89 plf

use 5/16, 6d @ 6" = 200 plf

200 plf




Wall D = 5.2 psf (34')30'/30' = 177 plf

177 plf

use 5/16, 6d @ 6" = 200 plf

200 plf

Note: To simplify construction, fewer wall types could be selected



Example: Rigid diaphragm

Assume: concrete slab on CMU shear walls

Allowable masonry shear stress

Seismic factor $C_s = 0.17 \times 1.5$

Note: increase C_s by 1.5 per IBC 2106.5.1 for ASD method

Dead Load

Wall lengths $L = 12(30') + 14(12') + 8(24')$

Wall DL = $(720') 8'(7.625''/12'') 120 \text{ pcf} / (68 \times 150)$

Floor/roof (12" slab)

Miscellaneous

$\Sigma \text{ DL}$

DL / level: $W = 200 \text{ psf} \times 68' \times 150' / 1000$

DL for 3 Levels: $W = 3 \times 2040 \text{ k}$

Base shear $V = C_s W = 0.26 \times 6120$

Force distribution

Level	W_x	h_x	$W_x h_x$	$w_x h_x / \Sigma w_i h_i$	$F_x = V(w_x h_x / \Sigma w_i h_i)$	$V_x = \Sigma F_x$
2	2,040 k	27'	55,080 k'	1591×0.50	796 k	796 k
1	2,040 k	18'	36,720 k'	1591×0.33	525 k	1,321 k
0	2,040 k	9'	18,360 k'	1591×0.17	270 k	1,591 k
			$\Sigma w_i h_i = 110,169 \text{ k'}$			$V = 1,591 \text{ k}$

Relative wall stiffness:

$R = L^3 / \Sigma L^3$

Wall B: $r = 12^3 / [12^3 + 24^3]$

Wall C: $r = 24^3 / [12^3 + 24^3]$

Wall cross section areas:

A walls = $12(30')12''(7.625'')$

B walls = $14(12')12''(7.625'')$

C walls = $8(24')12''(7.625'')$

Level 0 ($V_0 = 1591 \text{ k}$)

Wall A = $(1591) 1000 / 32940$

Wall B = $(1591) 1000 (0.11) / 15372$

Wall C = $(1591) 1000 (0.89) / 17568$

Level 1 ($V_1 = 1321 \text{ k}$)

Wall A = $(1321) 1000 / 32940$

Wall B = $(1321) 1000 (0.11) / 15372$

Wall C = $(1321) 1000 (0.89) / 17568$

Level 2 ($V_2 = 796 \text{ k}$)

Wall A = $(796) 1000 / 32940$

Wall B = $(796) 1000 (0.11) / 15372$

Wall C = $(796) 1000 (0.89) / 17568$

$F_v = 85 \text{ psi}$

$C_s = 0.26$

$L = 720'$

$DL = 43 \text{ psf}$

150 psf

7 psf

$\Sigma \text{ DL} = 200 \text{ psf}$

$W = 2,040 \text{ k}$

$W = 6,120 \text{ k}$

$V = 1,591 \text{ k}$

$A = 32940 \text{ in}^2$

$B = 15372 \text{ in}^2$

$C = 17568 \text{ in}^2$

48 psi < 85

11 psi < 85

81 psi < 85

40 psi < 85


10 psi < 85

67 psi < 85


24 psi < 85

6 psi < 85


40 psi < 85




1




2




3



4



5



6

Seismic design issues

Eccentricity

Offset between center of mass and center of resistance causes eccentricity which causes torsion under seismic load. The plans at left identify concentric and eccentric conditions:

- 1 X-direction concentric
Y-direction eccentric
- 2 X-direction eccentric
Y-direction eccentric

- 3 X-direction concentric
Y-direction concentric
- 4 X-direction concentric
Y-direction concentric

- 5 X-direction concentric
Y-direction concentric
- 6 X-direction concentric
Y-direction concentric

Note:

Plan 5 provides greater resistance against torsion than plan 6 due to wider wall spacing
Plan 6 provides greater bending resistance because walls act together as core and thus provide a greater moment of inertia



Hazard Configurations

Irregular configurations, such as H, L, T, and U-shapes, may split at intersections of wings due to differential movement in earthquakes.






Differential periods split wing intersections during Northridge Earthquake




Mitigation:


- Provide seismic joints at low-rise wing intersections
- Reinforce high-rise intersections (to avoid pounding of adjacent wings)



Stability Issues


- 1 Narrow shear walls are vulnerable to overturning
- 2 Architectural mitigation:
Combine adjacent windows to provide wider shear walls
- 3 Structural mitigation:
Attach shear walls to edge beams designed to resist wall overturning in bending
- 4 Slender wall failure
- 5 Soft-story tuck-under parking collapse
- 6 Moment frames to stabilize tuck-under parking







Hillside construction

To avoid expensive earthquake settlement repair



..... adapt building to site rather than adapting site to building





Critical wood-frame items

	Item	Requirements
A	Shear wall anchor bolts	Resist wall slippage
B	Hold-down	Resist shear wall overturning
C	Shear wall nailing	Attach panels to framing
D	Wall-to-wall hold-down	Resist shear wall overturning
E	Framing anchor clips	Transfer shear from floor to floor
F	Beam connection	Resist beam slippage
G	Shear wall width/height ratio	Minimum 1 : 3.5 for stability
	Wood panels	1:3.5 (Los Angeles, 1:2)
	Gypsum board	1:2
H	Joist blocking	Transfers shear at panel edges



Bracing

Eccentric bracing allows to adjust stiffness, providing:

- greater stiffness than moment frame
- less stiffness than braced frame
- Short link beam provides stiffness
- Long link beam provides ductility

Note:


Link beam is the distance between brace support and column

Typical link beam length is about 20 percent of beam length



Visco-elastic bracing provides:

- Stiffness for normal load
- Ductility for big seismic load




Base Isolator

Left: Conventional structure

- Large total and inter-story drift
- Accelerations increase with height
- Potential permanent deformations
- Potential equipment damage

Right: Base isolators:


- Reduce floor accelerations and drift
- Reduce damage to structure and equipment
- Are not good for high-rise structures



Left: Base isolator make-up

- Top and bottom steel plate
- Rubber sheets
- Steel sheets
- Central lead core

Right: Separate building from ground to allow drift



UCLA Kerckhoff Hall base isolator upgrade

Drawings, courtesy Widom Wein Cohen Architects, Santa Monica

10

Conceptual Design

Introduction

Conceptual design usually starts with approximate sizing principle elements of a structure and possible alternatives, followed by thorough analysis during design development. Approximate methods are essential to quickly develop alternate designs. They are also useful to verify final designs and computer analysis. If based on good assumptions, approximate methods can provide results of remarkable accuracy, usually within ten percent of precise results. The following conceptual design examples introduce approximate methods, sometimes referred to as back-of-the-envelope design. They are not meant to replace accurate design but as precursor of accurate design and analysis.

System Selection

Structural design starts with the selection of a system and material; often informed by similar past projects, even if not appropriate. For example, light wood structures are common for residential building where hurricanes cause frequent destruction, though heavy concrete or masonry would resist wind load much better. A rational method is proposed with the objective to select more appropriate systems. However, since design criteria may be conflicting in some cases, selection is both art and science, yet the following criteria make the selection process more objective

- Capacity limit
- Code requirements
- Cost
- Load
- Location
- Resources
- Technology
- Synergy

Capacity limit is based on limits of systems and materials. For example, beams are economical for a given span range. To exceed that range would yield a bad ratio of dead load to live load. A beam's cross section increases with span, resulting in heavier dead load. Eventually, the beam's dead load exceeds its capacity and it would break. Approaching that limit, the beam gets increasingly uneconomical because its dead weight leaves little reserve capacity to carry live load. The span limit can be extended by effective cross section shape. For example, steel beam cross sections are optimized in response to bending and shear stress, to allow greater spans.

Trusses have longer span capacity than beams, due to reduced self weight. They replace the bulk of beams by top and bottom chords to resist global moments, and vertical and diagonal web bars to transfer shear between compression and tension chords. Compared to beams, the greater depth of trusses provides a greater lever arm between compression and tension bars to resist global moments. Similarly, suspension cables use the sag between support and mid-span as moment resisting lever arm. Since cables have higher breaking strength and resist tension only, without buckling, they are optimal for long spans; but the high cost of end fittings makes them expensive solutions for short spans. These examples show, most systems have upper and lower span limits.

Code requirements define structures by type of construction regarding materials and systems; ranging from type I to type V for least and most restrictive, respectively, of the Uniform Building Code (UBC) for example. Each type of construction has requirements for fire resistance, maximum allowable floor area, building height, and occupancy group. Codes also have detailed requirements regarding seismic design; notable structures are categorized by ductility to absorb seismic energy and related height limits. Some code requirements are related to other criteria described in the respective section.

Cost is often an overriding criteria in the selection of structures. In fact, cost is often defined by some of the other selection criteria. However, costs also depend on market conditions and seasonal changes. The availability of material and products, as well as economic conditions and labor strikes may greatly effect the cost of structures. For example, a labor strike in the steel industry may shift the advantage to a concrete structure, or the shortage of lumber, may give a cost advantage to light gauge steel instead of light wood framing. Sometimes, several systems are evaluated, or schematic designs are developed for them, in order to select the most cost effective alternative. Load imposed on a structure is a major factor in selecting a system. For example, roofs in areas without snow must be designed only for a nominal load, yet roof load in mountain areas may be up to 20 times greater than the nominal load. Structures in earthquake prone areas should be lightweight and ductile, since seismic forces are basically governed by Newton's law, *force equals mass times acceleration* ($f=ma$). In contrast, structures subject to wind load should be heavy and stiff to resist wind uplift and minimize drift. Structures in areas of daily temperature variations should be designed for thermal load as well, unless the structure is protected behind a thermal insulation skin and subjected to constant indoor temperature only.

Location may effect structure selection by the type of soil, topography, ground water level, natural hazards, such as fire, frost, or flood. Local soil conditions effect the foundation and possibly the entire structure. Soft soil may require pile foundations; a mat foundation may be chosen to balance the floating effect of high ground water. Locations with winter frost require deep foundations to prevent damage due to soil expansion in frost (usually a depth of about one meter). Hillside locations may require caisson foundations to prevent sliding, but foundations are more common on flat sites. Locations with fire hazards require non-combustible material. Raising the structure off the ground may be the answer to flooding.


Resources have a strong impact on the selection of structure materials. Availability of material was a deciding factor regarding the choice of material throughout history. The Viking build wood structures, a logical response to the vast forests of Scandinavia, yet stone temples of Egypt and Greece reflect the availability of stone and scarcity of wood. More recently, high-rise structures in the United States are usually steel structures, but the scarcity of steel in some other countries makes concrete structures more common.

Technology available at a area also effects the selection of structures. For example, light wood structures, known as platform framing, is most common for low rise residential structures in the United States, where it is widely available and very well known; but in Europe where this technology is less known, it is more expensive than more common masonry structures. Similarly, in some areas concrete technology is more familiar and available than steel technology. Concrete tends to be more common in areas of low labor cost, because concrete form-work is labor intensive. On the other hand, prefabricated concrete technology is less dependent on low labor cost and more effected by market

conditions, namely continuity of demand to justify the high investments associated with prefabricated concrete technology.

Synergy, defined as a system that is greater than the sum of its parts is a powerful concept to enrich architecture, regarding both pragmatic as well as philosophic objectives. Pragmatic examples are numerous: Wall systems are appropriate for hotel and apartment projects which require spatial and sound separation; but moment frames provide better space planning flexibility as needed for office buildings. However, the core of office buildings, usually housing elevators, stairs, bathrooms, and mechanical ducts, without the need for planning flexibility, often consists of shear walls or braced frames, effective to reduce drift under lateral loads. Long-span systems provide column-free space required for unobstructed views in auditoriums and other assembly halls; but lower cost short span systems are used for warehouses and similar facilities where columns are usually acceptable.

On a more detailed level, to incorporate mechanical systems within a long-span roof or floor structure, a *Vierendeel* girder may be selected instead of a truss, since the rectangular panels of a *Vierendeel* better facilitate ducts to pass through than triangular truss panels. A suspended cable roof may be selected for a sports arena if bleachers can be used to effectively resist the roof's lateral thrust which is very substantial and may require costly foundations otherwise. Synergy is also a powerful concept regarding more philosophical objectives, as demonstrated throughout history, from early post and beam structures; Roman arches, domes and vaults; Gothic cathedrals; to contemporary suspension bridges or roofs. Columns can provide architectural expression as in post and beam systems, or define and organize circulation, as in a Gothic cathedral. The funicular surface of arches, domes and vaults can define a unique and spiritual space. The buttresses to resist their lateral thrust provides the unique vocabulary of Gothic cathedrals. Large retaining walls may use buttressing for rhythmic relieve, as in the great wall of Assisi, or lean backward to express increased stability as the wall of the Dalai Lama palace in Tibet.



Global moment and shear

Global moments help to analyze not only a beam but also truss, cable or arch. They all resist global moments by a couple F times lever arm d :

$$M = F d; \text{ hence } F = M / d$$

The force F is expressed as T (tension) and C (compression) for beam or truss, and H (horizontal reaction) for suspension cable or arch, forces are always defined by the global moment and lever arm of resisting couple. For uniform load and simple support, the maximum moment M and maximum shear V are computed as:

$$M = w L^2 / 8$$

$$V = w L / 2$$

w = uniform gravity load

L = span

For other load or support conditions use appropriate formulas

Beam

Beams resist the global moment by a force couple, with lever arm of $2/3$ the beam depth d ; resisted by top compression C and bottom tension T .

Truss

Trusses resist the global moment by a force couple and truss depth d as lever arm; with compression C in top chord and tension T in bottom chord. Global shear is resisted by vertical and / or diagonal web bars. Maximum moment at mid-span causes maximum chord forces. Maximum support shear causes maximum web bar forces.

Cable

Suspension cables resist the global moment by horizontal reaction with sag f as lever arm. The horizontal reaction H , vertical reaction R , and maximum cable tension T form an equilibrium vector triangle; hence the maximum cable tension is:


$$T = (H^2 + R^2)^{1/2}$$

Arch

Arches resist the global moment like a cable, but in compression instead of tension:

$$C = (H^2 + R^2)^{1/2}$$

However, unlike cables, arches don't adjust their form for changing loads; hence, they assume bending under non-uniform load as product of funicular force and lever arm between funicular line and arch form (bending stress is substituted by conservative axial stress for approximate schematic design).



Radial pressure

Referring to diagram A, pressure per unit length acting in radial direction on a circular ring yields a ring tension, defined as:

$$T = R p$$

T = ring tension

R = radius of ring

p = uniform radial pressure per unit length

Units must be compatible, i.e., if p is force per foot, R must be in feet, if p is force per meter, R must be in meters. Pressure p acting reversed toward the ring center would reverse the ring force from tension to compression.

Proof

Referring to ring segment B:

T acts perpendicular to ring radius R


p acts perpendicular to ring segment of unit length



Referring to ring segment B and vector triangle C:

p and T in C represent equilibrium at o in B

$T / p = R / 1$ (due to similar triangles), hence

$$T = R p$$





Examples

Vierendeel Girder

Assume

Steel girders spaced 20'

Allowable stress (60% of $F_y = 46$ ksi tubing)

DL = 18 psf

LL = 12 psf (20 psf reduced to 60% for tributary area > 600 sq. ft.)

$\Sigma = 30$ psf

Uniform girder load

$w = 30 \text{ psf} \times 20' / 1000$

Joint load

$P = w e = 0.6 \times 10'$

Vertical Reaction

$R = w L / 2 = 0.6 \times 100' / 2$

END BAY CHORD

Chord shear

$V_c = (R - P/2) / 2 = (30 - 6/2) / 2$

chord bending

$M_c = V_c e / 2 = 13.5 \times 10' \times 12" / 2$

Moment of Inertia required

$I = M_c c / F_a = 810 \times 5" / 27.6 \text{ ksi}$

Use ST 10x10x5/16

WEB BAR (2nd web resists bending of 2 adjacent chords)

2nd bay chord shear

$V_c = (R - 1.5 P) / 2 = (30 - 1.5 \times 6) / 2$

2nd bay chord bending

$M_c = V_c e / 2 = 10.5 \times 10' \times 12" / 2$

Web bending

$M_w = M_c \text{ end bay} + M_c \text{ 2nd bay} = 810 + 630$

Moment of Inertia required

$I = M_w c / F_a = 1,440 \times 5" / 27.6$

Use ST 10x10x1/2 web bar

MID-SPAN CHORD (small chord bending ignored)

Mid-span global bending

$M = w L^2 / 8 = 0.6 \times 100^2 / 8$

Mid-span chord force

$P = M / d = 750 / 6$

Use ST 10 x 10 x 5/16

$L = 100'$

$F_a = 27.6 \text{ ksi}$

$w = 0.6 \text{ klf}$

$P = 6 \text{ k}$

$R = 30 \text{ k}$

$V_c = 13.5 \text{ k}$

$M_c = 810 \text{ k"}'$

$I = 147 \text{ in}^4$

$I = 183 > 147, \text{ ok}$

$V_c = 10.5 \text{ k}$

$M_c = 630 \text{ k"}'$

$M_w = 1,440 \text{ k"}'$




$I = 261 \text{ in}^4$

$I = 271 > 261, \text{ ok}$

$M = 750 \text{ k'}$

$P = 125 \text{ k}$

$297 > 125, \text{ ok}$



Wood Arch

Assume

Glue-lam, spaced 16', 3-hinged for transport and to avoid settlement stress. Available dimensions: $\frac{3}{4}$ " lams; $3\frac{1}{8}$ ", $5\frac{1}{8}$ ", $6\frac{3}{4}$ ", $8\frac{3}{4}$ " and $10\frac{3}{4}$ " wide).

Allowable buckling stress (from case studies)

$$F_c' = 200 \text{ psi}$$

LL = 12 psf (reduced to 60% of 20 psf for tributary area > 600 sq. ft.)

DL = 18 psf (estimate)

$$\Sigma = 30 \text{ psf}$$

Uniform load

$$w = 30 \text{ psf} \times 16' / 1000 =$$

$$w = 0.48 \text{ klf}$$

Global moment

$$M = w L^2 / 8 = 0.48 \times 100^2 / 8 =$$

$$M = 600 \text{ k'}$$

Horizontal reaction

$$H = M / d = 600 / 20 =$$

$$H = 30 \text{ k}$$

Vertical reaction

$$R = w L / 2 = 0.48 \times 100' / 2 =$$

$$R = 24 \text{ k}$$

Arch compression (max.)

$$C = (H^2 + R^2)^{1/2} = (30^2 + 24^2)^{1/2}$$

$$C = 38 \text{ k}$$

Cross section area required

$$A = C / F_c' = 38 / 0.2 \text{ ksi}$$

$$A = 190 \text{ in}^2$$

Glue-lam depth (try $5\frac{1}{8}$ " wide glue-lam)

$$t = A / \text{width} = 190 / 5.125 = 37'; \text{ use } 50 \text{ lams of } \frac{3}{4}"$$

$$t = 37.5"$$

Check slenderness ratio

$$L / t = 100' \times 12" / 37.5" =$$

$$L / t = 32 \text{ ok}$$

Note:


Arch slenderness of $L/t = 32$ is ok (the $5\frac{1}{8}$ " arch width is braced against buckling by the roof diaphragm).

Wind bracing at end bays may consist of diagonal steel rods in combination with compression struts. The lateral thrust of arches may be resisted by concrete piers that may be tied together by grade beams to resist the lateral arch thrust.

Final design must consider non-uniform load (snow on half the arch) resulting in combined axial and bending stress; the bending moment being axial force times lever arm between funicular pressure line and arch center. The funicular line may be found graphically.

Graphic method

- Draw a vector of the computed vertical reaction
- Draw equilibrium vectors parallel to arch support tangent
- Equilibrium vectors give arch force and horizontal reaction



Case studies

Skating Rink, Heerenveen, Holland

Architect: Van der Zee & Ybema

Engineer: Arie Krijegsman, ABT

Steel trusses

Allowable stress $F_y = 36 \text{ ksi} \times 0,6$

Truss span $L = 66\text{m}/0.3048$

Truss spacing $e = 7.2\text{m}/0.3048$

Truss depth at mid span $d = 5.8\text{m}/0.3048$

$DL = 0.6 \text{ kPa} \quad (12.5 \text{ psf})$

$LL = 0.5 \text{ kPa} \quad (10.4 \text{ psf})$

$\Sigma = 1.1 \text{ kPa} \quad (22.9 \text{ psf})$

Uniform load per truss

$w = 24' \times 22.9 \text{ psf} / 1000$

Mid span point load (center truss, A transfers load of circular end units)

Tributary area of end units

$A = \pi r^2/3 = \pi(217'/2)^2/3$

Point load per truss

$P = 12,278 \times 22.9 \text{ psf} / 1000 / 16 \text{ trusses}$

Global moment

$M = PL/4 + wL^2/8 = 18 \times 217/4 + 0.55 \times 217^2/8$

Chord bar force

$C = T = M/d = 4,214 / 19$

Bottom tension chord

Try wide flange section

Try wide flange

Allowable force P from AISC table (use $L = 0'$ for tension, no buckling)

$P_{all} = 222$

Top chord un-braced length $L = 217'/12$

Top chord bending (negative support bending)

$M = w L^2/12 = 0.55 \times 18^2 / 12$

Try W12x50

$A = 14.7 \text{ in}^2$, $I_x = 394 \text{ in}^4$, $r_x = 5.17''$ (y-axis is braced by roof deck)

Bending stress

$f_b = M c / I = 15 \text{ k}' \times 12'' \times 6'' / 394$

Axial stress $f_a = C / A = 222 \text{ k} / 14.7 \text{ in}^2$

Slenderness $KL/r_x = 1 \times 18' \times 12'' / 5.17''$

Allowable buckling stress (from AISC table)

Check combined stress $f_a/F_a + f_b/F_b \leq 1$

$f_a/F_a + f_b/F_b = 15.1/19 + 2.74 / 21.6 = 0.92$

Use

$F_a = 21.6 \text{ ksi}$

$L = 217'$

$e = 24'$

$d = 19'$

$w = 0.55 \text{ klf}$

$A = 12,278 \text{ sq. ft.}$

$P = 18 \text{ k}$

$M = 4,214 \text{ k}'$

$C = T = 222 \text{ k}$

W8x35

$222 = 222, \text{ ok}$

$L = 18'$

$M = 15 \text{ k}'$

$f_b = 2.74 \text{ ksi}$

$f_a = 15.1 \text{ ksi}$

$KL/r = 42$

$F_a = 19 \text{ ksi}$

$0.92 < 1, \text{ ok}$

W12x50




Exhibit Hall 26 Hanover

Architect: Thomas Herzog

Engineer: Schlaich Bergermann

Given

Steel suspender bands 30x400 mm (1.2x16"), spaced 5.5 m (18')

LL = 0.5 kN/m² (10 psf)

DL = 1.2 kN/m² (25 psf)

Σ = 1.7 kN/m² (35 psf)

Uniform load

$w = 1.7 \text{ kN/m}^2 \times 5.5 \text{ m} =$

$w = 9.35 \text{ kN/m}$

Global moment

$M = w L^2 / 8 = 9.35 \times 64^2 / 8$

$M = 4787 \text{ kN-m}$

Horizontal reaction

$H = M / f = 4787 / 7$

$H = 684 \text{ kN}$

Vertical reaction R (max.)

Reactions are unequal; use R/H ratio (similar triangles) to compute max. R

$R/H = (2f+h/2) / (L/2)$, hence

$R = H (2f+h/2) / (L/2) = 684 (2 \times 7 + 13/2) / (64/2)$

438 kN

Suspender tension (max.)

$T = (H^2 + R^2)^{1/2} = (684^2 + 438^2)^{1/2}$

$T = 812 \text{ kN}$

Suspender stress ($A = 30 \times 400 \text{ mm}$)

$f = T / A = 1000 \times 812 / (30 \times 400)$


$f = 67.7 \text{ MPa}$

US unit equivalent

$67.7 \text{ kPa} \times 0.145$

$f = 9.8 \text{ ksi}$


$9.8 < 22 \text{ ksi, ok}$



Graphic method

- Draw a vector of the total vertical load
- Equilibrium vectors parallel to support tangents give cable forces
- Equilibrium vectors at supports give H and R reactions.

Note: The unequal support height is a structural disadvantage since the horizontal reactions of adjacent bays don't balance, but it provides lighting and ventilation, a major objective for sustainability. The roof consists of prefab wood panels, filled with gravel to resist wind uplift. Curtain wall mullions at the roof edge are prestressed between roof and footing to prevent buckling under roof deflection. In width direction the roof is slightly convex for drainage; which also gives the interior roof line a pleasing spatial form.



Portal method

The Portal Method for rough moment frame design is based on these assumptions:

- Lateral forces resisted by frame action
- Inflection points at mid-height of columns
- Inflection points at mid-span of beams
- Column shear is based on tributary area
- Overturn is resisted by exterior columns only

1 Single moment frame (portal)

2 Multistory moment frame

3 Column shear is total shear V distributed proportional to tributary area:

$$V_a = (V/B) L_1 / 2$$

$$V_b = (V/B) (L_1 + L_2) / 2$$

$$V_c = (V/B) (L_2 + L_3) / 2$$

$$V_d = (V/B) L_3 / 2$$

4 Column moment = column shear $\times$ height to inflection point

$$M_a = V_a h / 2$$

$$M_b = V_b h / 2$$

$$M_c = V_c h / 2$$

$$M_d = V_d h / 2$$

5 Exterior columns resist most overturn, the portal method assumes they resist all

6 Overturn moments per level are the sum of forces above the level times lever arm of each force to the column inflection point at the respective level:

$$M_2 = F_2 h_2 / 2 \quad (\text{level 2})$$

$$M_1 = F_2 (h_2 + h_1 / 2) + F_1 h_1 / 2 \quad (\text{level 1})$$

Column axial force = overturn moment divided by width B

$$N = M / B$$

Column axial force per level:

$$N_2 = M_2 / B \quad (\text{level 2})$$

$$N_1 = M_1 / B \quad (\text{level 1})$$

7 Beam shear = column axial force below beam minus column axial force above beam

Level 1 beam shear:

$$V = N_1 - N_2$$

Roof beam:

$$V = N_2 - 0 = N_2$$

Beam bending = beam shear times distance to inflection point at beam center

$$M = V L / 2$$

Beam axial force is negligible and assumed 0

Example: 2-story building

Assume:

$$L1 = 30'$$


$$L2 = 20'$$

$$B = 30+20+30 = 80'$$

$$h = h1 = h2 = h = 14'$$

$$F1 = 8 \text{ k}$$

$$F2 = 12 \text{ k}$$



1st floor

Base shear

$$V = F1 + F2 = 8 + 12$$

$$V = 20 \text{ k}$$

Column shear

$$Va = (L1/2) (V/B) = 15 \times 20/80$$

$$Va = 3.75 \text{ k}$$

$$Vb = (L1+L2)/2 (V/B) = (20+30)/2 (20/80)$$

$$Vb = 6.25 \text{ k}$$

Column bending

$$Ma = Va h/2 = 3.75 \times 14/2$$

$$Ma = 26 \text{ k'}$$

$$Mb = Vb h/2 = 6.25 \times 14/2$$

$$Mb = 44 \text{ k'}$$

Overtake moments

$$M1 = F2 (h2+h1/2) + F1 h1/2 = 12 (14+7) + 8 \times 7$$

$$M1 = 308 \text{ k}$$

$$M2 = F2 h2/2 = 12 \times 7$$

$$M2 = 84 \text{ k'}$$

Column axial load 1st floor

$$N1 = M1/B = 308/80$$

$$N1 = 3.9 \text{ k}$$

Column axial load 2nd floor

$$N2 = M2/B = 84/80$$

$$N2 = 1.1 \text{ k}$$

Beam shear

$$V1 = N1 - N2 = 3.9 - 1.1$$

$$V1 = 2.8 \text{ k}$$

Beam bending

$$M1 = V1 L1/2 = 2.8 \times 30/2$$

$$M1 = 42 \text{ k'}$$

$$M2 = V1 L2/2 = 2.8 \times 20/2$$

$$M2 = 28 \text{ k'}$$

2nd floor

2nd floor shear

$$V = F2$$

$$V = 12 \text{ k}$$

Column a shear

$$Va = (L1/2) (V/B) = 15 \times 12/80$$

$$Va = 2.25 \text{ k}$$

Column b shear

$$Vb = (L1+L2)/2 (V/B) = (30+20)/2 \times 12/80$$

$$Vb = 3.75 \text{ k}$$

Column a bending

$$Ma = Va h/2 = 2.25 \times 14/2$$

$$Ma = 15.75 \text{ k'}$$

Column b bending

$$Mb = Vb h/2 = 3.75 \times 14/2$$

$$Mb = 26.25 \text{ k'}$$

Overtake moment

$$M2 = F2 h/2 = 12 \times 14/2$$

$$M2 = 84 \text{ k'}$$

Column axial load

$$N2 = M2/B = 84/80$$

$$N2 = 1.0 \text{ k}$$

Beam shear

$$V2 = N2$$

$$V2 = 1.0 \text{ k}$$

Beam 1 bending


$$M1 = V2 L1/2 = 1.0 \times 30/2$$

$$M1 = 15 \text{ k'}$$

Beam 2 bending

$$M2 = V2 L2/2 = 1.0 \times 20/2$$

$$M2 = 10 \text{ k'}$$



Moment frame

Eight story steel moment frame, high strength steel, $F_y = 50$ ksi $F_a = F_b = 30$ ksi

Live load 50 psf, load reduction R in percent per IBC

$R = 0.08$ (A-150)

A = tributary area

Max. reduction: 40% for members supporting a single level, 60% for other members

Gravity load	Beam (psf)	Column (psf)
Framing	10	10
Concrete slab	37	37
Partitions	20	20
Floor / ceiling	3	3
DL	70	70
LL	$50 \times 0.6 = 30$	$50 \times 0.4 = 20$
Total DL + LL	100	90
Average wind pressure		$P = 33$ psf

Design ground floor and 4th floor

Uniform beam load (shaded tributary area)

$W = 100$ psf $\times 30' / 1000$

$w = 3$ klf

Uniform column load (distributed on beam)

$w = 90$ psf $\times 30' / 1000$

$w = 2.7$ klf

Base shear

$V = 33$ psf $\times 30' \times 7.5 \times 12' / 1000$

$V = 89$ k

Level 4 shear

$V = 33$ psf $\times 30' \times 3.5 \times 12' / 1000$

$V = 42$ k

Overturn moments

Ground floor $M_0 = 33$ psf $\times 30' \times (7.5 \times 12')^2 / 2 / 1000$

$M_0 = 4,010$ k'

First floor $M_1 = 33$ psf $\times 30' \times (6.5 \times 12')^2 / 2 / 1000$

$M_1 = 3,012$ k'

Fourth floor $M_4 = 33$ psf $\times 30' \times (3.5 \times 12')^2 / 2 / 1000$

$M_4 = 873$ k'

Beam design

Column a & d axial load

$N_0 = M_0 / B = 4,010 / 90$

$N_0 = 45$ k

$N_1 = M_1 / B = 3,012 / 90$

$N_1 = 34$ k

Beam design

Beam shear

$V = N_0 - N_1 = 45 - 34$

$V = 11$ k

Beam bending

$M_{lateral} = V L / 2 = 11 \times 30 / 2$

$M_{lateral} = 165$ k'

$M_{gravity} = w L^2 / 12 = 3 \times 30^2 / 12$

$M_{gravity} = 225$ k'

$\Sigma M = 165 + 225$

$\Sigma M = 390$ k'


Required $S_x = M / F_b = 12' \times 390$ k' / 30 ksi

$S_x = 156$ in³

Use W18x86

$S_x = 166 > 156$

Note: W18 beam has optimal ratio $L/d = 20$




Ground floor


Column shear			
Column	$V_c = L_{\text{tributary}} V / B$		V_c
a & d	$15 \times 89 / 90$		14.8 k
b & c	$30 \times 89 / 90$		29.7 k
Column bending			
Column	$M_{\text{lateral}} = V_c h / 2$	$M_{\text{gravity}} = w L^2 / 24$	ΣM
a & d	$14.8 \times 12 / 2 = 89 \text{ k'}$	$2.7 \times 30^2 / 24 = 101 \text{ k'}$	190 k'
b & c	$29.7 \times 12 / 2 = 178 \text{ k'}$	0	178 k'
Column axial force (n = # of stories)			
Column	$P_{\text{lateral}} = M_o / B$	$P_{\text{gravity}} = n w L_{\text{tributary}}$	ΣP
a & d	$4,010 / 90 = 45 \text{ k}$	$8 \times 2.7 \times 15 = 324 \text{ k}$	369 k
b & c	0	$8 \times 2.7 \times 30 = 648 \text{ k}$	648 k
Column axial force + bending ($\Sigma P = P + M B_x$, estimate B_x than verify)			
Column	P	$M B_x$ (convert M to k")	ΣP
a & d	365 k	$12" \times 190 \text{ k' } \times 0.185 = 422 \text{ k}$	787 k
b & c	648 k	$12" \times 178 \text{ k' } \times 0.185 = 395 \text{ k}$	1043 k
Design column (assume $KL = 1.2 \times 12 = 14'$)			
Column	Use	Check P allowable vs. P	Check B_x estimate vs. B_x
a & d	W14x109	$803 > 785$, OK	$0.185 = 0.185$, OK
b & c	W14x145	$1090 > 1043$, OK	$0.185 > 0.184$, OK

4th floor


Column shear			
Column	$V_c = L_{\text{tributary}} V / B$		V_c
a & d	$15 \times 42 / 90$		7 k
b & c	$30 \times 42 / 90$		14 k
Column bending			
Column	$M_{\text{lateral}} = V_c h / 2$	$M_{\text{gravity}} = w L^2 / 24$	ΣM
a & d	$7 \times 12 / 2 = 42 \text{ k'}$	$2.7 \times 30^2 / 24 = 101 \text{ k'}$	143 k'
b & c	$14 \times 12 / 2 = 84 \text{ k'}$	0	84 k'
Column axial force (n = # of stories)			
Column	$P_{\text{lateral}} = M_o / B$	$P_{\text{gravity}} = n w L_{\text{tributary}}$	ΣP
a & d	$873 / 90 = 10 \text{ k}$	$4 \times 2.7 \times 15 = 162 \text{ k}$	172 k
b & c	0	$4 \times 2.7 \times 30 = 324 \text{ k}$	324 k
Column axial force + bending ($\Sigma P = P + M B_x$, estimate B_x than verify)			
Column	P	$M B_x$ (convert M to k")	ΣP
a & d	172 k	$12" \times 143 \text{ k' } \times 0.196 = 336 \text{ k}$	508 k
b & c	324 k	$12" \times 84 \text{ k' } \times 0.196 = 198 \text{ k}$	522 k
Design column (assume $KL = 1.2 \times 12 = 14'$)			
Column	Use	Check P allowable vs. P	Check B_x estimate vs. B_x
a & d	W14x82	$515 > 508$, OK	$0.196 = 0.196$, OK
b & c	W14x90	$664 > 522$, OK	$0.196 > 0.185$, OK



1



2



3

Test models

Static models are useful to test structures for strength, stiffness, and stability. They may have axial resistance (truss), bending resistance (beam), or both axial and bending resistance (moment frame). Static models have three scales: geometric scale, force scale, and strain scale. The geometric scale relates model dimensions to original dimensions, such as 1:100. The force scale relates model forces to the original structure. For a force scale of 1:100 one pound in the model implies 100 pounds in the original structure. The force scale should be chosen to keep model forces reasonable (usually under 50 pounds). The strain scale relates model strain (deformation) to strain in the original structure. A strain scale of 1:1 implies model strain relates to original strain in the geometric scale; given a geometric scale of 1:10 a model strain of 1 inch implies 10 inch original strain. For structures with small deformations may a strain scale of 5:1, for example, helps to visualize strain. However, structures with large strain like membranes, require a strain scale of 1:1 to avoid errors (see 2). Scales are defined as:

Geometric Scale: $S_G = L_m/L_o = \text{model dimension} / \text{original dimension}$

Force Scale: $S_F = P_m/P_o = \text{model force} / \text{original force}$

Strain Scale: $S_S = \epsilon_m/\epsilon_o = \text{model strain} / \text{original strain}$

The derivation for axial and bending resistance models assumes:

A = Cross-section area

E = Modulus of elasticity

I = Moment of inertia

k = Constant of integration for deflection; for cantilever beams with point load $\Delta = kPL^3 / (EI)$ where $k = 1/3$

m = Subscript for model

o = Subscript for original structure

Axial resistance

Unit Strain $\epsilon = \Delta L/L$ $\Delta L = P L / (AE)$ hence

Force $P = A E \Delta L/L = A E \epsilon$ hence

Force Scale = $S_F = P_m/P_o = A_m E_m / (A_o E_o) \epsilon_m/\epsilon_o$ since $\epsilon_m/\epsilon_o = S_S$

$S_F = A_m E_m / (A_o E_o) S_S$

$S_F = A_m E_m / (A_o E_o)$ if $S_S = 1$

$S_F = A_m/A_o = S_G^2$ if $E_m = E_o$


1 Axial strain $\Delta L = P L / (AE)$; unit strain $\epsilon = \Delta L/L$

2 Structures with large deformations, such as membranes, yield errors if the strain scale S_S is not 1:1; as demonstrated in the force polygon

3 Structures like trusses, with small deformations, may require a strain scale $S_S > 1$ to better visualize deformations.




1




2

Case A: Assuming $B = 1$ and $D = 2$
 $A = 1 \times 2 = 2$
 $I = 1 \times 2^3 / 12 = 0.66$




Case B: Assuming $B = 1$ and $D = 4$
 $A = 1 \times 4 = 4$
 $I = 1 \times 4^3 / 12 = 5.33 (= 8 \times 0.66)$

$= 2 \times \text{case A}$
 $= 8 \times \text{case A}$



Case C: Assuming $B = 2$ and $D = 2$
 $A = 2 \times 2 = 4$
 $I = 2 \times 2^3 / 12 = 1.33 (= 2 \times 0.66)$

$= 2 \times \text{case A}$
 $= 2 \times \text{case A}$



3

Bending resistance

$$\text{Unit Strain } \varepsilon = \Delta / L \quad \Delta = kPL^3 / (EI) \quad \text{hence}$$

$$\text{Force } P = EI\Delta / (kL^3) = EI / (kL^2) \Delta / L \quad \text{hence}$$

$$\text{Force Scale } S_F = P_m / P_o = [E_m I_m / (E_o I_o)] k_o / k_m L_o^2 / L_m^2 \varepsilon_m / \varepsilon_o$$

Since the model and original have the same load and support conditions the constants of integration $k_m = k_o$, hence the term k_o / k_m may be eliminated. The term $L_o^2 / L_m^2 = 1 / S_G^2 = 1 / \text{geometric scale squared}$, and $\varepsilon_m / \varepsilon_o = S_S = \text{strain scale}$. Therefore the force scale is:

$$S_F = E_m I_m / (E_o I_o) 1 / S_G^2 S_S$$

$$S_F = E_m I_m / (E_o I_o) 1 / S_G^2$$

$$\text{If } S_S = 1$$

$$S_F = I_m / I_o 1 / S_G^2$$

$$\text{If } E_m = E_o, \text{ or simplified}$$

$$S_F = S_G^2$$

$$\text{assuming all model dimensions,}$$

including details, relate to the original in the geometric scale

In the simplest form the force scale is equal to the geometric scale squared for both axial and bending resistant models. Thus a model with a geometric scale of 1:100 has a force scale of 1:10,000 if it is made of the same material or modulus of elasticity as the original structure.

Combined axial and bending resistance



Models with both axial and bending resistance, such as moment frames, should be of the same material or elastic modulus as the original in order to avoid errors. Referring to diagrams 3, if, for example, the elastic modulus of a model is half as much as in the original structure and the cross-section area is doubled to compensate for it, then the moment of inertia is four times greater, assuming area increase is perpendicular to the bending axis. For small adjustments this can be avoided by increasing the area parallel to the bending axis. Large differences in stiffness, such as wood simulating steel, with an elastic modulus about 20 times greater, are not possible. In such a case the strain scale could be 20:1 to amplify deflection rather than adjusting the cross-section area.

- 1 Model strain $\varepsilon = \Delta / L$ must be equal to the original strain.
 $\Delta = k PL^3 / EI$ where $k = 1/3$

- 2 Original strain $\varepsilon = \Delta / L$
 $\Delta = k PL^3 / EI$ where $k = 1/3$

Since k is the same in the model as in the original, for equal load and support conditions, it may be eliminated from the force scale equation

- 3 Correlation between cross-section area A and moment of inertia I demonstrates incompatibility between A and I since they increase at different rates, unless the increase is only in width direction



Test stand

- Light gauge steel frame 3'x5'
- Frame to support test models
- Adjustable platform for loads below the test model (crank mechanism lowers platform to apply load)
- Blocking device holds load platform at any position
- Support frame for measure gauges above test model


Test procedure

- Position model with open base to allow loads below
- Suspend load cups filled with lead or sand from model (support loads on load platform before loading)
- Attach measure gauges above model
- Lower load platform with crank to apply load
- Measure deformations and stress
- Apply alternate loads (half load, etc.)
- Record deformations and stresses for all load conditions


Note

- Apply loads briefly to avoid creep deformation
- Apply loads gradually to avoid rupture
- Test all load conditions that may cause critical deformation or stress
- Adjust design if deformation or stress exceeds acceptable limits






Moment frame(with joint numbers and member names)



Load diagram (uniform beam load, lateral point load)



Hexagonal grid shell dome

Computer aided design

Advance in computer technology made structural design and analysis widely available. The theory and algorithm of structural design programs is beyond the scope of this book. However, a brief introduction clarifies their potential and use.


Structure programs generate and solve a stiffness matrix of the structure. Based on the degree of freedom of joints, the output provides stress and strain. A two-dimensional truss with pin joints has two degrees of freedom and thus two unknowns per joint, X and Y-displacement. A three-d truss has three unknowns per joint. Two-D frames have four unknowns, X, Y-displacement and X, Y-rotation, but three-D frames have six unknowns per joint, X, Y, Z-displacement and X, Y, Z-rotation.

The structure input is defined by joints, members connecting the joints and loads. Joints of three-d structures are defined by X, Y, Z-coordinates, joint type (pin or moment joint), and degree of freedom, regarding X, Y Z-displacement and X, Y, Z-rotation (joints attached to the ground are fixed with pin or moment joints). Members are defined by properties, cross section area, moment of inertia, and modulus of elasticity. Some members may have *end release* at one or both ends, to allow pin joints of braces to connect to moment joints of beam to column, for example. End releases are simulated by a dummy pin adjacent to the moment joint. The geometry of a structure may be defined in the analysis program or imported as DFX file from a CAD program. Loads are defined as distributed or point load. Gravity load is usually assigned as uniform beam load, yet lateral wind or seismic loads are usually assigned as point loads at each level.

Output includes force, stress, and deformation for members, joint displacement and rotation, as well as support reactions. Output may be in tables and / or graphic display. Graphic display provides better intuitive understanding and is more convenient to use.

Some programs simulate non-linear material behavior and / or non-linear geometric behavior. For example, non-linear material may include plastic design of steel with non-linear stress/strain relation in the plastic range. Non-linear geometric analysis is for structures with large displacements, such as cable or membrane structures. Non-linear analysis usually involves an iterative algorithm that converges after several iterations to a desired level of accuracy. Some programs include a *prestress* element to provide form-finding for membranes structures. Some programs provide dynamic analysis, sometimes referred too as 4-D analysis. Programs with advanced features provide greater versatility and accuracy, but they are usually more complex to use.


Multiframe-4D used for the demonstrations features 2-d and 3-d static and 4-d dynamic analysis. For static analysis Multiframe is very user friendly, intuitive, and thus good for architecture students. The 4-d dynamic feature is beyond the scope of this book. The examples presented demonstrate 2-d and 3-d design/analysis. A very convenient feature are tables of steel sections with pre-defined properties for US sections and for several other countries. The program features US and SI units.




Output display

Output includes member force, stress, deformation, joint displacement and rotation, as well as support reactions, all as numeric tables and color graphs. Clicking any member or joint provides detailed information. Force and stress include axial, bending, shear, as well as combined axial and bending stress. Based on the output, members may be resized in proportion to stress or strain. Animation allows to visualize deformation correlated with force or stress patterns.


Bending stress





Axial stress



Shear stress



Deflection with colored stress (also available in animation mode)



Belt truss effect

CAD-analysis provides efficient means to compare framing systems. For convenience the following example was done with constant W18 beams and W14 columns, 30' beam spans, and 12. story heights. The results, comparing the effect of belt and top trusses on a moment frame and a braced frame are very revealing:

20-story moment frame



Gravity load

$w = 3 \text{ klf}$

Wind load

$P = 10 \text{ k / level}$

Frame:	Drift
Frame only	15.1"
Top truss	14.9"
Belt truss	14.2"
Top and belt truss	14.0"



20-story braced frame

Gravity load

$w = 3 \text{ klf}$

Wind load

$P = 10 \text{ k / level}$

Frame	Drift
Frame only	17.6"
Top truss	11.4"
Belt truss	11.1"
Top and belt truss	8.6"

Note:

Belt and top trusses are much more effective to reduce drift at the braced frame than at the moment frame. The combined belt and top trusses reduce drift:

- 7 % at moment frame
- 49 % at braced frame

Interpreting the results clarifies the stark difference and fosters intuitive understanding of different deformation modes of moment and braced frames.

PART IV

11






HORIZONTAL SYSTEMS

Part III presents structure systems, divided into two categories: horizontal, and vertical/lateral. Horizontal systems include floor- and roof framing systems that support gravity dead- and live load and transfer it to vertical supports, such as walls and columns. As the name implies, vertical/lateral systems include walls, columns and various other framing systems that resist gravity load as well as lateral wind- and seismic load.

In the interest of a structured presentation, both, horizontal and vertical/lateral systems are further classified by type of resistance controlling the design. This also helps to structure the creative design process. Though many actual systems may include several modes of resistance, the controlling resistance is assumed for the classification. For example, cable stayed systems usually include bending elements like beams, in addition to cables or other tension members. However, at least at the conceptual level, their designed is controlled more by tension members than by bending. Therefore they are classified as tensile structures. Horizontal systems are presented in four chapters for structures controlled by bending, axial, form and tensile resistance. Vertical/lateral systems are presented in three chapters for structures controlled by shear-, bending-, and axial resistance.

HORIZONTAL SYSTEMS Bending Resistant

Bending resistant systems include joist, beam, girder, as well as Vierendeel frame and girder, folded plate and cylindrical shell. They carry gravity load primarily in bending to a support structure. Shear is typically concurrent with bending, yet bending usually controls the design. Though bending resistant elements and systems are very common, they tend to be less efficient than other systems, because bending varies from maximum compression to maximum tension on opposite faces, with zero stress at the neutral axis. Hence only half the cross-section is actually used to full capacity. Yet, this disadvantage is often compensated by the fact that most bending members are simple extrusions, but trusses are assembled from many parts with costly connections. Like any structure system, bending elements are cost effective within a certain span range, usually up to a maximum of 120ft (40m). For longer spans the extra cost of more complex systems is justified by greater efficiency.



Bending Concepts

Some concepts are important for an the intuitive understanding of bending members and their efficient design. They include the effects of span and overhang, presented in this section. Other concepts, such as optimization and the *Gerber* beam, are included in the following section.

Effect of span

The effect of the span L for bending members may be demonstrated in the formulas for deflection, bending moment and shear for the example of a simple beam under uniform load.

$$\Delta = (5/384) wL^4 / (EI)$$

$$M = wL^2/8$$

$$V = wL/2$$

where

Δ = Maximum deflection

E = Elastic modulus

I = Moment of Inertia

L = Length of span



M = maximum bending moment

V = maximum shear force

w = Uniform load per unit length

The formulas demonstrates, deflection increases with the 4th power of span, the bending moment increases with the second power, and shear increases linearly. Although this example is for a simple beam, the same principle applies to other bending members as well. For a beam of constant cross-section, if the span is doubled deflection increases 16 times, the bending four times, but shear would only double. Thus, for long bending members deflection usually governs; for medium span bending governs, yet for very short ones, shear governs


- 1 Beam with deflection $\Delta = 1$
- 2 Beam of double span with deflection $\Delta = 16$
- 3 Short beam: shear governs
- 4 Medium-span beam: bending governs
- 5 Long-span beam: deflection governs



Effect of overhang

Bending moments can be greatly reduced, using the effect of overhangs. This can be describe on the example of a beam but applies also to other bending members of horizontal, span subject to gravity load as well. For a beam subject to uniform load with two overhangs, a ratio of overhangs to mid-span of 1:2.8 (or about 1/3) is optimal, with equal positive and negative bending moments. This implies an efficient use of material because if the beam has a constant size – which is most common – the beam is used to full capacity on both, overhang and span. Compared to the same beam with supports at both ends, the bending moment in a beam with two overhangs is about one sixth ! To a lesser degree, a single overhang has a similar effect. Thus, taking advantage of overhangs in a design may result in great savings and economy of resources.

- 1 Simple beam with end supports and uniform load
- 2 Cantilevers of about 1/3 the span equalize positive and negative bending moments and reduces them to about one sixth, compared to a beam of equal length and load with but with simple end support




Beam optimization


Optimizing long-span girders can save scarce resources. The following are a few conceptual options to optimize girders. Optimization for a real project requires careful evaluation of alternate options, considering interdisciplinary aspects along with purely structural ones.

- 1 Moment diagram, stepped to reflect required resistance along girder
- 2 Steel girder with plates welded on top of flanges for increased resistance
- 3 Steel girder with plates welded below flanges for increased resistance
- 4 Reinforced concrete girder with reinforcing bars staggered as required
- 5 Girder of parabolic shape, following the bending moment distribution
- 1 Girder of tapered shape, approximating bending moment distribution


1




2



3




4



Gerber beam

The *Gerber* beam is named after its inventor, Gerber, a German engineering professor at Munich. The Gerber beam has hinges at inflection points to reduce bending moments, takes advantage of continuity, and allows settlements without secondary stresses. The Gerber beam was developed in response to failures, caused by unequal foundation settlements in 19th century railroad bridges.


- 1 Simple beams over three spans
- 2 Reduced bending moment in continuous beam
- 3 Failure of continuous beam due to unequal foundation settlement, causing the span to double and the moment to increase four times
- 4 Gerber beam with hinges at inflection points minimizes bending moments and avoids failure due to unequal settlement




Joist, Beam, Girder

Joists, beams, and girders can be arranged in three different configurations: joists supported by columns or walls¹; joists supported by beams that are supported by columns²; and joists supported by beams, that are supported by girders, that are supported by columns³. The relationship between joist, beam, and girder can be either flush or layered framing. Flush framing, with top of joists, beams, and girders flush with each other, requires less structural depth but may require additional depth for mechanical systems. Layered framing allows the integration of mechanical systems. With main ducts running between beams and secondary ducts between joists. Further, flush framing for steel requires more complex joining, with joists welded or bolted into the side of beams to support gravity load. Layered framing with joists on top of beams with simple connection to prevent displacement only

- 2 Single layer framing: joists supported directly by walls
 - 3 Double layer framing: joists supported by beams and beams by columns
 - 4 Triple layer framing: joists supported by beams, beams by girders, and girders by columns
 - 5 Flush framing: top of joists and beams line up
May require additional depth for mechanical ducts
 - 6 Layered framing: joists rest on top of beams
Simpler and less costly framing
May have main ducts between beams, secondary ducts between joists
- A Joists
B Beam
C Girders
D Wall
E Column
F Pilaster
G Concrete slab on corrugated steel deck



1



2

National Gallery, Berlin (1968)

Architect: Mies van der Rohe


The National Gallery was initially commissioned in 1962 for Berlin's twentieth century art collection. In 1965 it was merged with the National-galerie and renamed accordingly. A semi-subterranean podium structure of granite-paved concrete is the base for the main structure, a steel space-frame of 64.8m (212ft) square has a clear interior height 8.4m (28ft). At the roof edge eight cross-shaped steel columns with pin joint at the roof cantilever from the podium for lateral resistance. Based on a planning module of 1.2m, the unique space-frame consists of two-way steel shapes, 1.8m deep, spaced 3.6m on center in both direction. The shallow span/depth ratio of 33 required the roof to have a camber to cancel deformation under gravity load. The entire roof was assembled on ground from factory pre-welded units and hydraulically lifted in place on a single day.

1 Steel roof framing concept

2 Steel roof framing detail

A Steel edge beam

B Cross-shaped steel column



School in Gurtweil, Germany (1972)

Architect: H. Schaudt


Engineer: Ingenieurbüro für Holzbau

A grid of equilateral triangles is the base of this honeycomb of ten hexagonal classrooms. The side length of each regular hexagon is 5.4 m (18 ft). The composition of classrooms defines a free-form hall with entry from a central court. The sloping site provides space for a partial ground floor for auxiliary spaces below the classroom level.


Laminated beams spanning three ways presented a challenge to minimize the number of beam intersections. The continuous beams need moment connections. To this end, the main roof and floor structures have identical configurations but different support conditions. Six columns support each hexagonal classroom at the vertices. The classroom floors have an additional column at the center of each hexagon to support the cross point of three girders that span the six hexagon vertices. Those columns do not interfere with the auxiliary spaces below classrooms. Three beams span between the girders to form four triangular panels. Floor joists rest on the beams and support a particle board sub-floor with acoustical and thermal insulation. To provide uninterrupted classrooms, the roof structure has no column support within each hexagon. The column-free spaces required beams with moment connections. The roof deck consists of planks with tongue-and-groove. Diagonal steel rods, 24 mm (1 in) ϕ , with turnbuckles, brace some peripheral columns to resist lateral wind load.

- 1 Floor structure (roof is similar but without column at hexagon centers)
- 2 Column supporting center of floor hexagon
- 3 Moment resistant joint of roof beam at hexagon center without column

- A Laminated girder, 12x60 cm (5x24")
- B Steel insert bar with dowels ties beams to column
- C Hexagonal laminated column, ϕ 21 cm (8")
- D High-strength concrete core resists compression at top of roof beam
- E Steel strap, 10x80 mm (3/8x3"), resists tension at bottom of roof beam
- E Tension straps, 10x80mm, at bottom of beams



1




2

Labor Palace Turin (1961)

Architect/Engineer: Pierre Luigi Nervi

This project, first prize of a design competition, was build for the centenary of Italy's unification in 1981 to house an international labor exhibition. The classic order of this structure is a departure from Nervi's funicular oeuvre. Due to a short time from design to completion, one of the design objectives was fast construction. The solution of 16 freestanding mushroom structures allowed for sequential manufacture and erection, a critical factor for speedy completion. The facility measures 158x158m and has a height of 23m. Each of the 16 units measures 38x38m. The mushrooms are separated by gabled skylights of 2m width, that help to accentuate individual units visually, provide natural lighting and structural separation. Each mushroom consists of concrete pylons that taper from 2.4m at the top to 5.5m at the base in response to the increasing bending moment toward the base. The pylons are rounded at the top and cross-formed at the base. Twenty tapered steel plate girders cantilever from the pylons in a radial patterns; with increasing depth toward the support in response to greater bending. Triangular brackets strengthen the transition from girder to pylon. Stiffener plates welded to girder webs stabilizes them against buckling and provide a visual pattern in response to the structural imperatives.




1

Watt Hall, University of Southern California, Los Angeles (1974)



Architect: Sam Hurst

Watt Hall, the USC School of Architecture building, features 5 x 5 foot concrete waffle slabs, supported by a column grid of 30 x 30 feet (9x9 m). Four panels above each column are solid to resist shear the stress which is maximum over the columns. The exposed waffle slab provides a rich ceiling pattern as well as an educational demonstration of a common construction technology.




2







5




2




6




3



7



4




8

Vierendeel

Named after the Belgian builder *Vierendeel* who is credited with its invention, the Vierendeel girder has rectangular panels, composed of struts, which are connected by moment resistant joints. Since load is resisted in frame action rather than truss action, the terms *Vierendeel girder* or *frame* (depending on configuration) are more suitable than *Vierendeel truss* which implies triangular panels and axial stress rather than bending stress. Compared to trusses with triangular panels, rectangular Vierendeel panels allow ducts or pipes to pass through with greater ease. Rectangular panels also have a different visual appearance. Vierendeel girders resist load in combined axial and bending stress and, thus, tend to be less efficient than trusses of triangular panels, which resist load in axial tension and compression. Bending stress in members varies from zero at the neutral axis to maximum at the outer fibers, but axial stress is uniform and thus more efficient. For convenience, we refer to horizontal and vertical struts as **chord** and **web**, respectively. The load bearing of Vierendeel girders and frames can be visualized by magnifying their deformation under load. A single-bay Vierendeel¹ deforms under gravity load similar to a moment resisting portal frame²: top and bottom chords develop positive moments at mid span and negative moments at both ends, with two inflection points at the transition. Chord rotation is transmitted to webs and deforms them into S-shapes. The resulting web moments are inverse on top and bottom, with inflection points of zero moment at mid height. Under lateral load³ both chord and web struts are deformed with single inflection points in the middle. In multi-bay girders⁵, too, webs deform under both gravity- and lateral loads similar to frames⁶⁻⁷, with inflection points that may be hinged. However, the chords develop single inflection points for both lateral and gravity loads, except the center bay which has two inflection points under gravity load. In girders with even number of bays and a center web strut, all chords have single inflection points. Since all web struts, assume inflection points under both gravity and lateral load, they could have hinges at those points, provided those hinges can resist out-of-plane deformation to avoid instability.

- 1 Single-bay Vierendeel girder
- 2 Deformation under gravity load
- 3 Deformation under lateral load
- 4 Web struts with hinges at inflection points
- 5 3i-bay Vierendeel girder
- 6 Deformation under gravity load
- 7 Deformation under lateral load
- 8 3-bay web struts with hinges at inflection points



Vierendeel girders resist load in combed beam action and frame action as shown on the left and right diagrams, respectively. Load causes *global* shear and bending which elongates the bottom in tension and shortens the top in compression. The internal reaction to global shear and bending is different in a Vierendeel compared to a beam. A beam's bending stress varies gradually over the cross-section, but global bending in a Vierendeel causes concentrated tension and compression forces in the chords. By visual inspection we can derive simple formulas for approximate axial and shear forces and bending moments. Respective stresses are found using formulas for axial, shear and bending stress and superimposing them. Chord tension T and compression C are computed, dividing the respective global moment M by frame depth D (distance between centers of chords).


$$C = T = M / D$$

Bending of individual struts can be visualized too. In a structure where moment resistant strut/chord connections are replaced with hinges, chords would deflect as independent beams⁶. Assuming flexible chords and stiff webs, vertical shear would deform chords to S-shapes with inflection point. Assuming flexible webs and stiff chords, horizontal shear, caused by a compressive force pushing outward on top and a tensile force pulling inward on the bottom, would deform webs to S-shapes with inflection point. The combined effect of these two idealized cases imparts S-shaped deformation and inflection points in both chord and web struts. The deformation yields strut bending moments which vary from positive to negative along each strut. Top and bottom chords carry each about half the total shear V . Assuming inflection points at midpoints of chords, the local chord moment M is half the shear V multiplied by half the chord length.


$$M = (V / 2) (e / 2)$$

The moment M is maximum at supports where shear is greatest and equal to support reactions. For equilibrium, webs have to balance chord moments at each joint. Their moment equals the difference of adjacent chord moments.


- 1 Gravity load on a Vierendeel
- 2 Global shear (in overall system rather than individual members)
- 3 Global bending (in overall system rather than individual members)
- 4 Compression and tension in top and bottom chord, respectively
- 5 Free-body visualizes derivation of chord tension T and compression C
- 6 Global shear deformation
- 7 Chord bending, assuming flexible chords and stiff webs
- 8 Web bending, assuming flexible webs and stiff chords
- 9 Combined chord and web bending under actual condition
- 10 Free-bodies visualize derivation of chord bending moment M




1




4




2



5



3



6

Configurations


Vierendeels may have various configurations, including one-way and two-way spans.

One-way girders may be simply supported or continuous over more than two supports. They may be planar or prismatic with triangular or square profile for improved lateral load resistance. Some highway pedestrian bridges are of the latter type. A triangular cross-section has added stability, inherent in triangular geometry. It could be integrated with bands of skylights on top of girders.

When supports are provided on all sides, Vierendeel frames of two-way or three-way spans are possible options. They require less depth, can carry more load, have less deflection, and resist lateral load as well as gravity load. The two-way option is well suited for orthogonal plans; the three-way option adapts better to plans based on triangles, hexagons, or free-form variations thereof.

Moment resistant space frames for multi-story or high-rise buildings may be considered a special case of the Vierendeel concept.

- 1 One-way planar Vierendeel girder
- 2 One-way prismatic Vierendeel girder of triangular cross-section
- 3 One-way prismatic Vierendeel girder of square cross-section
- 4 Two-way Vierendeel space frame
- 5 Three-way Vierendeel space frame
- 6 Multi-story Vierendeel space frame



1

Salk Institute, La Jolla, California (1966)



Architect: Louis I. Kahn

Engineer: August Komendant and Fred Dubin Associates


The Salk Institute in La Jolla houses two research laboratories, flanked by service towers facing the outside, and study cells for scientists facing a central courtyard with view to the Pacific Ocean. North being oriented to the left on the drawing, offices are located on both west ends of the two lab wings. Mechanical rooms are located to the east. The courtyard concept was inspired by Dr. Salk's memory of the monastery of St. Francis of Assisi which he visited in the 1950's. This concept and the sparse use of material, reinforced concrete, accented by the study cell's teak wood finish, give the Salk Institute a serene beauty.

To avoid interior columns for greater flexibility, 9 ft (2.7m)-deep Vierendeel girders of prestressed concrete span across the width of the labs. These girders are located at interstitial spaces between ceiling and floor to provide space for ducts and pipes, allowing access to change them as required by evolving research needs. The Vierendeel struts vary in thickness and shape to reflect variable stress patterns. Top- and bottom chords are tapered for increased depth toward the supports where global shear, which generates chord bending stress, is greatest. Vertical struts, too, vary from minimum thickness at mid-span to maximum toward the supports, since their bending is the sum of the bending of all chords connected to them. However, the greatest bending in vertical struts occurs not over the supports but at struts next to them, since they absorb bending from chords on both sides; yet end struts transfer bending to only one set of chords.


Perspective section, courtesy Salk Institute




2



1



2




3 A - A

Beinecke library, Yale University, New Haven, Connecticut (1963)

Architect and Engineer: Skidmore, Owings and Merrill

The Beinecke library of Yale University for rare books has a 5-level central book tower, freestanding within a single story donut-shaped hall that extends over the full height of the tower. The tower holds 180,000 books and is climatically separated from the surrounding hall by a glass curtain wall.

The library's five-story open space is framed by a unique structural concept. Four Vierendeel steel frames, 50 ft (15 m) high, support the roof and wall load and span 131 and 88 ft (40 and 27m) in length and width, respectively. The frames are supported by a reinforced concrete plate that transfers the load via steel pin joints to four reinforced concrete pylons. The Vierendeel frames consist of 8'-8" (2.6m) prefabricated steel crosses, welded together during erection. The cladding of the crosses express pin joints at mid-points of chord and web struts, where inflection points of zero bending occur. The pin joints express two-way hinges by the tapering. This does not represent actual construction of the steel frame behind the cladding. If the frame had in fact two-way hinges, out-of-plane instability would result. This is a visual weakness of an otherwise compelling tectonic expression.




Recreation center, UC Davis, California


Architect: Perkins & Will

Engineer: Leon A. Riesenberg


The recreation center for the University of California at Davis holds 10,000 spectators for occasional events. Considering the low-rise context around the facility, a major design objective was to minimize the height. This was achieved by several means. The main level is 10 ft (2.7m) below grade. Landscaped earth berms, filled from the excavated soil, surround the facility to reduce its visual height. Along the building edge the roof deck is attached to the bottom chord to further reduce the bulk of the facility. The exposed space frame articulates the facade as well.

The Vierendeel space frame of steel tubing spans 252x315 ft (77x96m) with modules of 21x21x14ft (6x6x4m) for span/depth ratios of 18 and 22 in width and length directions, respectively. The optimum depth determined by computer was 15ft, but 14ft, the limit for rail or highway transportation was selected. The structure consists of 16in (406 mm) square tubing, ranging from 3/16 to 5/8in (5 to 16mm) thickness according to force distribution. Compared to a space truss with diagonal struts, Vierendeel frames make it easier to integrate lighting, mechanical ducts, and catwalks for maintenance. The structure weighs 15psf (73kg/m²) and was built in 1977 for \$11.54/ft² (\$124/m²). It was assembled in units spanning 1/3 the width of 252ft (77m). For economy sake, the tubular struts were shop welded from steel plates rather than using finished tubing.







1



2



3



4

Folded Plate


The effect of folding on folded plates can be visualized with a sheet of paper. A flat paper deforms even under its own weight. Folding the paper adds strength and stiffness; yet under heavy load the folds may buckle. To secure the folds at both ends increases stability against buckling

- 1 Flat paper deforms under its own weight
- 2 Folding paper increases strength and stiffness
- 3 Paper buckling under heavy load
- 4 Secured ends help resist buckling

Folded plate behavior


Folded plates combine slab action with beam action. In length direction they act like thin inclined beams of great depth, stabilized against buckling at top and bottom by adjoining plates. In width direction they are one-way slabs that span between adjacent plates.

- 1 Folded plate concept
 - 2 Slab action in width direction
 - 3 Slab-and-beam equivalent
 - 4 Beam action in length direction
- A Bending deformation causes top compression and bottom tension
 B Horizontal shear caused by compression and tension
 C Vertical shear is maximum at supports and zero at mid span



Bending in folded plates causes top compression and bottom tension. Folded plates also tend to flatten out under gravity load, which may be prevented by walls or frames at end supports. Tendency of end panel buckling can be resisted by edge beams.


- 1 Bending visualized as external compression and tension forces
 - 2 Flattened folded plate under gravity load
 - 3 Folded plate with walls and frames to resist flattening
 - 4 Buckled end panels
 - 5 End panels stabilized by edge beams
- A Stabilizing wall at support and, for long systems, at mid-span
 B Stabilizing frame at support and, for long systems, at mid-span
 C Edge beam to stabilize end panel against buckling



Folded plate forms


Folded plates may have many one-way, two-, or three-way spans. They may be motivated by aesthetic or spatial objectives, or to add strength and stability to a system. In areas with snow, flat folded plates are problematic since snow can accumulate in the valleys. One-way systems are shown below; Two and three-way systems are right.





- 1 Folded plate with one straight and one gabled edge
- 2 Folded plate with offset gabled edges
- 3 Folded plate with gabled edges offset at mid-span
- 4 Folded plate with vertical support folding and gables offset at mid-span



Folded plates may be two or three-way systems.

- 1 Three-way folded plate unit and assembly on triangular base plan
- 2 Two-way folded plate unit and assembly on square base plan
- 3 Three-way folded plate unit and assembly on hexagonal base plan





Railroad Station Savona, Italy (1961)

Architect: Antonio Nervi

Engineer: Pier Luigi Nervi

This first prize of a design competition consists of site-cast concrete folded plates, supported by a folded plate concrete wall on the rear which also provides lateral stability. Ten concrete pylons support the public entry front. The pylons are cantilevered from a grade beam for lateral stability in length direction. The pylons transform from rectangular cross-section in length direction at the ground to rectangular cross-section in width direction at the roof. They support a u-shaped roof girder that is integral with and supports the folded plate roof. One-third of the roof overhangs in front, beyond the girder. The overhang is tapered, transforming from the folded plate profile to a flat roof edge. The taper makes an elegant edge in logic response to the diminished negative bending moment requiring less depth at the edge. Light-weight gabled roof elements cover the folded plates over interior space for waterproofing. Over the central area skylights, integrated in the roof, provide natural lighting.

1 Folded plate concrete roof layout

2 Typical folded plate concrete unit

A Cross-section through roof overhang with tapered folded plates and u-shape girder

B Length-section through folded plates

Gunma Music Center, Takasaki, Japan (1961)


Architect: Antonin Raymond

Engineer: Tsuyashi Okamoto

This Gunma music center for the Gunma Philharmonic Orchestra, consist of a folded plate concrete roof of 60 m span and folded plate walls, that form frames to resist gravity and lateral loads. The architect, a former student of Frank Lloyd Wright at Taliesin took the challenge to design the center for the following requirements:

- The center had to be fire and earthquake proof
- Good acoustics for the music center
- Provide for Kabuki performances that required a revolving stage

The folded plate roof is 3.3 m deep for a span/depth ratio of 1:18. Two wings flanking the stage for meeting and green rooms, also have folded plate roofs.



Shopping Center, Würzburg, Germany


Architect: Schönewolff and Geisendörfer


Engineer: Julius Natterer

The folded plate wood roof modules are 7 m wide and span 16.25 m for the large space; 5 m wide and span 12.5 m for small spaces.


- 1 View of folded plate wood roof
- 2 Cross-section of typical folded plate module
- 3 Detail of valley joint

- A Tie strut 135x520 mm. At both ends
B Folded plate cross planking 4 cm
C Transverse ribs, 8 x 16 cm, spaced 1.9 m







1




2



3



4










5

Cylindrical Shell

The shape effect of cylindrical shells can be visualized with paper. A flat paper deforms even under its own weight. To roll or bend paper into cylindrical shapes adds strength and stiffness; yet heavy load may flatten and buckle the paper. Securing both ends prevents buckling

- 1 Flat paper deforms under its own weight
- 2 Rolling paper increases strength and stiffness
- 3 Cylindrical form also increase strength and stiffness
- 4 Paper buckling under heavy load
- 5 Secured ends help resist buckling



Cylindrical shell behavior




Considering their name, cylindrical shells could be part of shells; but they are included here because they resist load primarily in bending, unlike shells which act primarily in tension and compression. Most cylindrical shells have semi-cylindrical cross-sections and act much like beams of such cross-section, spanning horizontally to transfer gravity load to supports. Like beams under gravity load, bending in cylindrical shells cause compressive stress on top and tensile stress at the bottom. Unlike vaults with primary span in width direction. Differential bending stress, pushing and pulling on top and bottom generates horizontal shear stress in cylindrical shells. To satisfy equilibrium, horizontal shear causes also vertical shear which can be visualized as tendency of individual parts to slide vertically with respect to one-another. Stress distribution over the cross-section is also similar to beams. Bending stress varies from maximum compression on top to maximum tension on the bottom, with zero stress at the neutral axis. In contrast, shear stress is maximum at the neutral axis and zero on top and bottom. Compressive stress in cylindrical shells also cause buckling. This can be resisted by cross-walls or ribs.

- 1 Compressive stress on top, tensile stress at bottom, with some arch action
- 2 Horizontal shear generated by differential compressive and tensile stress
- 3 Vertical shear visualized
- 4 Bending stress distribution
- 5 Shear stress distribution
- 6 Buckling under gravity load
- 7 Buckling under lateral load
- 8 Wall panels to resist buckling
- 9 Ribs to resist buckling

Configurations

Cylindrical shells can have various configurations: cross-sections of half or quarter cylinders, or other curved forms; they may have closed ends or be open at one or both ends; they may be simply supported, cantilevered, or span two supports with one or two overhangs. The end units may be open or closed. Butterfly cross-sections are also possible if designed to resist bending in width direction. The intersection between adjacent shells must incorporate a gutter to drain rainwater. In snow areas, horizontal cylindrical shells are problematic, since snow would accumulate in the valleys.




- 1 Semi-circular cylindrical shells, simply supported, with glass ends
- 2 Shallow units cantilever from a beam, designed to resist rotation
- 3 Butterfly units, cantilevered from pylons



Skylights

Various skylight forms may be integrated with cylindrical shells. This has been a popular solution for natural lighting of industrial buildings. Combining the inherent strength, stiffness, and stability of cylindrical shell forms with natural lighting is a logical design strategy. The skylights may be inclined in the shell form, or flat on top, or in the vertical plane of a quarter-cylindrical shell. Skylights could be incorporated with a truss as part of the cylindrical shell. An important factor in integrated skylights is waterproofing to prevent leaks, and to incorporate some form of gutter for drainage.

- 1 Cylindrical shell with truss skylight
- 2 Skylight on top of cylindrical shell
- 3 Vertical skylight with cylindrical shell of quarter cross-section




Kimbell Art Museum

Architect: Louis Kahn


Engineer: Kommendant


The Kimbell Art Museum is composed of three parts: the central main entrance, facing bookstore and library is flanked by two gallery wings, one on each side. The gallery wings include atrium courtyards. The entire facility is composed of 16 modules of about 30x100ft (9x31 m). The modules consists of cycloid shells, 24ft (7.3m) wide with a flat part of 6ft (1.8m) between them (the cycloid cross-section is formed by a point on a moving wheel). A 30in (76 cm) wide skylight extends on top of each shell unit. A metal deflector below each skylight reflects the daylight against the interior surface of the cycloid shells for indirect natural lighting. The cycloid shells consist of post-tensioned cast-in-place concrete. They were cast, using a single movable form-work used repetitively. The flat roof between cycloid shells forms an inverted U to house mechanical ducts and pipes as required.



- 1 Exploded isometric view
- 2 Cycloid, formed by a point on a cycle that moves horizontally
- 3 Cross-section of cycloid shells

- A Point on the cycle that
- B Cycloid traced by the point on a cycle
- C Linear skylight
- D Reflectors of polished metal
- E Mechanical ducts
- F Duct cover





1

California Museum of Science and Industry

Architect: California State Architect Office

Engineer: T. Y. Lin and Associates


The roof of this rectangular museum consists of ten cylindrical shells and two half shells as curved overhangs on the north and south sides. A group of eight inverted conical shells provides a canopy for the main south side entry. The cylindrical shells provide spatial relief and articulation for this stark rectangular plan. They continue over two bays with overhangs on both ends and with span/depth ratios of 10. Post-tensioned tendons are draped to approximate a parabola in space. Reflecting the bending deformation of the shells, the parabolic form has an uplifting effect to counteract and minimize deflection. The tendons are prestressed to produce a camber, designed to offset deflection due to dead load and partial live load. The cylindrical shells were site-cast, using lightweight concrete (80% of normal weight concrete) to minimize dead load. This is important in areas of seismic activity, like Los Angeles, since seismic forces are proportional to mass, which corresponds to deadweight. The shell thickness increases toward the base where they form beams between adjacent units.

1 Isometric roof plan


2 Length section in east-west direction

3 Typical shell cross-section


A Post-tensioned prestress tendons, draped to offset deflection




2



3



1



2

Kindergarten Yukari, Tokyo

Architect: Kenzo Tange

The fan-shaped plan of the Yukari Kindergarten for 280 children is designed in response to a conic site of mild slope. The director of the facility, an artist, wanted an environment of artistic inspiration for children of this kindergarten. The plan and space are strongly defined by prefabricated cylindrical concrete shells, consisting of twin quarter-circular elements with top stems for assembly and to hold the prestress tendons. Fan-shaped shells accommodate the plan layout: each twin unit covers a modular space; large spaces are covered by several units. Glass end walls emphasize the cylindrical shells and extend them visually to the outside. Unit lengths vary with the spatial requirements. The plan shows at left the roof and at right the floor plan with shells as dotted lines.


14


HORIZONTAL SYSTEMS Tensile Resistant

Tensile-resistant systems include stayed, suspended, cable truss, anticlastic, and pneumatic structures. Although compression, bending and shear may be present in some tensile structures, tensile stress is most prominent. For example, cable-stayed systems may include bending resistant beams and joists, yet they are secondary to primary stay cables or rods. Compared to bending and compression, tensile elements are most efficient, using material to full capacity. Bending elements use only half the material effectively, since bending stress varies from compression to tension, with zero stress at the neutral axis. Compression elements are subject to buckling of reduced capacity as slenderness increases. Furthermore, some tension elements, such as steel cables, have much greater strength than columns or beams of mild steel, because they are *drawn* (stretched) during manufacturing to increase strength. However, the overall efficiency of tensile structures depends greatly on supports, such as ground anchors. If poorly integrated, they may require a large share of the budget. Therefore effective anchorage is an important design factor. For example, the use of self-stabilizing compression rings or infrastructures, such as grandstands, to resist tensile forces can be an effective means of reducing support costs.

Tension members

- 1 Steel rod
 $E = 30,000$ ksi, $F_a = 30$ ksi, 100 % metallic
- 2 Strand consists of 7 or more wires (provides good stiffness, low flexibility)
 $E = 22,000$ to $24,000$ ksi; $F_a = 70$ ksi, 70% metallic
- 3 Wire rope consists of 7 strands (provides good flexibility, low stiffness)
 $E = 12,000$ to $20,000$ ksi, $F_a = 70$ ksi, 60% metallic






Prestress

Tensile structures usually include flexible membranes and cables that effectively resist tensile forces but get slack under compression. Yet, under some load conditions, compressive forces may be induced in flexible tensile members. Prestress allows flexible members to absorb compressive stress without getting slack which would cause instability. Prestress also reduces deformation to half. These phenomena may be observed on a simple string.


Consider a vertical string fastened on top and bottom. If a load is applied at mid-height, the top link absorbs the entire load, and the lower link will get slack and unstable.

Now consider the same string prestressed (with turnbuckles for example). The same load applied at mid-height will be carried half by the top link (through increase of prestress) and half by the lower link (through decrease of prestress). Since both links are active, each will absorb only half the load, reducing the deformation to half and avoiding the lower link from getting slack and unstable. Since half the load is absorbed by each link, when the applied load reaches twice the prestress or more, the lower link will get slack, just as the string with no prestress. Given similar conditions in a structure, prestress should be at least half of the design load to prevent slack members and instability. Also, loss of prestress due to creep and temperature variation should be considered.

The correlation between prestress, load, and deformation, described above, is visualized in the stress/strain diagram below.



- 1 String without prestress
 - 2 String with prestress
 - 3 Stress/strain diagram of both strings
- A Stress/strain line of un-prestressed string
 - B Stress/strain line of prestressed string
 - C Point where prestress is reduced to zero under load
 - D Stress/strain line of string after loss of prestress
- F Force
 f Stress
 P applied load
 PS Prestress
 Δ Deformation



Stayed Structures

Stayed structures consist of beams or trusses that are intermittently supported by strands or rods (strands and rods have greater stiffness than wire ropes and hence reduce deflection). Although stays usually support structures, pulling from above, they may also push from below by means of compression struts. The latter is also referred to as cable-propped or just propped. Given the slope of stays, they generate not only a vertical uplift but also a horizontal reaction in the supported members and masts. In beams the horizontal reactions yield compression; in masts they introduce bending and overturn moments, unless stays on both sides balance the horizontal reactions.





The span/depth ratio of stayed and propped structures is an important design factor. A shallow depth results in great tension and compression in stays and beam respectively, a steep slope has the opposite effect. The relationship of cable slope and resulting forces is illustrated in the diagrams, showing various slopes and resulting forces for an assumed gravity load as vertical vector. Optimal span/depth ratios depend on both, architectural and structural factors. Architectural factors include appearance and spatial considerations. Structural factors include the impact on deflection, overall cost of stays, beams, masts, and compression struts. As a rule of thumb, the optimal slope for stays is about 30 degrees. Optimum span/depth ratio for propped systems is about 10 to 15.

- 1 Steep stay slope causes small forces but high masts
- 2 Stay slope of 25° to 30° is usually optimal
- 3 Shallow stay slope causes high forces but low masts
- 4 Steep props cause small forces but great depth
- 5 Span/depth ratio of about 10 to 15 is optimal
- 6 Shallow props cause great forces but small depth

Configurations





Stayed structures may have radial or parallel strands, called radial and harp systems, respectively. Combinations of both systems are also possible. Harp systems have constant stay forces; the force of radial systems varies with the stay slope. The tributary length between radial stays may be adjusted to keep forces constant, i.e., strands with shallow slope support small tributary lengths.


- 1 Radial system (stay forces vary with slope)
- 2 Harp system (constant stay forces)
- 3 Mixed system, combining radial and harp patterns
- 4 System with variable distance between stay supports to equalize stay forces




For light-weight roofs, with wind uplift greater than the roof dead weight, stays could be added below the roof to resist wind uplift. Stays can also branch out like trees to reduce length. Single masts must be designed to resist overturning under unbalanced load. One-sided load causes unbalanced condition that require guy cables. The dead weight of an inclined mast may help to balance loads.

- 1 Stay cables below the roof resist wind uplift
- 2 Inverse tree stays reduce length but require more joints
- 3 Single tower with tie-downs at both beam ends to resist overturning
- 4 One-sided support with guy cable are unbalanced and less efficient; the inclined mast can help to balance the one-sided load







1



2



3



4

McCormick Place, Chicago (1987)


Architect: Skidmore, Owings and Merrill

Engineer: Knight and Associates

The expansion of McCormick Place exhibit hall, located over existing railroad tracks, required a long-span roof to provide column-free exhibit space without interfering with the tracks. Several structure systems had been investigated before selecting a stayed roof. The roof is suspended from 12 concrete pylons, spaced 120x240ft, with 120ft overhangs on both long sides. The pylons project 60 feet above the roof. The clear interior height is 40 feet. Stay cables consist of 3.75in galvanized steel strands, coated with corrosion resistant PVC, arranged in parallel harp form at an angle of 25 degrees. The stays support steel trusses which support secondary trusses, both 15ft deep and exposed at the interior. The concrete pylons are shaped to incorporate mechanical ducts which bring conditioned air from a mezzanine below the main floor and exhaust it over the roof, without mechanical equipment exposed on the roof. The roof truss edges are tied to the podium of the main hall to provide stability for unbalanced load. The podium is supported by steel columns, spaced to accommodate the rail tracks. Combined with the deep trusses, the stays have enough redundancy that they can be removed and replaced without affecting the structure's integrity. A glass band along the entire façade under the roof trusses and roof skylights, provide natural lighting.

- 1 Isometric roof structure
- 2 Cross-section of upper level with stayed roof
- 3 Mid-span stay support detail
- 4 Roof edge detail




- A Concrete pylons, shaped to accommodate mechanical ducts
- B Stays, 3.75in galvanized steel strands, PVC coated
- C Truss web bar
- D Stay connection bracket
- E Steel tie secures roof to podium



Suspended Structures

Suspended structures are used for long-span roofs. They are most effective if the curvature is compatible with spatial design objectives, and the horizontal thrust is resisted by a compression ring or by infrastructures, such as grandstands. Suspended cables effectively resist gravity load in tension, but are unstable under wind uplift and uneven loads. Under its own weight a cable assumes the funicular shape of a catenary (Latin for chain line). Under load uniformly distributed horizontally, the funicular will be parabolic; under point load the funicular is a polygon. Thus, without some means of stabilizing, cables assume different shapes for each load. Furthermore, under wind uplift suspended cables tend to flutter. Several means can be used to stabilize cables for variable loads and wind uplift. Among them are stabilizing cables, anticlastic (saddle-shaped) curvature, described later, and ballast weight. However, in seismic areas ballast weight would increase the mass and thus lateral loads.

- 1 Suspended roof with compression ring to absorb lateral thrust
- 2 Suspended roof with grandstands to resist lateral thrust
- 3 Catenary funicular under cable self weight
- 4 Parabolic funicular under horizontally distributed load
- 5 Polygon funicular under point load
- 6 Deformed roof under point load
- 7 Deformed roof under uneven load (snow at one side, for example)
- 8 Roof subject to wind uplift
- 9 Roof with convex stabilizing cables to resist uplift and uneven loads
- 10 Dead load to resist uplift and reduce deformation under uneven load





Dulles airport terminal, Washington, DC (1958-62)

Architect: **Eero Saarinen**

Engineer: **Ammann and Whitney**

The Dulles international airport terminal near Washington, DC, has a cable roof supported by concrete pylons. The outward leaning pylons partly resist the cable thrust. Based on the dimensions of movable loading docks, designed by Saarinen, the pylons are spaced at 40 ft (12m) for a column-free concourse space of 150x600ft (46x183m), recently expanded, extruding the same structure. Given the slanted pylons, the suspension cables actually span 161 ft (49 m). Concrete edge beams span the pylons at heights that vary from 65ft (20m) along the entry to 40ft (12m) facing the runways. Suspended from the edge beams are 128 bridge strands of $\varnothing$ 1in (25mm) which support site-cast concrete roof panels. The concrete dead weight resists wind uplift and minimizes roof deformations under unbalanced roof loads. In Saarinen's own words the Dulles roof is "a strong form between earth and sky that seems both to rise from the plain and hover over it." It presents functional integrity and synergy of form and structure.




Recycling hall, Vienna (1981)


Architect: L. M. Lang

Engineer: Natterer and Diettrich

This recycling center features a tent-like wood structure of 560 feet (170m) diameter that soars to a height of 220 feet (67m) above ground, supported by a central concrete mast. The suspended wood roof consists of 48 radial laminated ribs that rise from outer concrete pylons with wood compression ring to the mast top. The ribs follow the funicular tension line to carry uniform roof load in pure tension, but asymmetrical loads may cause bending stress in the radial ribs that are designed as semi-rigid tension bands with some bending resistance capacity. Diagonal boards form the roofing membrane and add shear resistance to the assembly of ribs and ring beams. The cylindrical concrete support mast cantilevers from a central foundation. It was designed to resist asymmetrical erection loads and to contribute to lateral wind load resistance. The peripheral pylons are triangular concrete walls with metal brackets on top to secure the radial ribs.

- 1 Cross section
- 2 Roof plan
- 3 Top of central support mast
- 4 Typical roof assembly
- A Radial laminated wood tension rib, 7.8x31-43 (20x80-110cm)
- B Laminated wood ring beams, 5x15in (12x39cm)
- C Laminated wood compression ring
- D Steel tension ring
- E Steel anchor bracket






Cable Truss

Cable trusses evolved from needs to stabilize suspension structures against wind uplift and unbalanced gravity loads, using a second set of cables with opposing curvature. The Swedish engineer Jawerth developed a cable truss with diagonal brace cables separating top support- and bottom stabilizing cables that resist wind uplift. This system was widely used in the 1960's. Lev Zetlin and other US engineers designed cable trusses with various other configurations, including lintel shapes with compression struts separating bottom support- and top stabilizing cables. In 1969 the author and his students at UC Berkeley developed trusses with flat chord cables separated by compression struts and diagonal truss cables. Model tests, a full scale prototype, and extensive computer analysis demonstrated great stiffness of these trusses in one-way, two-way, and three-way layouts.

- 1 Isometric of lintel trusses with bottom support- and top stabilizing cables separated by vertical compression struts
- 2 Isometric of concave trusses with top supporting- and bottom stabilizing cables separated by vertical tension struts
- 3 Lintel truss with diagonal compression braces
- 4 Lintel truss with vertical compression struts
- 5 Concave truss with diagonal tension braces
- 6 Concave truss with vertical tension struts
- 7 Concave/lintel truss with diagonal compression braces
- 8 Concave/lintel truss with vertical compression struts
- 9 Concave gable truss with fan support and stabilizing cables and central compression strut
- 10 Concave gable truss with tension struts and central compression strut
- 11 Concave support cable and fan stabilizing cables
- 12 Parallel chord truss, vertical compression struts and diagonal tension braces




Sports center project, University of California, Berkeley (1975)

Architect: G G Schierle

Engineer: T Y Lin


The Intramural sports center extension of the University of California Berkeley is a linear extrusion of four multipurpose gyms 120ft (37m) square and an Olympic swimming pool. An entrance hall facing the swimming pool links the new and existing facilities (at right in the drawing) via a linear circulation that also provides a visual link and overview of major spaces. Parallel chord cable trusses, spaced 20ft (6m), span the width of the facility. They are bilaterally braced by diagonal guy cables, designed to resist the horizontal thrust of the trusses and also provide lateral bracing for wind and seismic forces in both the length and width directions. The guy cable anchors line up with handball courts at the lower floor which absorb the horizontal force component of the guy cables. The guy cables express the lateral resisting system at the façade, much like buttresses on Gothic cathedrals.

Joint detail of prototype structure



Two-way prototype structure by students of the author at UC Berkeley (1975)







Watts Towers Crescent (1998)


Architect: G G Schierle with Joe Addo

Engineer: ASI


A transparent membrane suspended from radial cable trusses is designed to provide sun shading for occasional performances at the Watts towers. The crescent-shaped roof follows the crescent-shaped seating below. The cable trusses minimize bulk for optimal view of the towers and facilitate fast erection and removal at annual events. The truss depth provides desired curvature for the anticlastic membrane panels. Two membranes provide shading for spectators and performers over the respective areas. The architectural design is shown below. The final computer drawings are shown at right.




1




2



3



4



Anticlastic Structures

Anticlastic tensile structures are flexible membranes or cable nets of saddle-shaped curvature. The term membrane is used here to imply membranes and cable nets. Given the nature of flexible membranes, double curvature and prestress are essential for stability. This can be observed with simple string models. Two strings pulled in opposite directions stabilize a point at their intersection. If the strings are in non-parallel planes the stability will be three-dimensional. Similarly, if a series of strings cross in opposite directions they stabilize a series of points at their intersection. The cross points form a surface, stabilized by anticlastic curvature. The surface may be a membrane of fabric or other material or a cable net. Although anticlastic curvature provides stability, some elastic deformation is possible due to material elasticity. Thus, steel cable nets with high elastic modulus deform less than fabric membranes with lower stiffness.

In addition to curvature, prestress is also required to stabilize anticlastic membranes. This too can be observed on a string model. Applied load elongates one string in tension and shortens the other in compression. Without prestress, the compressed string will get slack and unstable; but prestressed strings absorb compressive stress by reduction of prestress. Since prestress renders both strings active to resist load, the resulting deflection is reduced to half compared to non-prestressed condition where only one string is active. This observation is also described under *Prestress* at the beginning of this chapter.

Flat membranes are unstable. This, too, can be observed on a string model. Two strings in a flat surface must deform into a polygon to resist load (a straight string would assume infinite forces). Therefore, flat membranes are unstable under load. Similarly, synclastic (dome-shape) membranes would deform excessively under gravity load and flutter in wind.

- 1 Two strings crossing in non-parallel planes stabilize a point in space
- 2 A series of strings (or a membrane) form a stable surface
- 3 Without prestress, one string (or series of strings) would get slack under load, causing instability
- 4 Strings in a flat surface deform excessively under load, causing instability

Minimal surface

As the name implies, a minimal surface covers any boundary with a minimum of surface area. The minimal surface is defined by three criteria:



- Minimum surface area between any boundary
- Equal and opposite curvature at any point
- Uniform stress throughout the surface

A minimal surface may be anticlastic or flat. A surface of flat or triangular boundaries is always flat. Flat membranes are unstable structures. Increased curvature increases stability. The minimal surface can be studied on soap film models; but they disappear quickly. The author studied quadrilateral plastic models that keep a minimal surface after drying. The models revealed:


$$f1/f2 = A/B$$

This is contrary to Hyperbolic Paraboloid shells. The surface of HP shells passes at mid-height between low and high points regardless of boundary conditions.


- 1 Minimal surface of square plan
- 2 Minimal surface of rhomboid plan
- 3 Hyperbolic Paraboloid of square plan
- 4 Hyperbolic Paraboloid of rhomboid plan




1



2



3



4

Minimal surface equations

The minimal surface models also revealed equations that define the principle curvature of equilateral minimal surfaces (Schierle, 1977):


$$Y = f1(X/S1)^{(f1+f2)/f1} + X \tan \phi$$

$$Y = f2(Z/S2)^{(f1+f2)/f2}$$


The equations are based on empirical studies of minimal surface models of plastic film, measured by means of a projected light grid with an accuracy of only 1.26% standard deviation. The findings were first published in the *Journal for Optimization Theory and Application* (Schierle, 1977)

Although the equations are for minimal surface of quadrilateral plans, they provide reasonable accuracy for other boundaries as well. This should be further studied.


- 1 Plan view of quadrilateral minimal surface
- 2 Length section of quadrilateral minimal surface
- 3 Length section with Y-axis vertical
- 4 Cross section



1



2



3

4

Saddle shapes

Structures symbolizing mountens (top and sailing (bottom)




Expo '64, Sector 7, Lausanne (1964)

Architect: Saugey / Schierle, Frei Otto, consultant

Engineer: Froidveaux et Weber

Sector 7 of the Swiss Expo '64 housed 26 restaurants, designed to connote mountains and sails as metaphor of Switzerland as vacation land. A village-like composition of quadrilateral membrane was nestled along and partly in lake Geneva to create a leisure setting. Each unit of 30/35m diagonal dimensions had three low points and one high point supported by steel mast. Colorful canvass membranes were stitched to cable nets in plastic tubes of 60/60cm meshes attached to edge cables. The high front was covered with a secondary membrane over a 3m tempered glass wall. Two prototypes of 15 and 23m high masts represented symbolic sails and mountain peaks, respectively.


- 1 Top of tall mast
- 2 Lake low point anchor
- A Cables
- B Tubular steel mast
- C Steel anchor bracket
- D Concrete sphere
- E Steel piles



Olympic Pool Tokyo (1964)

Architect: Kenzo Tange



The 1964 Olympic pool structure consists of two anticlastic saddles, offset to form entries and supported by two cables draped over two concrete pylons. The anticlastic saddles are formed by flexible beams, designed to resist load in tension, but with some bending stiffness to facilitate a curvature suitable for natural ventilation through louvers attached to trusses that join the main cables.




Kagawa Gymnasium (1964)


Architect: Kenzo Tange

Built about the same time as the much larger Olympic arena in Tokyo, Tange's design for the Kagawa gymnasium also features an anticlastic cable roof. The gymnasium of 4,707 m² floor features two concave concrete walls that cantilever over 20 m from four giant concrete pillars to support a cable roof of 80m span in length direction. The gymnasium evokes the metaphor of a ship








1




2



3



4



5


Olympic Roof, Munich (1972)


Architect: Guenther Behnisch, Frei Otto, consultant

Engineer: Leonhard und Andrea / Schlaich

The metaphor for this project was a spider web hovering over the landscape to minimize the bulk, usually associated with sports facilities. The prefabricated cable nets consist of 75cm square meshes, that become rhomboids to assume anticlastic curvature. To facilitate this deformation net cables consist of two strands each, joint by concentric clamps. The cable roof covers stadium, arena, and swimming pool (clockwise from left to right in the site plan below). Acrylic panels, supported by neoprene cylinders attached to the cable net, provide natural lighting for optimal TV productions. The roof over enclosed spaces has thermal insulation (foam panels between two membranes). The thermal assembly provides a translucent enclosure for natural lighting. The stadium roof is supported by a ring cable, consisting of ten 100mm strands, suspended from steel masts by guy cables that also support flying buttresses that support cable net high points. The arena roof also has flying buttresses; the swimming pool roof is suspended from an external slanted mast. Unique hardware had to be custom designed and tested, a major factor for the high cost.

- 1 Axon and section of typical stadium roof panel
- 2 Cast steel joints of stadium edge cable
- 3 Flying buttress support joint
- 4 Hinged camp connecting adjacent cable nets
- 5 Neoprene support and joint/gutter of 3/3m acrylic roof panels






Wave shapes

Recycling center project, Mil Valley, California (1971)

Architect: Neil Smith and G G Schierle

Engineer: G G Schierle

This structure was designed to expand easily in response to needed growth, using a modular system. A base module of 25x80ft (7.6x24m) is supported by 22ft (6.7m) high masts. Two half end modules provide enclosure at both ends. Only one base module with both end enclosures is shown here. For sustainable energy efficiency the membrane was designed of translucent natural canvass allowing natural daylight. Edge, ridge, and valley cables where designed as bridge rope for flexibility in adjusting to the curvatures. Membrane prestress was introduced by turnbuckle adjustment at cable ends anchored to helix ground anchors. Variable prestress was required in order for the ridge cables to remain in vertical planes as required for repeatability of the modules. The prestress levels were determined by computer analysis. Mats were designed as standard steel pipes with pin joint attachment to the foundation. The pin joints avoided bending stress for optimal efficiency; moment resistant joints would introduce bending stress in the masts under any movement.





San Diego Convention Center (1987-89)

Architect: Arthur Erickson and a joint venture team

Engineer/membrane designer : Horst Berger

The San Diego Convention Center features a linear plan of 1.7 million square feet (157,935 m²). Part of the top level is designed as outdoor exhibit space, covered with a wave-shape membrane roof. The membrane undulates between ridge and valley cables that are suspended from triangular concrete pylons. Openings at the membrane ridges provide natural ventilation. The openings are protected by secondary membranes hovering over them. Flying buttress masts supported by guy cables holding up ridge cables provide a column-free interior space. This complex support system makes the translucent fabric roof appear seemingly weightless hovering above the space, flooded in natural light. The guy cables are also suspended at both ends by triangular concrete pylons that contrast the lightweight roof with the solid conventional infrastructure. The Teflon-coated glass fiber membrane provides a fireproof enclosure, as required for permanent structures of this size.





Arch shapes

Portable classroom Detroit (1967)

Architect: G G Schierle

Engineer: Nick Forell

This portable classroom for *Educational Facilities Laboratory*, designed and built 1968 for ease of erection and transportation. The circular structure of 40 ft diameter consists of four circular aluminum arches supporting a two-layer fabric with pockets for 2 inch rigid thermal insulation. The four arches are hinge-joined to allow assembly on the ground. The structure is erected by rotating the arches in fan-like manner. Two arches are staked to the ground; the other two support the membrane and are stabilized by it. Elliptical doors and windows correspond to the respective fabric stress patterns. The PVC fabric has 600 pli tensile strength.



Theater pavilion, Armonk, NY (1968)

Architect: G G Schierle

Engineer: Nick Forell


This 80/120 ft theater pavilion was designed to be erected for occasional events, consists of two circular aluminum arches with hinge join to allow assembly on the ground. To be erected by rotating the arches about their hinge support. The fabric is attached to grade beams that are staked to the ground. The slanted aluminum arches are stabilized by the membrane, high-strength *Hypalon* fabric of 800 pli tensile strength. Elliptical door openings correspond to the respective fabric stress patterns. Within days after its first erection in winter 1968, the structure resisted unharmed snow load and wind gusts above the design load.



Tennis pavilion, Detroit (1968)

Architect: G G Schierle

This 60/120 ft tennis pavilion features side walls that are partly removable for natural ventilation. The remaining fabric has edge cables, tied to the ground by link cables. Three aluminum arches support the fabric and are stabilized by it. The arches are hinged at the base to allow erection on the ground. The translucent fabric provides diffused natural lighting. The third center arch provides the required height for unobstructed ball trajectories.







Skating rink, Munich (1983)

Architect: Kurt Ackermann

Engineer: Schlaich Bergermann

This facility, initially designed as ice skating rink was recently converted into an inline-skating facility due to the increasing popularity of this new sport. The elliptical rink of 88x67m is covered by a cable net roof, suspended from a central arch and supported along the edges by a series of steel masts with guy cables. A prismatic trussed steel arch spans 104m between concrete abutments. The arch supports the cable net and is itself stabilized by it. The cable net is suspended to the arch by means of looping edge cables along the central spine. The space between the edge cables is designed as a skylight that exposes the arch from the inside and provides natural lighting in addition to a translucent roofing membrane. The cable net of double strands has 75x75cm meshes to which a lattice grid of wood slats is attached at the joints. A translucent PVC membrane is nailed to the lattice grid. This unusual combination of materials creates a unique interior spatial quality of quite elegance, contrasting the lightness of the translucent fabric membrane with the warmth of the wood lattice grid.






Point shapes

Sea World pavilion, Vallejo, California (1994)

Architect: G G Schierle

Engineer: ASI



This conical pavilion is supported by a central steel mast and seven peripheral anchors of three steel pipes each. A loop cable and doubled fabric resists the fabric stress concentration on top. The loop cable is linked to the mast top by guy cables. Stay cables secure the mast top in case of fabric failure. The design process started with stretch fabric models exploring alternative designs. The final form and cutting patterns were defined by computer. Non-linear computer analysis also defined stress and deflection under various design loads. The conical fabric patterns were cut from fabric bands in reversed pairs to minimize waist.



Garden show pavilion Hamburg (1963)

Architect: Frei Otto




This pavilion for the international Garden Show 1961 covers an area of 29/64m and has 5.5m high masts. The point shape roof was fabricated as flat fabric without patterns. The canvass stretched enough to assume the curvature between high and low points. The high points are supported by steel masts with laminated wood springs over octagonal steel ring to avoid stress peaks. Low points are anchored to the ground to resist wind uplift and act as drainage points with rain water collector basins. Membrane edge cables are anchored to the ground by guy cables.



Ice skating rink Villars, Switzerland (1959)

Architect: Frei Otto

The sunken skating area is surrounded by spectator seating and covered by a point shape canvass membrane roof of 32x64m. The roof membrane is hang from three suspension cables that span the length of the rink with steel masts at both ends. Metal dishes distribute the membrane stress at support points. Light fixtures are suspended from the same support points. Guy cables anchor membrane edge cables to the ground.







German Pavilion, Expo'67, Montreal (1967)

Architect: Rolf Gutbrod and Frei Otto

Engineer: Fritz Leonhard

The German Pavilion at Expo'67 in Montreal was the first prize of design competition. Following the expo theme *Terre des hommes*, the objective was a man made landscape as free form roof of point shape membrane, suspended from eight high points on steel masts and low points for drainage. The membrane consisted of translucent fabric for natural lighting, suspended from a cable net of 60x60cm mesh size. Designed before computer programs became available, the structure was fabricated based on a 1:75 scale model that also served for structural testing. A full scale prototype was built to develop and test details and erection procedures. This prototype later housed the Institute of Lightweight Structures (IL). The structure was prefabricated in Germany and assembled on site. The cable net and masts were first erected. The fabric membrane was suspended from the net by means of turnbuckles and brackets, designed to allow adjustments between fabric and cable net. The cable net was fabricated as a flat orthogonal net. During erection, the square meshes deformed into rhomboids to take the anticlastic curvature. High and low points were designed with eye loop cables to transfer membrane stress to mast tops. The eye loops featured skylights for natural lighting and to emphasize the support points.





Pneumatic Structures

Pneumatic structures are flexible membranes that derive their stability from air pressure. They usually have synclastic curvature like domes, but anticlastic curvatures are possible as well. Two generic types of pneumatic structure are *air supported* (low pressure) and *air inflated* (high pressure) systems. The air pressure in inflated high pressure structures is 100 to 1000 times greater than in air supported low pressure structures.

Air supported structures typically have a single fabric layer enclosing a space in form of domes or similar shapes. The fabric is supported by inside air pressure. However, considering human comfort, air pressure can be only slightly higher than outside atmospheric pressure. The low air pressure makes air supported structures more vulnerable to flutter under wind load. Since the usable space is under air pressure, door openings must have air locks, usually in form of revolving doors to minimize loss of air pressure. Air supported structures require continuous air supply, usually with standby electric power generator to retain air pressure in case of power outage.

Air inflated structures are hermetically enclosed volumes that are inflated under high pressure much like a football to provide stability. They can have various tubular or cushion forms with high air pressure between two layers of fabric that provide usable space under normal air pressure. The air pressure ranges from 2 to 70 meters of water, yielding 2.8 to 100 pounds per square inch pressure, enough to resist gravity and lateral load. Without air pressure they would have no stability. Air inflated structures also require some continuous air supply to make up for pressure loss due to membrane leaks.

- 1 Air supported dome or vault
- 2 Air supported vault
- 3 Air supported vault with support cables
- 4 Air supported dome repetitions
- 5 Air inflated cushion
- 6 Air inflated tubular vault
- 7 Air inflated tubular dome
- 8 Air inflated cushion repetitions


US Pavilion, Expo 70, Osaka (1970)

Architect: Davis, Brody, Chermayeff, Geismar, De Harak


Engineer: David Geiger

The US Pavilion was the first large-scale pneumatic structure in 1970 with an elliptical plan of 466x272 feet (142x83 meters); yet rising only 20 feet (6 meters) from a peripheral earth berm, the structure had a very low profile. This shallow curvature was possible because the translucent roof membrane was laced to a grid of diagonal cables, spaced 20x20 feet (6x6 meter) that provided the primary support. The tension cables were supported by a concrete compression ring on top of the earth berm by means of adjustable anchor bolts. The compression ring formed a gutter to collect rain water along the periphery. Bending moments that could have been generated in the compression ring resulting of asymmetrical loads, were transferred to and resisted by the earth berm. The pavilion impressed not only by its great size but by its combination of understatement and technical innovation and refined sophistication.


- 1 Elliptical roof plan
- 2 Length section
- 3 Laced membrane to cable attachment
- 4 Concrete compression wing with gutter and adjustable cable anchors




1




2



3



4





Fuji Pavilion, Expo 70, Osaka (1970)

Architect: Yutaka Murata

Engineer: Mamoru Kawaguchi

The Fuji Pavilion housed an exhibit and light show of the Fuji corporation in a unique, organic form. Over a circular floor plan of 164 feet (50 meter) diameter, the pavilion featured a vaulted fabric structure composed of 16 pneumatic arched tubes. The tubes of 13 feet (4 meter) diameter were tied together by horizontal belts at 13 feet (4 meter) intervals. The tubes consisted of two vinyl fabric layers that were glued together for improved tear resistance. Given the circular floor plane, the arching tubes of equal length form cross sections that vary from semi-circular at the center to semi-elliptical at the entries on both opposite ends. To adjust the structure's stiffness in response to various wind pressures, the tubes were connected by pipes to a multi-stage turbo blower, that provided 1,000 to 2,500 mm water pressure.



PART V

VERTICAL SYSTEMS

Vertical structures are presented in four categories, considering primary resistance to load: shear, bending, axial, and suspended (tensile). Although most structures combine several categories, one usually dominates. For example, axially stressed braced frames may also have moment resistant joints, yet the bracing provided most strength and stiffness.


15


VERTICAL SYSTEMS General Background

Vertical structures have been a challenge since the famed tower of Babylon. Motivations to build tall structures include: a desire to reach toward heaven; to see the world from above; the prestige of being tallest, and high land costs. The tallest church tower in Ulm, Germany exemplifies the spiritual motivation. The Eiffel tower allows to see Paris from above. The towers of the Italian hill-town San Gimignano, and contemporary corporate office buildings express power and wealth; the latter are also motivated by high land cost. Traditional building materials like wood and masonry imposed height limitations overcome by new materials like steel and prestressed concrete. The Eiffel tower in Paris marks the beginning of tall steel towers. Prestressed concrete towers were pioneered 1955 by Fritz Leonhard with a television tower in Stuttgart.


Tall Structures

1	SDR television tower Stuttgart	1955	217 m	712 feet
2	Eiffel tower Paris	1889	300 m	984 feet
3	Chrysler building New York,	1930	319 m	1047 feet
4	John Hancock tower Chicago	1968	344 m	1127 feet
5	Bank of China tower Hong Kong	1988	369 m	1211 feet
6	Empire State building New York	1933	381 m	1250 feet
7	Sears tower Chicago	1974	443 m	1453 feet
8	CN tower Toronto	1976	553 m	1814 feet
9	Transmission tower Warsaw	1974	643 m	2110 feet





1




4

2



3




5



6




7



Gravity load

Gravity load is the combined live and dead load, acting vertically to generate compressive stress in supporting columns or walls. At every level they carry the combined loads from above. Since load accumulates from top down, members at the top carry the least, those at the bottom carry the most. Steel structures usually have the same nominal column size but of increasing unit weight, resulting in thin columns at top and bulky ones at ground level. For example W14 wide flange columns come in many weights from 43 to 730 plf (64 to 1,086 kg/m) with capacities of 272 to 4,644k (1,210 to 20,656 kN). It is also possible to use higher strength steel at lower floors. However, increase in steel strength does not yield higher stiffness since the modulus of elasticity of steel is constant regardless of strength. For concrete structures it is possible to increase concrete strength and stiffness, or to increase the cross sectional area. If a mechanical room is on the top floor it is possible to balance the decreasing need for duct sizes from top down, with need for increasing column sizes from top to bottom. Eero Saarinen designed the CBS tower New York with such a strategy but was only partly consistent since the lower floors are served from a mechanical room on the second floor.


- 1 structure with increasing column size as load increases from top down
- 2 Light-weight wide-flange column
- 3 Heavy weight wide-flange column of equal nominal size as in 2 above
- 4 Increasing column size dovetails with reducing duct size from top down
- 5 Small column cross section and large duct size on top column
- 6 Large column cross section and small duct size on lower floor column
- 7 Large column on ground level where no duct space is needed



Lateral load

The effect of lateral load on tall structures is similar to gravity load on cantilevers, such as balconies. Tall structures act like cantilevers projecting from the ground. Lateral load generates shear and bending that may be presented in respective shear and bending diagrams as in a cantilever beam. Yet there are important differences. The shear and bending diagrams for buildings are usually *global*, for the entire system rather than for individual elements like beams. For example, global bending (overturn moment) causes axial tension and compression in columns, and local shear and bending in beams. Further, lateral wind and seismic loads are non-uniform. Wind force increases with height due to higher wind speed and reduced friction. Seismic forces increase with height in proportion to increasing acceleration (acceleration increases with height due to increased drift). However, shear increases from top to bottom since the structure at each floor must resist not only the force at that floor but the forces from all floors above as well. The non-uniform wind and seismic loads cause nonlinear shear distribution.

- 1 Cantilever beam with shear and bending deformation
 - 2 Tall building with shear and bending deformation
 - 3 Shear and bending diagrams for uniform load on a cantilever beam
 - 4 Shear and bending diagrams for idealized uniform load on a building
 - 5 Vertical distribution of wind force, shear, and bending diagrams
 - 6 Vertical distribution of seismic force, shear, and bending diagrams
- A Load/force diagram
 B Shear deformation
 C Bending deformation
 D Shear diagram
 E Moment diagram



Lateral resistance

Lateral loads may be resisted by shear walls, cantilevers, moment frames, braced frames, or combinations thereof. The choice of a suitable system depends on structural and architectural objectives. Shear walls and braced frames are strong and stiff, cantilevers and moment frames are more ductile, to dissipate seismic energy. Shear walls are good for apartments or hotels that require party-walls between units. Moment frames offer better planning flexibility required for office buildings with changing tenant needs.


Shear walls resist lateral load primarily through in-plane shear. They may be of reinforced concrete or masonry, or, for low-rise, of wood studs with plywood or particle board sheathing. Short shear walls tend to overturn and must be stabilized by dead load or tie-downs.

Cantilevers are slender elements that resist load primarily in bending. Pole houses are cantilevers; but more commonly, cantilevers are of reinforced concrete or masonry, anchored to foundations, wide enough to resist overturn. Overturn causes compression on one side and tension on the other. Compression acts in addition to gravity, tension may be partly offset by gravity compression. In tall cantilevers, tension due to lateral load may be greater than gravity compression, resulting in net tension.


Moment frames consist of posts and beams connected by moment resistant joints. They may be of steel or reinforced concrete. To resist seismic load, concrete should have ductile reinforcement that yields before brittle concrete failure. Ductile design results in greater concrete members with less reinforcing steel.

Braced frames may have diagonal-, A-, X-, or V-braces. The best bracing scheme depends on structural and architectural considerations. K-bracing tends to buckle columns and must not be used. X-bracing allows no doors and requires more joints for greater cost; but X-bracing can be of tension rods to eliminate buckling. A- and V-braces are shorter than single diagonals and result in reduced buckling. (however, beams must be designed for the full span since bracing may adversely affect the beam load). Braced frames are usually of steel but may be of reinforced concrete or wood (for low-rise).


- 1 Long shear wall resists in-plane load in shear primarily
- 2 Shear wall supports adjacent bays (slender walls tend to overturn)
- 3 Cantilever resists lateral load primarily in bending
- 4 Cantilever supporting adjacent bays
- 5 Moment frame requires moment resisting beam-column joints to resist lateral load by beam-column interaction
- 6 Moment frames at both ends support intermittent bays
- 7 Braced frame with diagonal bracing
- 8 braced center core supports adjacent bays




1




2



3



4




5

Braced /moment frame

Combined braced/moment frames are used to reduce drift under lateral load. Moment frames have the greatest drift at the building base, but braced frames have the greatest drift on top. Combining the two systems reduces drift at both base and top. The objectives to reduce drift are:

- To prevent occupant discomfort
- To reduce the risk of failure of cladding and curtain walls
- To reduce secondary stress caused by $P-\Delta$ effects
(the $P-\Delta$ effect generates bending moments caused by column gravity load P and the lateral drift Δ as lever arm)

- 1 Bending resistance of moment frame portal under lateral load
- 2 Axial resistance of braced frame portal under lateral load
- 3 Lateral drift of moment frame is maximum at base
- 4 Lateral drift of braced frame is maximum on top
- 5 Reduced drift of combined braced/moment frame




Structure systems

The vertical-lateral framing systems of wall, cantilever, braced frame, and moment resisting frame, shown from left to right, may be optimized for height and use, including combinations of systems. The importance to select an efficient system increases with building height in order to achieve a low weight per floor area ratio for the structure. The late engineer Fazlur Kahn of Skidmore Owings and Merrill recommended the following systems for various heights:


Concrete moment resisting frame	20 stories
Steel moment resisting frame	30 stories
Concrete shear wall	35 stories
Braced moment resisting frame	40 stories
Belt truss	60 stories
Framed concrete tube	60 stories
Framed steel tube	80 stories
Braced tube	100 stories
Bundled tube	110 stories
Truss tube without interior columns	120 stories

- 1 Cellular shear walls
- 2 Exterior shear walls
- 3 Curved shear walls
- 4 Cantilever core with cantilever floors
- 5 Cantilever round core with cantilever floors
- 6 Cantilever core with suspended floors
- 7 Moment resistant frame
- 8 Moment frame with two shear cores
- 9 Moment frame with single shear core
- 10 Braced core
- 11 Braced exterior bays
- 12 Braced core with outrigger trusses


1




2



3



4






Tubular systems incorporate lateral resistance into the skin by either some form of bracing or narrowly spaced columns with moment resisting beam-column connections. For very tall buildings, bundled tubes increase lateral resistance with interior cell “walls” to reduce shear lag between exterior skin bracing. The Sears tower in Chicago has a framed bundled tube structure.

- 1 Framed tube
- 2 Braced tube
- 3 Bundled tube, framed
- 4 Bundled tube, braced

Structure systems vs. height

The diagram is based on a study by the late Fazlur Kahn regarding optimal structure system for buildings of various heights, defined by number of stories.






Structure weights

The amount of structural steel required per floor area is a common measure of efficiency for steel structures. Comparing various systems demonstrates the importance of selecting a suitable system. As shown in the diagram, considering gravity load alone, the structural weight would increase only slightly with height. The effect of lateral load, however, accelerates the increase dramatically and at a non-linear rate.


- 1 Structural steel weight related to building height (by Fazlur Kahn)
- 2 Weight of structural steel per floor area of actual buildings

- A Number of stories
- B Weight of structural steel in psf (pounds per square foot)
- C Weight of structural steel in N/m^2
- D Weight of structural steel considering floor framing only
- E Weight of structural steel considering gravity load only
- F Weight of structural steel for total structure optimized
- G Weight of structural steel for total structure not optimized


- H Empire State building New York
- I Chrysler building New York
- J World Trade center New York
- K Sears tower Chicago
- L Pan Am building New York
- M United Nations building New York
- N US Steel building Pittsburgh
- O John Hancock building Chicago
- P First Interstate building Los Angeles
- Q Seagram building New York
- R Alcoa building Pittsburgh
- S Alcoa building San Francisco
- T Bechtel building San Francisco
- U Burlington House New York
- V IDS Center Minneapolis
- W Koenig residence Los Angeles




1




4




7




2




5




8



3



6



9

Beam-column interface

The type of interface between spandrel beam and column on a facade is important considering architectural and structural implications. Assuming moment resisting connections, the best structural solution is to frame the beam directly into the column for effective moment transfer without torsion. If shown on the facade, this expresses most clearly a moment resisting frame. Beams may run behind the column to express verticality, or in front of the column to express horizontally; yet both cases generate torsion in the beam and bending in the column due to eccentricity.







- 1 Visual expression of frame
- 2 Axon of beam framed directly into column
- 3 Section of beam framed directly into column
- 4 Visual expression of columns
- 5 Axon of beam running behind column
- 6 Section of beam running behind column yielding a moment couple
- 7 Visual expression of beam
- 8 Axon of beam running in front of column
- 9 Section of beam running in front of column yielding a moment couple

17

VERTICAL SYSTEMS

Bending Resistant

Bending resistant structures include cantilever, moment frame, framed tube, and bundled tube structures. They resist lateral load by combined axial and bending stresses. Since bending stress varies from tension to compression with zero stress at the neutral axis, only half the cross section is effectively engaged. This makes them less stiff than shear walls or braced frames, but it provides greater ductility to absorb seismic energy in the elastic range, much like a flower in the wind. On the other hand, bending resistance implies large deformations that may cause damage to non-structural items. Bending resistant structures are sometimes combined with other systems, such as braced frames or shear walls, for greater stiffness under moderate load; but moment frames provide ductility under severe load, after the bracing or shear walls may fail.




Cantilever

Cantilever structures consist of towers that rise from the foundation. They resist gravity load in compression and lateral load in bending and shear, similar to moment frames. Cantilevers are subject to global bending of the entire tower, whereas moment frames are subject to localized bending of columns and beams joint by moment resistant joints. The global bending of cantilever towers increases from minimum on top to maximum at the base; whereas the local bending of beams and columns in moment frames varies at each level from positive to negative.

Cantilever towers may be very slender walls, hollow boxes, or solid columns. But compared to shear walls which resist lateral load primarily in shear, cantilevers resist primarily in bending. The most common materials are reinforced concrete and wood poles of pole houses. Floors may also cantilever from the towers. Cantilevers need large foundations to resist overturn moments. Cantilever systems of multiple towers may have joint foundations that tie the towers together for better stability.

- 1 Single tower cantilever with cantilever floors
- 2 Single tower cantilever under lateral load
- 3 Twin tower cantilever with joined footing for improved stability
- 4 Twin tower cantilever under lateral load
- 5 Single tower cantilever with suspended floors
- 6 Single tower suspension cantilever under lateral load



Pirelli tower, Milan (1956-58)

Architect: Ponti, Fornaroli, Rosselli, Valtolina, Dell'Orto

Engineer: Arturo Danusso, Pier Luigi Nervi

Facing Milan's central station across a major urban plaza, the 32-story Pirelli tower rises prominently above the surrounding cityscape. A central corridor, giving access to offices, narrows toward both ends in response to reduced traffic. The reinforced concrete structure features two twin towers in the midsection for lateral resistance in width direction and triangular tubes at both ends for bilateral resistance. The towers and tubes also support gravity load. The gravity load of the towers improves their lateral stability against overturning. The central towers are tapered from top to base, reflecting the increasing global moment and gravity load. The towers are connected across the central corridors at each level by strong beams that tie them together for increased stability. In plan, the central towers are fan-shaped to improve buckling and bending resistance. The tubular end towers of triangular plan house exit stairs, service elevators, and ducts. Concrete rib slabs supported by beams that span between the towers provide column-free office space of 79 and 43 ft (24 and 13 m). The plan and structure give the tower its unique appearance, a powerful synergy of form and structure.

Floor plan:	18 x 68 m (59 x 223 ft)
Height:	127 m (417 ft)
Typical story height:	3.9 m (12.8 feet)
Height/width ratio	7

Hypo Bank, Munich (1980)


Architect: Bea and Walter Betz



The design objective for the Hypo Bank headquarter was to create a landmark for Munich and a unique architectural statement for the bank. Built 1980, the 22 story bank has 114m height. The structure consist of four tubular concrete towers that support a platform which supports 15 floors above and 6 floors suspended below. The suspended floors had been built from top down simultaneous with upper floors being built upwards. Four towers combined with a platform form a mega-frame to resist gravity and lateral loads. The four towers include exit stairs in prestressed concrete tubes of 7m diameter and 50 to 60 cm wall thickness. A fifth tower of 12.5m diameter, houses eight elevators and mechanical equipment. The support platform consist of prestressed site-cast concrete of 50cm thick concrete slabs on top and bottom, joined by 1.5m rib walls that are tied around the towers. The formwork for the platform was assembled on ground and lifted 45 m by 12 hydraulic jacks.

The office space consists of three triangular units, joined by a T-shaped center. Two-way beams for office floors are supported by columns above the platform and suspended below. Three sub-grade levels include parking, security control, and loading stations.



Floor plan:	7 m (23 ft) diameter towers
Height:	114 m (374 ft)
Height/width ratio	16 per tower

- 1 Typical upper floor supported by columns above the platform
- 2 Story-high platform forms a mega frame with four towers
- 3 Typical lower floor suspended from the platform
- 4 Isometric view of building
- 5 Roof plan
- 6 Typical office floor framing
- 7 Support platform framing
- 8 Typical floor plan layout





1



2

1 Commerzbank Düsseldorf (1965)

Architect: Paul Schneider-Esleben

This 12-story bank building is located at the boundaries between the old and new banking district of Düsseldorf, linked by a pedestrian footbridge to an older building of the bank. The 12-story building above a 2-story podium was initially designed to allow a drive-in bank at street level. A free-standing service core supports the pedestrian bridge and makes the link to the office floors. A second stair and bathroom core is located at the far end of the building, providing undivided and flexible office space. The curtain wall façade is designed and manufactured using vehicular technology of insulating sandwich panels. The structure consists of reinforced concrete. Two rows of square cantilever columns support cantilever beams and concrete floor slabs. The interior core helps to resist lateral load in length and width directions, but the exterior core at the other end of the building resist lateral load in width direction only.


Floor plan: 16 x 32 m (52 x 104 ft)
 Height: 44 m (144 ft)
 Typical story height 3 m (9.8 ft)
 Height/width ratio 10 per cantilever

2 Lend Lease House Sydney (1961)

Architect: Harry Seidler

This 15-story office tower with north-south orientation of its length axis has movable exterior blinds for sun control. They give the facade an ever-changing appearance. On sunny mid-days, they are horizontal for optimal sun protection. On cloudy days, in lowered position, they tend to darken the inside rooms. The orientation provides inspiring views to the Sydney harbor and a nearby botanical garden. A two-story showroom with mezzanine floor is located on the ground floor, above a four-story underground parking garage. The office floors feature elevators, stair and bathrooms on one end and an exit stair at the opposite end, providing flexible office floors. Mechanical equipment is in a roof penthouse. The structure consists of reinforced concrete. Two rows of wall-shape cantilever columns support cantilever slabs. The cantilever columns resist both gravity and lateral loads.

Floor plan: 12 x 30 m (39 x 98 ft)
 Height: 38 m (125 ft)
 Height/width ratio 4.7 per twin cantilever







Moment frame

Moment frames consist of one or more portals with columns joint to beams by moment resistant connections that transmit bending deformation from columns to beam and vice-versa. Beams and columns act together to resist gravity and lateral loads in synergy and redundancy. Bending resistance makes moment frames more ductile and flexible than braced frames or shear walls. The ductile behavior is good to absorb seismic energy, but increases lateral drift, a challenge for safety and comfort of occupants, and possible equipment damage.

Moment frames provide optimal planning freedom, with minimal interference of structure. Office buildings that require adaptable space for changing tenant needs, usually use moment frames. To reduce lateral drift in tall buildings, dual systems may include bracing or shear walls, usually at an interior core where planning flexibility is not required. Given the high cost of moment-resistant joints, low-rise buildings may provide only some bays with moment resistant frames. The remaining bays, with pin joints only, carry gravity load and are laterally supported by adjacent moment frames.

Moment frame behavior can be visualized by amplified deformations. The connection of column to beam is usually perpendicular and assumed to remain so after deformation. Under lateral load, columns with moment joints at both ends assume positive and negative bending at opposite ends, causing S-shapes with inflection points of zero bending at mid-span and end rotation that rotates the ends of a connected beam. By resisting rotation, beams help to resist lateral load. Similarly, a beam subject to bending under gravity load will rotate the columns connected to it and thus engage them in resisting the gravity load. Columns with moment-resistant joints at both ends deform less than columns with only one moment joint. Deformations under gravity and lateral loads are visualized in the diagrams, with dots showing inflection points of zero bending stress.

- 1 portal with hinged joints unable to resist lateral load
 - 2 Moment joints at base, hinge joints at beam, large drift
 - 3 Moment joints at strong beam, hinge joints at base, large drift
 - 4 Moment joints at base and strong beam, drift reduced to half
 - 5 Hinged base, moment joints at beam, beam forms inflection point
 - 6 Gravity load, hinged base, beam moment joints, 2 beam inflection points
 - 7 Lateral load, all moment joints, inflection points at beam and columns
 - 8 Gravity load, all moment joints, inflection points at beam and columns
 - 9 Multi-bay frame deformation under lateral load
 - 10 Multi-bay frame deformation under gravity load
- A Inflection point of zero bending stress





Moment-resistant Joints

Moment-resisting joints usually consist of steel or concrete. They join members (usually column to beam) to transfer bending moments and rotations of one member to the other. The moment resistant connection makes post and beam act in unison to resist both gravity and lateral loads. In seismic regions, moment frames must be ductile to absorb seismic energy without breaking.

Steel moment joints are usually wide-flange beams connected to wide-flange columns. Generally, post and beam are joint about their strong axis. Semi-rigid joints connect the strong beam axis to the weak column axis. Moment resistant joints require stiffener plates welded between column flanges. They resist bending stress of beam flanges that tend to bend column flanges without stiffener plates. Compact columns with very thick flanges do not require such stiffener plates. Steel is a ductile material which is good to absorb seismic energy in the elastic range. Yet the seismic performance of steel joints was challenged by failures during the 1994 Northridge Earthquake. The failure resulted primarily from joint welds. Research developed solutions for moment-resisting steel joints, notably *dog-bone* beam ends to form plastic hinges to reduce stress at the joints.

Concrete frames achieve ductile joints by proper steel reinforcing, designed to yield before the concrete crushes in brittle mode. Usually that implies 25% to 50% less steel and more concrete than used for balanced design (balanced design has just enough reinforcing to balance the concrete strength). Ductile design also requires: closely spaced tie bars near beam/column joints; column rebars to extend through beams; beam rebars to extend through columns; and column ties to continue through beams.

- 1 Moment-resisting steel joint at end column
 - 2 Moment-resisting steel joint at interior column
 - 3 Moment-resisting concrete joint at end column
 - 4 Moment-resisting concrete joint at interior column
- A Steel wide-flange column
 - B Steel wide-flange beam
 - C Stiffener plates resist bending stress of beam flanges
 - D Steel bar, welded to column in shop and bolted to beam in field
 - E Weld, joining beam flange to column
 - F Steel reinforcing bars in concrete beam
 - G Steel ties to restrain reinforcing bars from buckling
 - H Column reinforcing bars to resist compression and bending



Steel framing



Steel framing with wide-flange profiles requires careful orientation of columns in order to achieve proper strength and stiffness to resist lateral load in both orthogonal directions. Measured by the moment of inertia, typical wide-flange columns have a stiffness ratio of about a 3:1 about the x and y-axis, respectively, yet some deep sections have stiffness ratios up to 50:1, about strong to weak axes. Therefore, column orientation for lateral resistance is an important design consideration for moment frames. Assuming equal lateral load and column size, half of the columns should be oriented in either direction. For unequal loads, column orientations should provide strength proportional to loads. For example a rectangular building has more wind load on the long than on the short facade. If wind governs lateral design, this should be considered in column orientation. Further, column orientation should provide symmetry of stiffness in both directions to prevent torsion. Torsion would occur for example if one end of a building has columns with greater stiffness than the other end. Also to better resist possible torsion from asymmetric mass distribution, columns should be placed near or at the building edge, rather than near the center of mass where they have no effective lever arm to resist torsion. Column size should also account for setbacks on upper floors, to account for asymmetric wind or seismic load resulting from such setbacks.

- 1 Front view of moment resisting frame with setback floors on top
- 2 Column layout in plan for moment resistance in both direction
- A Column oriented for lateral support in width direction
- B Column oriented for lateral support in length direction

Casa Terragni, Como, Italy (1936)

Architect: Giuseppe Terragni


With 33.2x33.2x16.6m height, the building is a perfect half cube. The plan is organized around a central atrium, surrounded by circulation. Terragni used the concrete moment frame as organizing grid in a liberal manner, modified as required to meet planning needs: the 4.75m grid is reduced for circulation and increased for large spaces. Beams of variable depth express the respective spans. The front facade is recessed behind a veranda to emphasize the frame. Moment frames with shear walls have proven a failsafe solution in earthquakes prone areas: shear walls provide good stiffness under moderate load, and the moment frame provides ductility if shear walls fail in sever earthquakes.




Commonwealth (formerly Equitable) Building (1947-48)

Architect: Pietro Belluschi

The Equitable Building 1948 pioneered the clear expression of a steel moment frame, a model for many subsequent buildings. With this building Beluschi also pioneered the first double glazed aluminum curtain wall of simple elegance.. The building is a National Historic Landmark of mechanical engineering because it was the first building using heat pumps for efficient air conditioning.. It was the first skyscraper to use double-paned glass. The first building with air conditioning, completely sealed The first to use a flush curtain wall design. The first to be clad completely in aluminum. In 1982 the American Institute of Architects awarded it the building its 25 year award. The building is a compelling testimony of Beluschi's philosophy of simplicity.





Seagram building, New York (1954-58)


Architect: Mies van der Rohe, Philip Johnson, Kahn and Jakobs

Engineer: Severud, Elstad, Krueger

The 38-story Seagram building is a classic icon of modern architecture. It was the result of unique cooperation between the client, Samuel Bronford, his daughter, Phyllis Lambert as planning director, and the architects. The building exemplifies Mies' philosophy of *Baukunst* (art and craft of building), with great attention to detail and proportion. The structure, based on a 28 ft (8.5 m) module, is expressed as colonnade at the base to signal the entrance. The skin of the mechanical floor on top provides a visual cap. Most of the structure is concealed behind the curtain wall which eliminates thermal stress and strain due to outside temperature variations, an important factor in tall structures. The recessed rear gives the tower its classic proportions of five to three for front and side, respectively. The steel moment frame structure is embedded in concrete for fire protection and added stiffness. The core walls have diagonal bracing up to the 29th floor for additional wind bracing. Concrete shear walls up to the 17th floor provide additional stiffness.

Floor plan:	84 x 140 feet (26 x 43 m) without extrusion
Height:	525 feet (160m)
Typical story height:	13.6 feet (4.15m)
Height/width ratio	6.3 without extrusion

- 1 Axon view of tower
- 2 Corner detail of structure and skin
- 3 Typical plan with recessed corners to express 3 to 5 proportion
- A Air conditioning duct as parapet
- B Glare reducing pink glass appears without color from inside
- C Bronze cover of steel column embedded in concrete



Crown Zellerbach building, San Francisco (1959)

Architect: SOM and Hertzka and Knowles

Engineer: H. J. Brunnier

The 20-story Crown Zellerbach headquarters building covers about one third of a triangular site on Market Street, the main street of San Francisco. The building features a large office wing flanked by an external core for stairs, elevators, bathrooms, and mechanical ducts. The exterior core gives the office wing a column-free floor area for optimal space planning flexibility. A planning module of 5.5 feet (1.6 m) provided for good size office spaces.

The structure is a moment resistant steel frame with wide-flange girders spanning 63 feet (19 m) across the width of the building, supported by wide-flange columns, spaced 22 feet (6.7 m) on center. Spandrel beams connect the columns in the longitudinal direction. Steel joists, spaced 7 feet (2.1 m), support concrete slabs on cellular metal decks. The joists cantilever at each end of the building. All columns are oriented with their strong axis to provide moment resistance in the width direction, giving the building much greater strength and stiffness in width than in length direction. Since the building is much longer than wide, the column orientation is good for wind load which is greater on the long faced; but it is less effective for seismic load which is greater in length direction. Also the eccentric service tower causes seismic torsion. The fire exits on both side of the service tower are too close together for fire safety and would not be allowed by current code. The building is supported by a mat foundation, 8 feet (2.4 m) deep, extending the full width and length of the building. The foundation rests on firm soil 45 feet (13.7 m) below grade under a 2-story parking garage. The steel structure is protected by fire proofing that consists of stucco applied to metal lath wrapped around beams and columns.


Floor plan: 201x69 ft (61x21m) without exterior core

Height: 320 ft (96m)

Typical story height: 13.67 ft (4m)

Height/width ratio 4.6 without exterior core

- A Column spaced 22ft (6.7 m)
- B Spandrel beam
- C Girder spanning the full width of the building
- D Joist spaced 7ft (2.1 m)
- E Stiffener plate for moment connection
- F Fire proofing on metal lath




Thyssen tower, Düsseldorf (1957-60)

Architect: Hentrich and Petchnigg

Engineer: Kuno Boll

The Thyssen tower's unique plan of three slabs is a composition with efficient circulation and good daylighting for all offices that are never more than 7m (23 ft) from a window. The floor area of offices is 62,7% of the gross floor area. Located at the center of town, the long axis is oriented north-south with a park to the North. The central block includes the service core and, as tallest block, houses mechanical and elevator equipment in the top floors of this 25-story tower. Parking for 280 cars is in the underground garage, rapped around the building. The long facades feature glass curtain walls; the narrow end facades are clad in stainless steel. The steel frame structure is embedded in concrete for fire protection and to provide additional stiffness. The columns consist of steel pipes produced by the building owner. The structural module is 7x4.2 m (23x14 ft), with some variation between central and outer slabs. Braced end walls provide some additional stiffness to resist wind load on the long building sides. The exterior composition of the building, expressing the internal organization, has earned the nickname "Drei-Scheiben Haus" (Three-slab-house). The pristine design, combining American know-how with European sophistication stands as an icon of the modern movement in Europe.




Floor plan:	21x80 m (70x226 feet)
Height:	94 m (308 feet)
Typical story height:	12.2 feet (3.7 m)
Height/width ratio	4.48



Framed Tube

Framed tubes are a variation of moment frames, wrapping the building with a “wall” of closely spaced columns and short spandrel beams. To place the lateral resistance system on the façade rather than at the interior gives it a broader base for greater stability as well as improved rotational resistance. In addition, the lateral resisting system on the façade allows smaller columns on the interior to carry gravity load only. Further, designing floors and roof to span the full width of a building can make the interior completely column free for optimal flexibility. A major challenge of framed tubes is the high cost of numerous moment resistant joints between closely spaced columns and beams. To minimize this adverse cost factor, designers often use prefab methods to weld the joints in the fabrication hop rather than on the job site. This process also improves quality control and reliability.

- 1 Framed tube without interior core
 - 2 Framed tube with interior core
 - 3 Global stress diagram of framed tube
 - 4 Framed tube with belt and top truss for additional stiffness
 - 5 Prefab frame with joints located at beam inflection point of zero bending
 - 6 Prefab element ready for assembly
- A Reduced shear resistance (shear lag) at hollow interior
 - B Peak axial force from overturn moment
 - C Pin joint at inflection point of zero beam bending stress



CBS Tower New York (1961-650





Architect: Eero Saarinen

Engineer: Paul Weidlinger

The 38-story CBS tower is a stark vertical extrusion of the rectangular floor plan. Columns forming a framed tube are expressed as triangular extrusions on the upper floors and diamond shaped on the ground floor. The triangular columns include niches for mechanical ducts and pipes. The niches decrease from top to bottom with the decreasing duct sizes that run down from the mechanical room on the top floor. The decreasing niches result in increasing net column size that coincides with increasing load as it accumulates from top down. Concrete floors span between the walls of a central core and the framed tube, providing a column-free donut-shape floor space for flexible use. The four sides facing the core feature one-way rib slabs, but the four corners have two-way waffle slabs, designed to make the transition from one direction to the other. Glazed in black granite the closely spaced triangular columns express a stark verticality, perforated with regular windows on all but the top and ground floors. The top mechanical floor has ventilation louvers instead of windows, the ground floors have taller windows and doors. The articulation of top and bottom of the façade emphasizes the most prominent part of the building, a strategy often use for the design of tall buildings.

Floor plan:	155x125 feet (47x38m)
Height:	494 feet (151m)
Typical story height:	12 feet (3.66m)
Floor-to-ceiling height:	8.75 feet (2.67m)
Height/width ratio	3.9

- A Column profile at top floor
- B Column profile at lower floors
- C Column profile at ground floor



World Trade Center, New York (1977

(demolished by terrorists 9-11-2001)

Architect: Minoru Yamasaki and E. Roth

Engineer: Skilling, Helle, Jackson, Robertson





The World Trade center of two 110-story towers and related smaller structures housed 50,000 employees and up to 80,000 visitors daily. Both towers, in diagonal juxtaposition, were vertical extrusions of square plans, with very closely spaced steel columns. Each tower had two-story mechanical spaces on top, near the bottom, and two distributed at 1/3 intervals, with elevator sky-lobbies two floors above each. Each tower had 100 passenger and four service elevators. Each sky-lobby was reached by 11 or 12 elevators from ground floor; with five express elevators non-stop to the 107th and 110th floors. Since elevators are stacked, 56 shafts needed, take 13% floor area on each floor. The framed tube structure consisted of 56 box steel columns on each façade, joint at each floor by spandrel beams with moment resistant connections. This giant Vierendeel frame was assembled from prefab elements of three two-story columns with beam and column joints at mid-span and mid-height where inflection points of zero bending occur under lateral load. Combined with rigid floor diaphragms, the towers formed torsion-resistant framed tubes that cantilever from a five-story underground structure that houses train and subway stations as well as parking for 2,000 cars. Although the framed tube column's overall dimensions are constant, their wall thickness increases from top to bottom in response to increasing loads. Floor truss joists span from the framed tube to columns around the central core. Mechanical ducts run between truss joists for reduced story height. The core columns are designed to carry gravity load only. The framed tube resisted both lateral and gravity load.

Floor plan (square):	208x208 feet (63.4x63.4 m)
Height:	1361 feet (415m)
Typical story height:	12 feet (3.66m)
Floor-to-ceiling height	8.6 feet (2.62m)
Height/width ratio	6.5






- 1 Axon of tower
- 2 Typical floor framing plan
- 3 Typical prefab two-story façade assembly
- 4 Typical framed tube column size and spacing







1




2



3



4




5

Bundled Tube


Bundled tube structures are composed of tubes framed by closely spaced columns joined to beams to form moment frames. The bundled tubes resulting from the rows of columns add lateral resistance to the structure, transferring shear between exterior columns subject to tension and compression under lateral load. This shear transfer makes it possible for the exterior columns to act in synergetic unison, whereas independent columns would act alone to provide much less lateral resistance. Bundled tubes transfer shear not only through exterior frame "walls" but also through interior cell "walls." To reduce shear lag.

An alternative to framed bundled tube are braced bundled tube systems. However, though they provide greater stiffness, the braces disrupt spatial flow between interior columns. Regarding plan geometry, bundled tubes may have bundles of square, rectangular, or triangular polygons that are repeatable. However, hexagonal polygons would be less efficient


- 1 Square tube modules
 - 2 Triangular tube modules
 - 3 Hexagonal tubes would be less effective to reduce shear lag
 - 4 Framed tube shear lag
 - 5 Bundled tube with reduced shear lag
- A Shear lag between connecting shear walls
 - B Peak resistance at shear wall




1



2




3




4




5




6



7



8



9

Sears tower, Chicago (1973)

Architect/ Engineer: Skidmore, Owings and Merrill

With 110 stories, the Sears Tower was the tallest building in the world for many years and occupies an entire city block on the southwest of Chicago's loop. The tower starts at ground level with nine square modules of 75 feet (22.9m) each. The nine modules gradually reduce to a twin module on top in response to needed office space and also to reduce wind resistance and overturn moments. The large areas of the lower floors are occupied by Sears, the smaller floors at higher levels serve smaller rental needs. Elevators serve the building in three zones of 30 to 40 stories separated by sky-lobbies that are reached by double deck elevators express elevators. The building façade is clad in black aluminum and tinted glass. The structure is anchored to a five-story underground structure. Nine bundled tubes are separated by rows of columns, spaced 15 feet (4.6m) on center. The columns, welded to beams, form moment resisting portals to transfer global shear under lateral load from compressed to tensed side of the structure, to reduce lateral drift. This shear transfer between exterior walls reduces "shear lag" and gives the bundled tube greater strength and stiffness to resist lateral loads. The bundled tube concept conceived facilitates the setbacks as the floors get smaller toward the top. Belt trusses at three levels in conjunction with mechanical floors reduce lateral deflection by about 15 percent and help distribute uneven gravity load caused by floor setbacks. The horizontal floor framing consists of trusses that span 75 feet (23m) between columns and support concrete slabs on metal deck. The one-way floor trusses of 40 inch (1m) depth change direction every 6th floor to redistribute the gravity load to all columns. Trusses consist of top and bottom T-bars, connected by twin angle web bars. They allow mechanical ducts between top and bottom chords. The small truss depth was possible, using composite action; shear studs engage the concrete slab in compression for increased resistance.

Floor plan at ground:	225 x 225 feet (69 x 69m)
Height:	1,450 feet (442m)
Typical story height:	13 feet (3.96m)
Height/width ratio	6.4


- 1 Tower axon
- 2 Base floor plan
- 3 Floor framing
- 4 Stress diagram of single framed tube with shear lag between walls
- 5 Stress diagram of bundled tube with reduced shear lag
- 6 Floor plan at ground floor
- 7 Floor plan starting at 51st floor
- 8 Floor plan starting at 66th floor
- 9 Floor plan of top floors

19


Vertical Systems Suspended

Vertical systems, suspended, also referred to as **suspended high-rise** structures, are different from suspension structures like suspension bridges, which are draped from two suspension points; suspended high-rise structures hang usually about vertically from top. A rational for suspended high-rise structures is to free the ground floor from obstructions. Other architectural and structural reasons are described on the next page.


Regarding Lateral load, the challenge of suspended high-rise is usually a narrow footprint and slender aspect ratio. Thus their behavior is comparable to a tree, where the trunk resists load primarily in bending and large roots are required to resist overturning. Properly designed, the narrow aspect ratio can enhance ductility to make the structure behave like a flower in the wind to reduce seismic forces.




1



2



3



4

Suspension rational

At first glance suspended high-rise structures seem irrational, given the load-path detour: gravity load travels to the top and then down to the foundation. However, as described below, there are advantage, both architectural and structural, that justify this detour. Understanding the pros and cons and their careful evaluation are essential for design.

Challenges

- Load path detour: load travels up to the top, then down to foundation
- Combined hanger / column deflection yields large differential deflection

Architectural rational

- Less columns at ground floor provides planning flexibility and unobstructed view
- Facilitates top down future expansion with less operation interference
- Small hangers instead of large columns improve flexibility and view


Structural rational

- Eliminates buckling in hangers, replacing compression with tension
- High-strength hangers replace large compression columns
- Floors may be built on ground and raised after completion
- Concentration of compression to a few large columns minimizes buckling


Design options

- Multiple towers with joint footing to improve overturning resistance
- Multiple stacks to limit differential deflection
- Adjust hangers for DL and partial LL to reduce deflection
- Prestress hangers to reduce deflection to half


- 1 Gravity load path
Load travels to top, then down to foundation
- 2 Differential deflection is cumulative
Shortening of columns and elongation of hangers are additive
- 3 Prestress can reduce deflection to half
Top resists half the load through increase of prestress
Bottom resists half the load through decrease of prestress
- 4 Ground anchors for improved stability
(assuming hangers as ground anchors are ok)




1




2




3



4



5



6

Design options

Suspended high-rise structures may be designed in various configurations with distinct limitations and implications regarding behavior. The following description provides guidelines for rational design, starting with the introduction of a terminology, followed by implications of various design options:


- Single towers (one vertical support)
- Multiple towers (several vertical supports)
- Single stacks (one set of floors)
- Multiple stacks (several sets of floors)

The effect of these options are described and illustrated as follows:

- 1 Single tower / single stack
Single towers require large footing like a tree to resist overturning
- 2 Multi towers
Multiple towers with joint footing increase stability
- 3 Twin stacks
Twin stacks reduce the length of hangers and thus differential deflection
Max. ten stories per stack limits differential deflection to < 2 inch (50 mm)
- 4 Twin stacks / towers
Twin stacks reduce the length of hangers and thus differential deflection
Twin towers with joint footing increase stability
- 5 Triple stacks
Three or more stacks limit hanger length and thus differential deflection
- 6 Triple stacks / twin towers
Three or more stacks limit hanger length and thus differential deflection
Two or more towers with joint footing increase stability

Limits

An important limit for suspended high-rise structures are the limited number of floors per stack. More than ten floors per stack would cause unacceptable differential deflections. Conventional columns in compression are subject to about equal strain under load. Suspended high-rise structures are subject to greater differential deflection since hangers elongate but columns shorten under gravity load. Without buckling, the high tensile stress of hangers causes greater strain which further increases differential deflection.



Case studies

Westcoast Transmission Tower, Vancouver (1969)


Architect: Rhone and Iredale

Engineer: Bogue Babicki

The 12-story tower, initially designed and built as Westcoast Transmission headquarters, has become an architectural icon of Vancouver. With support of the City of Vancouver, the historically significant building was converted in 2005 to 180 unique residential suites in studio, one and two bedroom configurations. The suspension concept was selected to provide an unobstructed view to the beautiful bay of Vancouver. According to the Bogue Babicki, the suspension option was also more economical than a conventional alternative they had considered. The suspended structure, sitting 30 feet (9 m) above grade provided unobstructed views at ground level to the beautiful bay of Vancouver. The tower is supported by a site-cast concrete core, 36 feet (11 m) square. The floors are suspended by 12 cables. Each cable consists of two 2 7/8" (73 mm) diameter strands. The sloping guy cables have two additional 2 1/2" (64 mm) diameter strands (the 45 degree slope increased their vector force by 1.414).

Size:	108x108 feet (33 x33 m)
Core size:	36x 36 feet (11x11 m))
Height	12 stories, 224' (68 m)
Typical story height:	12 feet (3.65 m)
Core height/width ratio:	6.2

- 1 Section
- 2 Exploded axon
- 3 Floor framing




BMW Headquarters Munich (1972)

Architect: Karl Schwanzer

Engineer: Helmut Bomhard

The Viennese architect Karl Schwanzer won the international design competition for the BMW tower with his idea to represent the automobile company in form of a four-cylinder engine. Four cylinders are suspended from an assembly of four semi-cylindrical concrete cores by means of hangers, suspended from a concrete cores of stairs, elevators, etc. The core extends as four cylinders on top of the floor stacks. Each floor is supported by a hanger at its center and stabilized by the core. To keep differential deflection within acceptable limits, the tower is partitioned into two stacks of eleven and seven office floors of the lower and upper stacks, respectively. Eight elevators, stairs and services are located in the core. Except for the four central hangers, the office space around the core is free from columns to provide highly flexible office areas. Construction of the tower started with the central core in conventional method; but then proceeded from top down. Post-tensioned concrete floor plates, cast on the ground, where lifted up by hydraulic means; starting with the top floor, followed by successive floors downward. Silver gladding exterior conveys a sophisticated high-tech image, true to the BMW philosophy.

Size:	52,30 m (172 feet) diameter
Core size	24.4 m (80 feet)
Height:	18 suspended stories, 101 m (331 feet)
Typical Story height:	3.82 m (10.8 feet)
Core height/width ratio:	4.1




Standard Bank Center, Johannesburg (1968)

Architect: Hentrich and Petschnigg

Engineer: Ove Arup and Partners

The Standard Bank Center is located in the financial center of Johannesburg. Given the dense surroundings, the design objective was to access the center via an open plaza with the least amount of bulk and obstructions. The response to this objective was a suspended structure. The central support core only at ground level, kept the plaza level open for free and spacious access. The suspension system also facilitated construction at the dense urban surrounding. After the central core was built, floors were suspended from three cantilevers. To limit differential deflection, the building is organized into three stacks of nine office floors each, suspended from concrete cantilever beams of 18 feet (5.4 m) depth. The cantilever beams are attached to the outside face of the concrete core by shear connection. The cantilever floors house the mechanical equipment and transformer stations. Basement floors for computer rooms and parking provide stability for the central core.

Floor size:	112x112 feet (34.29x34.28 m)
Core size:	48x48 feet (14.63x14.63 m)
Building height:	27 stories, 456 feet (139 m)
Core height:	520 feet (158.5 m)
Core height/width ratio:	10.8



Hon Kong and Shanghai Bank (1986)


Architect: Norman Foster

Engineer: Ove Arup

The design of the Hong Kong and Shanghai Bank emerged from a competition among seven invited architects. Foster's winning scheme is a suspension system intended to provide large public space at ground level without interior columns. The large floor area of 55x70m (180'x230') is supported by 8 Vierendeel towers, each consisting of four round columns spaced 5.1x4.8 m (17'x16') and connected at each level with tapered beams. The floors are suspended from twin suspension trusses which span the towers and cantilever from them on both sides to support service modules and exit stairs. A large floor area of 33.6x55 m (110'x180') between the towers are disrupted by only eight hangers, an additional benefit of the suspension scheme, besides the open ground floor. The space between two-story high suspension trusses serves as focal point of each stack of floors, as reception, conference and dining areas and lead to open recreation terraces with dramatic views of Hong Kong.



The maximum mast pipe diameter is 1400 mm (55"0 and 100 mm (3.9") thick


The maximum hanger pipe diameter is 400 mm (16") and 60 mm (2.4") thick



The suspension trusses and X-bracing perpendicular to them are also intended as belt trusses to reduce drift under lateral load. However, since the Vierendeel towers are moment resistant, the belt trusses are less effective than they would in conjunction with truss towers.

Size:	55x70m (180'x230')
Tower axis distance	38 m (126')
Height	35 floors, 180 m (590')
Typical story height:	3.9 m (12.8')
Height/width ratio:	4.7





Federal Reserve Bank, Minneapolis (1972)

Architect: Gunnar Birkerts

Engineer: Skilling, Helle, Christiansen, Robertson

The Federal Reserve Bank features a structure similar to suspension bridges. The floors are suspended from parabolic "cables". However, the "cables" are actually wide-flange steel sections of parabolic curvature to balance the distributed floor loads. A major reason to suspend the building from two towers, was to keep the bank vaults located below grade free of columns. Wide flange parabolic suspenders of 37 inch (944mm) span 328 feet (100m) between two concrete towers. Trusses on top of the towers resist the lateral thrust of the parabolic suspenders. Floors above the suspenders are supported by compression columns, whereas those below are suspended by tension hangers. The façade treatment reflects the compressive and tensile support zones by different recess of the glass line with respect to curtain wall mullions. Floor construction of concrete slabs rests on steel trusses that span the 60 feet (18m) width without interior columns.

Size:	335x60 feet (102x18 m)
Span between towers	275 feet (84 m)
Height	220 feet (67 m)
Typical story height	12.5 feet (3.8 m)
Height/width ratio:	3.7

Part V

MATERIAL

Part V explores the effect of material on structures. Material determines the physical properties and details of a structure. The most important physical properties are strength, stiffness, and ductility, as well as workability and isotropy. Physical properties also effect geometric properties, i.e., linear elements, surface elements, and bulk elements, such as beams, walls, and footings, respectively.

Physical properties of materials are important for selection and design. Steel has the highest compressive strength and stiffness, followed by concrete, masonry, and wood. In tensile strength too, steel is first, followed by wood. However, tensile strength of wood normal to grain is very small, but usually not relevant. Tensile strength of un-reinforced concrete and masonry is below 10% of respective compressive strength and is zero once cracks develop. However, reinforced concrete and masonry can assume tensile forces. Steel also has the highest shear strength, but shear strength in concrete, masonry, and wood parallel to grain is less than ten percent of the respective compressive strength. Isotropy, is also an important criteria for design. An isotropic material has the same properties in all directions. Steel is an isotropic material. So is concrete without reinforcing; but reinforced concrete and masonry are both not isotropic. Wood is also not isotropic, with very different properties parallel and normal to grain. Material properties effect the response to natural forces, like earthquake, fire, and wind. Seismic acceleration forces increase with mass. Steel, wood, and plastics are good for earthquakes, given their relative light weight. Ductility to absorbs seismic energy is another bonus for steel: By contrast, concrete and masonry are heavy and brittle, a double negative in earthquakes. Although proper reinforcement can provide ductility for concrete, it does not reduce weight. However, the weight of concrete and masonry is good in areas of strong winds to resist wind uplift. Further, concrete and masonry are most effective to resist fire.

Geometric properties define line, surface, and bulk elements. Wood and steel are primarily linear like posts, beams or steel frames; but some surface products such as plywood and metal decks are also available. Un-reinforced concrete is good for bulk and surface elements, like walls and domes in compression only, so is un-reinforced masonry. With reinforcing, concrete can be linear as well, like beams and moment frames. Reinforced masonry, too, can make linear elements, such as posts; though very slender masonry posts may seem unstable and inappropriate.

The workability of material defines how structures are build. Tough steel is fabricated in a shop and assembled in the field. Softer wood is easy to work and usually build in the field. Concrete can be site cast or precast in a plant for site assembly. It is a versatile material that can assume many shapes, limited only by formwork. Masonry is usually build up on the site from small bricks or concrete blocks with mortar and steel reinforcing. Masonry may also be veneer attached to other material.

20


Wood

Material

Wood is the only renewable building material. To use it in an ecologically responsible way, new plantings should replace harvested trees to replenish forests. Wood is a popular building material, not only because it is renewable and organic, but for other qualities too. Its natural texture, lively pattern, and warm color convey a genuine connection to nature. Fresh wood also has a pleasant fragrance and aging wood can develop a natural patina. Wood is easy to work with by hand or machine tools. Two generic types of wood are hardwood and softwood. Hardwood comes from broad-leaf deciduous trees. It is rarely used as structural material, but popular for furniture, finish wood work, and floors. Ash, beech, oak, and teak are examples of hardwood. Softwood comes from evergreen trees with needles. Douglas fir, hemlock, larch, pine, and redwood are softwood commonly used in building structures.

Structural wood, commonly called lumber, comes from tree trunks that support the crown and supply nutrition. Most tree cells are longer in trunk direction and arranged in circular year rings, representing fast and slow growth in spring and summer, respectively. Fast growth spring wood is softer and appears lighter than slow growth summer wood. Wood has good structural qualities, notably high strength to weight ratio and good resilience. However, wood is not isotropic since its properties vary with fiber orientation. Compared with allowable compressive stress parallel to fibers, perpendicular compressive stress is less than 50% and perpendicular tensile stress less than 1%, shear stress parallel to fibers is less than 10%.

With only about half the density of water, most structural wood has the lightest weight of common building materials. Wood is an ideal material to resist earthquakes, since seismic acceleration forces are proportional to mass. Wood's small mass yields small seismic forces; its resilience absorbs seismic energy like a tree or flower with little or no damage. However, the light weight of wood is a disadvantage under wind conditions. Wind uplift on a roof can be greater than the roof's dead weight and could blow it off in a strong storm. The light weight of wood, though favorable for earthquakes, is a liability under wind load. As a combustible material, wood also is susceptible to fire hazards. Light wood members require fire protection, usually by fire resistant sheathing of Type X gypsum board or stucco; heavy timber as defined by code can resist fire up to one hour by protecting itself with a charred layer caused by initial burning. To qualify as fire rated, heavy timber members must have the following minimum nominal dimensions: Roof beams 4x6; roof columns 6x8, floor beams 6x10, and floor columns 8x8.



Heavy timber







Timber structures evolved from ancient traditions of building shelter. Post and beam structures are a common type of timber structure. Post and beam systems without any extra measures are collapse mechanisms with little capacity to resist lateral wind or seismic load. Some means, such as bracing or shear walls, to resist lateral loads are common in timber structures. Shear walls usually serve also as space enclosures or dividers. Bracing may consist of wood struts, steel rods or cables. Moment connections to resist lateral loads are difficult to achieve in wood, for initially tight bolted connections get loose when wood shrinks over time. Shear walls or bracing in at least two bays in each direction assure symmetry of resistance.

The means to join post and beam is very important in wood since the grain direction is a critical factor to consider. For example, a beam supported on its top fibers only could split due to tensile stress perpendicular to grain. Joining a single beam to columns requires connecting devices, but twin beams require only bolts to connect to the column.

Closely spaced beams, 8 ft at roofs and 5 ft at floors, can support planks directly. For wider beam spacing, floor or roof decks require intermediary joists that result in a mix of light weight and heavy timber structure.

Timber structures provide more flexibility than rib structures, described in the next section, because the grid of posts is less intrusive than bearing walls. Timber structures usually have exposed wood that requires more careful craftsmanship than rib structures with walls covered by sheathing.

- A Joists provide intermediary support for floor or roof deck
- B Planks directly supported on beams
- C Single beams require some device to connect them to column
- D Twin beams bolted to column, allow pipes, etc. to pass between
- E Post
- F Cross-bracing resists lateral wind and seismic load



Post, beam, and joist connection

There are several ways to join post and beam, all are variations of three generic options: Flush connection of beam to column, twin beam to single column connection, and single beam to split column connection.

Two generic joist-to-beam connections are: Flush support with joists joined to side of beam; and top support with joists supported on top of beam.

Post to beam connections

1,2 Flush connection of single beam and post

Complex connections require metal joist- and beam-hangers
Vertical and horizontal ducts and pipes cannot pass between beams

3,4 Twin beam and single post

Twin beams have the same strength as a single beam of equal area
Simple bolted connection of twin beams to post
Ducts and pipes can easily pass between twin beams

5,6 Single beam and split column

Split posts have less buckling strength than a single post of equal area
Simple bolted connection of single beam to split posts

Joist to beam connections

1,2 Flush support joins beam and joist with flush top;

Requires metal joist hangers to support joists;
Is more labor intensive to install;
Provides narrow, less redundant, joist support;
Has slightly shorter joists;
Conceals the beam within the depth of joists;
Prevents ducts and pipes to pass between joists over beam;
Has reduced overall floor height


3-6 Top support is simpler, with joist supported on top of beam;

Needs only toe nails but no other hardware for connection;
Is less labor intensive and simple to install
Provides wider support for additional seismic safety;
Requires slightly longer joists to overlap over the beam;
Exposes the beam below the ceiling;
Allows ducts and pipes to pass between joist over the beam;
Has greater overall floor height

Post cap and base

Post caps secure beam to post to prevent slippage under lateral load. Toe-nailing is insufficient, especially for freestanding posts without sheathing. The post base secures a post to foundation or other support, to avoid slippage under lateral load. To prevent moisture penetration, the post base should not be in direct contact with the foundation.


- 1 Post cap
- 2 Post cap alternate
- 3 T-post-beam connector
- 4 L-post-beam connector
- 5 Post base with u-strap
- 6 Post base alternate



Concealed post cap

Concealed connections of post to beam and post to base are available, but they require greater care for proper installation and are more expensive. The alignment of bolt holes in connector and wood is essential and requires skill and experience on part of the carpenter.


- 1 Split ring with bolt, for twin beams, conceals all but the bolt
- 2 Concealed T-connector with dowels
- 3 Concealed L-connector with dowels
- 4 Concealed post base with dowels



Beam anchor

Beams need firm support attachment to prevent slippage under lateral load. Seismic forces may unseat a beam with insufficient support attachment. Toe-nailing a beam to a plate is not sufficient for major loads.


- 1 Steel bracket bolted to beam, with anchor bolt into wall
- 2 Anchor bolt directly through beam into wall
- 3 Axon of same attachment as in 1 above
- 4 Axon of same attachment as in 2 above
- 5 Twin bracket bolted to beam, with twin anchor bolts into wall
- 6 Concealed T-bracket, pinned to beam, with wall anchor bolts welded to bracket




Beam support

Beams supported on top of girders has the advantage that ducts and pipes can pass over girders between beams. However, flush support reduces floor-to-floor height.

- 1 Beam hanger with single flange
- 2 Beam hanger with twin flange
- 3 Heavy-duty twin beam hanger
- 4 Heavy-duty single beam hanger
- 5 Concealed beam hanger
- 6 Angle brackets to secure beam to wall plate





Grid structures

Two light wood structure types developed in the United States, *balloon framing* and *platform framing*. Platform framing is in wide use today.


Balloon framing

The inventor of balloon framing, George Washington Snow, a civil engineer, moved to Chicago in 1832 when it was a small village. St. Mary's Church, built in 1833, was the first building with balloon framing. The name *balloon framing* was initially a pejorative term, used by Snow's critics to make fun of its light weight. Today, platform framing, which evolved from balloon framing, replaced it in large part. However balloon framing has less vertical shrinkage than platform framing which is an advantage in case of applied veneer.

Standard balloon framing has wall studs, nominally 2x4, spaced 16 in on center, that extend over the full building height. Blocking between studs at each level provide fire stops. Plywood or other sheathing, nailed to studs, resists lateral wind and seismic load. Floor joists, also spaced 16 in on center, span between walls, supported by 1x4 ribbons let into the studs. Depending on span length, joist sizes range from nominally 2x6 to 2x12. Plywood, nailed to joists, provides floor and roof decks. Blocking between joists resists rotation and supports plywood panel edges to transfer shear from panel to panel. Blocking doubles the allowable shear in plywood diaphragms.

Studs are 2x6 for unsupported heights above 14 ft or for increased thermal insulation. Thermal insulation fits into spaces between studs, joists, and rafters, along with electrical wiring, small ducts and pipes. Joist spacing is 16, 12, or 24 in. Standard sheathing panels of plywood and gypsum board are 48 in wide to concur with 2, 3, or 4 joist spaces of 24, 16, or 12 in, respectively.

- A Joist spaced 16", 12 or 24"
- B Blocking under plywood panel edges
- C Double plates allow corners and splices to overlap for continuity
- D Stud, 2x6, spaced 16" or 24"
- E Fire blocking between floors
- F Ribbon, 1x4, let into studs to support joists
- G Anchor bolt, 1/2", spaced maximum 4'
- H Sole plate, min. 6" above soil
- I Concrete foundation




Platform framing

Platform framing evolved from previously described *balloon framing* and has replaced it in large part in contemporary construction. Given its versatility, low cost, and ease of construction, platform framing is very popular for low-rise residential structures in the United States.


Standard platform framing has nominally 2x4 (5x10 cm) wall studs, spaced 16 in (41 cm) on center, extending from platform to platform, joined by a sole plate at the base and double plates on top. The double plates allow overlap at splices and corners to provide continuity. Plywood sheathing, nailed to studs, resists lateral wind and seismic loads. Floor joists, also spaced 16 in, span between walls. Depending on span length, joist sizes range from nominally 2x6 to 2x12. Plywood, nailed to joists, provides floor and roof decks (platforms). Blocking between joists resists rotation and supports plywood panel edges to transfer shear from panel to panel. Blocking doubles the allowable shear in plywood diaphragms.

Studs are 2x4 (2x6 for heights above 14 ft or for increased thermal insulation). Thermal insulation fits into spaces between studs, joists, and rafters, along with electrical wiring, small ducts and pipes. Joist spacing may also be 12 or 24 in. Standard sheathing panels of plywood and gypsum board are 48 in wide to concur with 2, 3, or 4 joist spaces of 24, 16, or 12 in, respectively.


- A Joist spaced 16", alternately 12 or 24"
- B Blocking under plywood panel edges
- C Double plates allow corners and splices to overlap for continuity
- D Stud, 2x4, alternately 2x6 or 3x4; spaced 16" alternately 24" o. c.
- E Sole plate
- F Double plates overlap at corners and splices for continuity
- G Anchor bolt, 1/2", spaced maximum 4"
- H Sole plate, min. 6" above soil
- I Concrete foundation




1




2




3



4



5



6

Joist support

Beams may support joists two ways, flush support and top support.


Flush support (beam and joist with flush top)

- Requires metal joist hangers
- Is more labor intensive to install
- Provides narrow joist support
- Has shorter joists
- Conceals beam within depth of joists
- Prevents ducts and pipes to pass between joists over beam
- Reduces story height

Top support (joist rest on top of beam)

- Needs no connecting hardware
- Is less labor intensive and simple to install
- Provides wider support and better safety
- Requires slightly longer joists to overlap over the beam
- Exposes the beam below the ceiling
- Allows ducts and pipes to pass between joist over the beam
- Increases story height

- 1 Flush support with joist hanger
- 2 Flush support with joist hanger on steel beam with wood ledger
- 3 Flush support with double flange joist hanger
- 4 Hybrid support on wood ledger on steel beam
- 5 Top support overlapped on wood beam
- 6 Top support overlapped on steel beam with wood ledger



Fire and sound rating

Some aspects of fire and sound rating have important structural implications. Fire ratings define the time a structure retains its integrity while exposed to fire. Codes require fire rating for buildings based on floor area, occupancy and type of construction. Fire rated walls may also separate large buildings into smaller areas considered separate buildings. For light-weight wood structures a layer of 5/8 in Type X gypsum board on each side of the wall provides one hour fire rating. A second layer on each side provides two-hour fire rating. Fire rating of floors requires, in addition to gypsum board on the ceiling, light-weight concrete or thick floor plywood.

Sound rating provides privacy in party walls and floors separating adjacent apartments, condominiums, or offices. The *Impact Insulation Class (IIC)* for floors and *Sound Transmission Class (STC)* for both floors and walls define sound ratings. IIC and STC ratings of 50 are the typical minimum standard for party floors and walls. However, quality construction requires IIC and STC ratings of at least 60. To offset electric outlets on both sides of a party wall by one stud space is essential for the integrity of sound rated walls; so is the elimination of plumbing pipes in party walls. A continuous sound gap in plywood floors prevents floor sound to telegraph from unit to unit. Yet the sound gap breaks the structural integrity of the floor diaphragm. A plate, bridging the gap and nailed to both sides of the plywood gap can re-establish structural continuity of the plywood diaphragm.

- 1 One hour fire rated wall
 - 2 Two-hour fire rated wall
 - 3 One hour fire rated floor
 - 4 Two-hour fire rated floor
 - 5 Sound rated wall of about 60 STC
 - 6 Sound rated floor of about 60 IIC and 60 STC
- A Wall studs.
 - B Gypsum board, 5/8" type X (fire rated)
 - C Gypsum board, 2 layers 5/8" type X each side
 - D Cellular concrete, 1.5"
 - E Plywood sub-floor, minimum 5/8"
 - F Joists
 - G Plywood sub floor, 1"
 - H Gypsum boards, 2 layers 5/8" type X (type x is fire rated)
 - I Resilient furring channels, spaced 24"
 - J Double studs with minimum 1" sound gap
 - K Glass fiber insulation
 - L Cellular concrete, 1.5" with carpet and pad floor
 - M Plate to transfer shear over sound gap in plywood
 - N Sound gap in plywood to prevent sound transmission

23

Concrete

Material




Concrete is a versatile material that can be molded into many forms. It was first known in ancient Rome. Quarrying limestone for mortar, the Romans discovered that burning the limestone mixed with silica and alumina yields a cement stronger and more adhesive than ordinary lime mortar. The new material also could be used for underwater construction. Mixing the cement with sand and other materials, the Roman's invented the first concrete and used it widely in their construction, often filled between masonry.

The technology of concrete construction was lost with the fall of the Roman empire. Only toward the end of the eighteenth century did British inventors experiment to develop concrete again. In 1825, Joseph Aspdin patented *Portland cement* which he named after Portland limestone of similar color. The material was soon in wide use and the name Portland cement is still common today. It consists of lime, silica, and alumina, burned to clinkers in a furnace at about 3000° F (1650° C), and then crushed to a fine powder.

Concrete, consisting of cement, sand, and gravel mixed with water, is strong in compression, but very weak in tension and shear. Thus, concrete by itself is limited to applications subject to compressive stress only. This limit was soon recognized and by 1850 several inventors experimented with adding reinforcing steel to concrete. In 1867 the French gardener, Joseph Monier, obtained a patent for flower pots made of reinforced concrete. He went on to build water tanks and even bridges of reinforced concrete. Monier is credited to invent reinforced concrete..

As any material, concrete has advantages and disadvantages. Concrete ingredients are widely available and rather inexpensive. Concrete combines high compressive strength with good corrosion and abrasion resistance. It is incombustible and can be molded in many forms and shapes. Concrete's main disadvantage is its weakness in resisting tension and shear. Steel reinforcing needed to absorb tensile stress can be expensive. Concrete has no form by itself and requires formwork that also adds much to its cost. The heavy weight of concrete yields high seismic forces but is good to resist wind uplift. Concrete is inherently brittle with little capacity to dissipate seismic energy. However, concrete frames with ductile reinforcing can dissipate seismic energy. The inherent fire resistance of concrete is an obvious advantage in some applications.

Today, concrete serves many applications usually with reinforcing. In buildings, concrete is used for items like footings and retaining walls, paving, walls, floors, and roofs. Concrete is also used for moment resistant frames, arches, folded plates and shells. Apart from buildings, many civil engineering structures such as dams, bridges, highways, tunnels, and power plants are of concrete.



Concrete properties




Normal concrete has compressive strengths of 2 to 6 ksi (14 to 41 MPa) and high strength concrete up to 19 ksi (131 MPa). Low-strength concrete is used for foundations. Concrete strength is determined by the water-cement ratio (usually 0.6) and the cement-sand-gravel ratio (usually 1-2-3). Specified compressive strength of concrete f'_c , usually reached after 28 days, defines concrete strength. By the *strength method* (ultimate strength method) a structure is designed to 85% of the specified compressive strength f'_c with factored loads as safety factor. By the *working stress method*, a structure is designed to allowable stress, i.e., a fraction of the specified compressive strength f'_c .

Allowable concrete stress for working stress method

Compressive bending stress	$0.45 f'_c$
Bearing stress (full area):	$0.25 f'_c$
Bearing stress (1/3 area):	$0.375 f'_c$
Shear stress without reinforcing:	
beam	$1.1 f'_c^{1/2}$
joist	$1.2 f'_c^{1/2}$
footing and slab	$2.0 f'_c^{1/2}$
Shear stress, with reinforcing:	$5 f'_c^{1/2}$
Elastic modulus (w = concrete density in pcf):	$w^{1.5} 33 f'_c^{1/2}$

Temperature increase causes expansion of concrete defined by the thermal coefficient $\alpha = 5.5 \times 10^{-6}$ in/in/°F (3.1×10^{-6} m/m/°C). Hence, concrete slabs need temperature reinforcing to prevent cracks due to uneven expansion. Concrete also has creep deformation over time, mostly during the first year. Concrete shrinks about 1.3% due to loss of moisture, notably during curing. The temperature reinforcing helps to reduce shrinkage cracks as well. Density of concrete is determined by the type of aggregate. Light-weight concrete weighs about 100 pcf (1602 kg/m³). Normal concrete 145 pcf (2323 kg/m³) without reinforcing and 150 pcf (2403 kg/m³) with reinforcing. Concrete has good fire resistance if reinforcing steel is covered sufficiently. A 8 in (20 cm) wall has 4 hours and a 4 in (10 cm) wall 2 hours fire resistance.

- 1 Stress-strain curves for concrete
 - 2 Concrete creep (deflection with time)
 - 3 Concrete strength increase with time as percentage of 28-day strength
- A Point defining line of E-module on curve
 - B Elastic limit of idealized line for working stress method
 - C Idealized line for strength method
 - D Actual stress-strain curve
 - E Elastic modulus, defined as the slope from 0 to $0.5 f'_c$
 - ϵ Unit strain, in/in (m/m)
 - F Unit creep strain, in/in (m/m)
 - G Days after pouring concrete



Cement comes in bags of 1 ft³ (.028 m³), classified by ASTM-C150 as:

- Type I Normal cement (for most general concrete)
- Type II Moderate resistance to sulfate attack
- Type III High early strength
- Type IV Low heat (minimizes heat in mass concrete, like dams)
- Type V High resistance to sulfate attack

Types IA, IIA, IIIA correspond to I, II, III, but include air-entraining additives for improved workability and frost resistance.

Water must be clean, free of organic material, alkali, oil, and sulfate. The water-cement ratio defines the strength and workability of concrete. Low water content yields high strength, but is difficult to work. Typical water ratios are 0.4 to 0.6, verified by a *slump test*. For this test, a metal cone is filled with concrete and tamped. Lifting the cone slumps the concrete to under 3 in (7 cm) for foundations and walls, and 4 in (10 cm) for columns and beams.


Aggregate should be clean and free of organic material. Fine aggregate (sand) is less than 1/4 in (6 mm). Coarse aggregate (gravel or crushed rock) is used in normal concrete. Lightweight concrete has aggregate of shale, slate, or slag. Perlite and Vermiculite are aggregates for insulating concrete.

Admixtures are substances added to concrete to modify its properties:

- Air entrained agents improve workability and frost resistance
- Accelerators reduce the curing time and increase early strength
- Retarders slow the curing and allow more time to work the concrete
- Plasticizers improve the workability of concrete
- Colors and pigments add colors to concrete

Curing of concrete is a process of hydration until it reaches its full strength. Although this process may take several months, the design strength is reached after 28 days. During the curing process the concrete should remain moist. Premature drying results in reduced strength. Exposed concrete surfaces should be repeatedly sprayed with water or covered with a protective membrane during curing. This is most important in hot or windy climates. The curing process accelerates in hot temperatures and slows down in cold temperatures. Concrete shrinks about 2 % during curing. This may cause cracks. Synthetic fibers of 1/8 to 3/4 in (3 to 20 mm) are increasingly added to improve tensile strength and reduce cracking of concrete.

- 1 Concrete compressive strength defined by water-cement ratio
 - 2 Slump test: sheet metal cone and slumped concrete, C = slump
 - 3 Maximum aggregate sizes: 1/3 of slab, 1/5 of wall, 3/4 of bar spacing
- A Compressive strength of normal concrete
 - B Compressive strength of air entrained concrete
 - C Slump is the amount the wet concrete settles






Beam Reinforcement

Concrete beams require reinforcement for bending and shear in correlation with the respective stress patterns. This is illustrated for a simply supported beam under uniform load and for other beams on the next page.

Bending reinforcement is placed where the bending moment causes tensile stress. A simply supported beam under uniform gravity load deforms downward to generate compression on top and tension at the bottom. Thus, bending reinforcement is placed at the bottom. Beams with negative bending require tensile reinforcement on top. This is the case in beams with moment resistant supports, cantilever beams, and beams continuing over three or more supports. Some beams may require additional bars at mid-span or over supports to resist increased bending moment. Beams of limited depth also require compressive reinforcement to make up for insufficient concrete. Some reinforcement bars have hooks at both ends to anchor them to the concrete if the bond length between steel and concrete is insufficient. Deformed bars usually don't need hooks, given sufficient bond length. Temperature reinforcement continuous over the full length to resist stress caused by temperature variation and shrinkage during curing.

Shear reinforcement is placed where the shear stress exceeds the shear strength of concrete which is very small compared to compressive strength. Beams under uniform gravity load have maximum shear at supports which decreases to zero at mid-span. Thus, shear reinforcement in form of *stirrups* is closely spaced near the supports and spacing increases toward mid-span. Stirrups are usually vertical for convenience, though combined horizontal and vertical shear stresses generate diagonal tension which may cause diagonal cracks near the supports. Small longitudinal bars on top of a beam tie the stirrups together.

- 1 Shear diagram: maximum shear at supports and zero at mid-span
 - 2 Isostatic or principal stress lines: diagonal tension, dotted, near support
 - 3 Side view of beam with reinforcement
 - 4 Three-D view of beam with reinforcement
- A Bottom steel bars resist tensile stress
 B Stirrups resist shear stress which, for uniform load, is maximum at the supports and zero at mid-span



Waffle slab

Waffle slabs are two-way systems for medium spans where flat slabs or plates would be too deep and too heavy. They reduce dead weight by two-way ribs to eliminate excess weight between the ribs. The tensile steel for positive bending is placed at the bottom of ribs and the rib top and slab resist compressive stress. Since negative bending reverses the stress, waffle slabs are not efficient as cantilever with negative bending. Given the relative narrow spacing of ribs, minimum slab depth is determined not by its span/depth ratio, but by rebar size plus concrete cover. Waffle slabs need either solid panels on top of columns to resist shear stress or require intermediate beams. Waffle slabs are formed placing re-usable prefabricated pans of plastic or steel over a grid of wood boards.

Waffle slabs may be designed by the previously described *Direct Design Method* like a flat slab on columns but with reduced dead load due to ribs.

Waffle slab dimensions:

Span/depth ratio $L/d = 16-32$ (d = waffle depth)

Maximum span 60' (m); 70' (m) when prestressed


Slab depth 2.5" to 4.5" (6 to 11 cm)

Total depth 10" to 24" (25 to 60 cm)

Rib width 5" to 8" (13 to 20 cm)

Waffle size 2' to 5' (60 to 150 cm)

- 1 Waffle slab with a single solid panel over columns
- 2 Waffle slab with four solid panels over columns
- 3 Waffle slab supported by beams




Prestressed concrete

The effect of prestress on concrete is to minimize cracks, reduce depth and dead weight, or increase the span. Analogy with a non-prestressed beam clarifies this effect. In a simply supported non-prestressed beam the bottom rebars elongate in tension and concrete cracks due to tensile weakness. In prestressed concrete *tendons* (high-strength steel strands) replace rebars. The tendons are pulled against concrete to compress it before service load is applied. Service load increases the tension in tendons and reduces the initial concrete compression. Avoiding tensile stress in concrete avoids cracks that may cause corrosion in rebars due to moisture. Further, prestress tendons can take the form of bending moments that balances the service load to minimize deflection. This, combined with higher strength concrete of about 6000 psi (40 MPa), allows for longer span or reduced depth in beams.

Pre-tensioning and *post-tensioning* are two methods to prestress concrete. They are based on patents by Doebling (1886) and Jackson (1888); yet both were unsuccessful due to insufficient stress that dissipated by creep. Doebling stressed wires before casting the concrete, and Jackson used turnbuckles to stress iron rods after the concrete had cured. Subsequent experiments by others led to the first successful empirical work by Wettstein in 1921 and the first theoretical study by French engineer Eugene Freyssinet during 1920, followed by his practical development. In 1961 the US engineer T Y Lin pioneered prestress tendons that follow the bending diagram to balance bending due to load. Lin's method controls deflections for any desired load, usually dead load and about half the live load. By his method, before live load is applied a beam (or slab) bows upward. Under full load, they deflect and under partial live load they remain flat. Diagram 5 illustrates this for a simply supported beam.






- 1 Simply supported beam without prestress, cracked at tensile zone
 - 2 Prestress beam with **concentric** tendon deflects under service load
 - 3 Prestress beam with **eccentric** tendon pushes up without service load
 - 4 Same beam as 3 above with service load balanced at max. mid-span moment but not elsewhere since tendon eccentricity is constant
 - 5 Prestress beam with parabolic tendon to balance bending moment
- A Bending stress: top concrete compression and bottom steel tension
 - B Prestress uniform due to concentric tendon
 - C Prestress with greater compression near tendon at bottom
 - D Prestress for eccentric tendon: bottom compression and top tension (tension where tendon is outside beam's inner third (*Kern*). Simply supported beam of zero end moments has concentric tendon at ends
 - E Service load stress: top compression and bottom tension
 - F Combined stress from prestress and service load
 - G Combined stress with uniform distribution due to balanced moments



Tendons are high strength steel strands used in prestressed concrete. They have a breaking strength of 270 ksi (1860 MPa) and are composed of 7 wires, six of them laid helically around a central wire. Tendons come in sizes of 0.5 and 0.6 in (13 and 15 mm) diameter. Both sizes are used in post-tensioned concrete but only small tendons are used in pre-tensioned concrete which requires no bond length. The great strength of tendons allows initial stress levels high enough to make up for loss of stress due to creep, most notably during initial curing.

Post-tensioning begins by placing of metal or plastic tubes that house the prestress tendons prior to the pouring of concrete. Some tendons come enclosed in the tubes, but most are inserted after concrete has cured. Tubes prevent tendons to bond with the concrete to allow free movement for subsequent prestress operation. Once concrete has reached sufficient strength, the tendons are prestressed using hydraulic jacks that press against concrete to transfer prestress into it. Short members have tension applied at one end only but long members may require tension at both ends to overcome friction. Several devices are available to anchor the ends of post-tensioned tendons into concrete. One such device is a conical wedge that holds tendons by mechanical friction between the tendon and a rough surface of the device. Post-tensioning is usually done at the building site. It allows tendons to take any form desired to balance bending moments induced by service load.


- 1 Tendon cross section.
- 2 Conical tendon lock rests against steel sleeve (not shown) inserted into concrete and squeezes the tendon and hold it by friction
- 3 Beam with straight eccentric tendon below neutral axis
- 4 Parabolic tendon emulate bending moment to reduce deflection
- 5 Multiple parabolic tendons with offset anchors
- 6 Continuous beam with tendons emulating bending moment distribution
- 7 Continuous slab with tendons emulating bending moment distribution



Pre-tensioning stresses tendons between abutments in a concrete precasting plant. Once concrete has sufficient strength (with the help of steam in about 24 hours) tendons are cut off at the abutments to transfer prestress into the concrete. After cut off, tendons are anchored by friction with the concrete at both ends. Since abutments are difficult to secure at construction sites, pre-tensioning is usually done in a precast plant. Similar pieces may be laid in a row and cast together requiring only two abutments per row. Pre-tensioning is simplest with straight tendons, but some approximate curves that emulate bending moments are possible. They require temporary tie-downs to be cut off along with tendons after curing is complete.

Pre-tensioned members must be carefully handled during transportation to avoid damage or breakage. Since the reinforcement is designed for a given load direction, any reversed load may result in overstress and possible breakage. To avoid this they must be placed on the truck in the same position as in their final installation. Also, to avoid breakage of corners, it is advisable to provide corners with chamfers.

- 1 Beam with tendons anchored to abutments
 - 2 Beam with tendons cut off to transfer prestress into concrete after it has reached sufficient strength
 - 3 Beam with tendon tie-down to approximate bending moment curves
 - 4 Row of pre-tensioned members with tendon anchors at ends only
For members like walls and columns with possible bending in any direction, tendons may be placed at the center
 - 5 Row of pre-tensioned beams with tendon tie-down to approximate bending moments of service loads
- A Close approximation of parabolic bending moment by tendon shape
B Temporary tendon tie-downs to approximate bending moments are cut off after tendons are cut from abutments



Precast concrete

Precast concrete comes in a wide variety of shapes for both structural and architectural applications. Presented are structural systems and members: floor and roof members, columns, and walls. Though precast members may be of ordinary concrete, structural precast concrete is usually prestressed. The primary reinforcement of prestressed concrete is with tendons, yet normal rebars are often used as stirrups to resist shear. Rebars are also added for different loads during transportation and erection. Compared to site-cast concrete, precast concrete provides better quality control, repeated use of formwork, faster curing with steam, and concurrent operations while other site work proceeds. The advantages must offset the cost of transportation to a construction site. Precast concrete is similar to steel framing by allowing preparatory site work to be concurrent, yet it has the advantage to provide inherent fire resistance. Steel on the other hand, has lower dead weight, an advantage for seismic load that is proportional to dead weight. To reduce high costs of formwork the number of different precast members should also be reduced; yet this objective must be balanced by other considerations. For example, fewer parts may result in a monotone and uninspired design. Combining precast with site-cast concrete may satisfy economy as well as aesthetic objectives.

Precast framing allows many variations, both with and without site-cast concrete. A few typical examples are presented. They are possible with columns of several stories, limited primarily by transportation restrictions. The capacity of available cranes could also impose limitations. In such cases, columns should be spliced near mid-height between floors where bending moments from both gravity and lateral loads are zero.

- 1 T-columns with deep spandrel beams support floor and roof slabs. Shear connections between adjacent beams combine them to moment frames to resist lateral as well as gravity loads
- 2 Frames of split columns and deep spandrel beams support floor and roof slabs for gravity and lateral loads. Shear connections at adjacent split columns tie the frames together for unified action
- 3 T-columns with normal spandrel beams support floor and roof rib slabs. Shear connections between adjacent beams combine them to moment frames to resist lateral as well as gravity loads
- 4 Tree-columns with beam supports allow flexible expansion. Twin beams allow passage of services between them. Lateral load resistance must be provided by shear walls or other bracing
- 5 Rib slab or double T's supported on site-cast frame
- 6 U-channels with intermittent skylights supported on site-cast frame

24

Fabric and Cables

Material

Tent membranes have been around since ancient history, notably in nomadic societies. However, contemporary membrane structures have only evolved in the last forty years. Structural membranes may be of fabric or cable nets. Initial contemporary membrane structures consisted of

- Natural canvass for small spans
- Cable nets for large spans

Industrial fabric of sufficient strength and durability was not available prior to 1970.. Contemporary membrane structures usually consist of synthetic fabric with edge cables or other boundaries. Cables and fabric are briefly described.

Fabric for contemporary structures consists of synthetic fibers that are woven into bands and then coated or laminated with a protective film

Common fabrics include:

- Polyester fabric with PVC coating
- Glass fiber fabric with PTFE coating
- Glass fiber fabric with silicon coating
- Fine mesh fabric, laminated with PTFE film

Fabric properties are tabulated on the next page. Foils included are only for very short spans due to low tensile strength. Unfortunately the elastic modulus of fabric is no longer provided by fabric manufacturers, though it is required for design and manufacture of fabric structures. The elastic modulus of fabric is in the range of:

E = 2000 lb/in, 11492 kPa/m to

E = 6000 lb/in, 34475 kPa/m

Cables may be single strands or multiple strand wire ropes as shown on following pages.

Cables consist of steel wires, protected by one of the following corrosion resistance:

- Zinc coating (most common)
- Hot-dip galvanizing
- Stainless steel (expensive)
- Plastic coating (used at our cable nets at Expo64 Lausanne)

Depending on corrosion protection needs, zinc coating comes in four grades: type A, type B (double type A), type C (triple type A), type D (four times type A). Cables are usually prestressed during manufacture to increase their stiffness.

Elastic modulus of cables:

E = 20,000 ksi, 137900 MPa	(wire rope)
E = 23,000 ksi, 158,585 MPa	(strand > 2.5 inch diameter)
E = 24,000 ksi, 165,480 MPa	(strand < 2.5 inch diameter)

Fabric

Type	Makeup	Common use	Tensile strength
Coated fabric*	Polyester fabric PVC coating	Permanent + mobile Internal + external	40 to 200 kN/m 228 to 1142 lb/in
Coated fabric*	Glass fiber fabric PTFE coating	Permanent Internal + external	20 to 160 kN/m 114 to 914 lb/in
Coated fabric	Glass fiber fabric Silicone coating	Permanent Internal + external	20 to 100 kN/m 114 to 571 lb/in
Laminated fabric*	Fine mesh fabric Laminated with PTFE film	Permanent Internal + external	50 to 100 kN/m 286 to 571 lb/in
Foil	PVC foil	Permanent internal Temporary external	6 to 40 kN/m 34 to 228 lb/in
Foil*	Flouropolymer foil ETFE	Permanent Internal + external	6 to 12 kN/m 34 to 69 lb/in
Coated or uncoated fabric*	PTFE fabric (good qualities for sustainability)	Permanent + mobile Internal + external	40 to 100 kN/m 228 to 571 lb/in
Coated or uncoated fabric*	Flouropolymer fabric	Permanent + mobile Internal + external	8 to 20 kN/m 46 to 114 lb/in

* Self-cleaning properties

SI-to-US unit conversion:

1 kPa/m = 5.71 lb/in

Fire rating ++ incombustible + low flammability 0 none	UV light resistance ++ very good + good	Translucency	Durability
+	+	0 to 25 %	15 to 20 years
++	++	4 to 22 %	> 25 years
++	++	10 to 20 %	> 20 years
++	++	35 to 55 %	> 25 years
0	+	Up to 90 %	15 to 20 years internally
++	++	Up to 96 %	> 25 years
++	++	15 to 40 %	> 25 years
++	++	Up to 90 %	> 25 years

Maximum fabric span*

Tensile strength	Maximum span
500 lb/in	60 ft
1000 lb/in	120 ft

* Assuming:

Live load = 20 psf, 956 Pa (wind or snow)

Safety factor = 4

Fabric span/sag ratio = 10

Cables

Cables may be of two basic types and many variations thereof. The two basic types are strands and wire ropes.

Strands have a minimum of six wires twisted helically around a central wire. Strands have greater stiffness, but wire ropes are more flexible. To limit deformation, strands are usually used for cable stayed and suspension structures.

Wire ropes consist of six strands twisted helically around a central strand. They are used where flexibility is desired, such as for elevator cables.



Metallic area, the net area without air space between wires, defines the cable strength and stiffness. Relative to the gross cross section area, the metallic area is about: 70% for strands and 60% for wire ropes. To provide extra flexibility, some wire ropes have central cores of plastic or other fibers which further reduces the metallic area.


- 1 Strand (good stiffness, low flexibility)
E = 22,000 to 24,000 ksi; 70% metallic
- 2 Wire rope (good flexibility, low stiffness)
E = 12,000 to 20,000 ksi; 60% metallic

Cable fittings

Cable fitting for strands and wire ropes may be of two basic types: adjustable and fixed. Adjustable fittings allow to adjust the length or to introduce prestress by shortening. The amount of adjustment varies from a few inch to about four feet

- 3 Bridge Socket (adjustable)
 - 4 Open Socket (non-adjustable)
 - 5 Wedged Socket (adjustable)
 - 6 Anchor Stud (adjustable)
- A Support elements
B Socket / stud
C Strand or wire rope






1

2

1 Cable-to-cable connection with integral strand fitting

2 Cable-to-cable connection with wire rope thimble




3

4

3 Open socket connection, perpendicular
Trapezoidal gusset plate for synergy of form and reduced weld stress


4 Open socket connection, angled
Sloping gusset plate for synergy of form and uniform weld stress distribution




Mast / cable details

The mast detail demonstrates typical use of cable or strand sockets. A steel gusset plate usually provides the anchor for sockets. Equal angles A and B result in equal forces in strand and guy, respectively.

- A Mast / strand angle
- B Mast / guy angle
- C Strand
- D Guy
- E Sockets
- F Gusset plates
- G Bridge socket (to adjust prestress)
- H Foundation gusset (at strand and mast)
- I Mast



1



2

3



Production process

Fabric pattern

To assume surface curvature, fabric must be cut into patterns which usually involves the following steps:

- Develop a computer model of strips representing the fabric width plus seams
- Transform the computer model strips into a triangular grids
- Develop 3-D triangular grids into flat two-dimensional patterns

The steps are visualized as follows:

- 1 Computer model with fabric strips
- 2 Computer model with triangular grid
- 2 Fabric pattern developed from triangular grid

Pattern cutting

Cutting of patterns can be done manually or automatic.

The manual method requires drawing the computer plot on the fabric

The automatic method directs a cutting laser or knife from the computer plot

Note:

For radial patterns as shown at left, cutting two patterns from one strip, juxtaposing the wide and narrow ends, minimizes fabric waste.

Pattern joining

Fabric patterns are joined together by one of three methods:

- Welding (most common)
- Sewing
- Gluing

Edge cables

Unless other boundaries are used, edge cables are added, either embedded in fabric sleeves or attached by means of lacing.

Fabric panels

For very large structures the fabric may consist of panels that are assembled in the field, usually by lacing. Laced joints are covered with fabric strips for waterproofing.